Safe use of contrast media - part 2

Inhoudsopgave

Startpagina - Veilig gebruik van contrastmiddelen (deel 2)

Waar gaat deze richtlijn over?

Deze richtlijn beschrijft hoe contrastmiddel voor beeldvormend onderzoek veilig toegediend kan worden aan patiënten.

In de richtlijn wordt ingegaan op vier aspecten van het veilig toedienen van contrastmiddelen

1. Overgevoeligheidsreacties na contrasttoediening
2. Veilig gebruik van gadolinium houdende contrastmiddelen
3. Veilige injectie van contrastmiddelen via centrale catheters en ports
4. Contrastmiddel extravasatie

Voor wie is deze richtlijn bedoeld?

Deze richtlijn is bedoeld voor alle artsen, die werkzaam zijn in het ziekenhuis en die beeldvormend onderzoek, al dan niet met een interventie, met contrastmiddel aanvragen of uitvoeren.

Voor patiënten

Deze richtlijn beschrijft de zorg voor patiënten die een beeldvormend onderzoek krijgen, waarbij contrastmiddel wordt toegediend. De richtlijn is bedoeld voor volwassen (>18 jaar) patiënten. Het gaat om contrastmiddelen die via een infuus worden ingespoten in de bloedvaten voor röntgenonderzoek, vaatonderzoek of vaatbehandeling.

Wanneer contrastmiddel in de bloedvaten komt, kan een kleine groep patiënten overgevoelig reageren op het contrastmiddel. Deze richtlijn beschrijft hoe een dergelijke reactie moet worden behandeld. Er wordt ook beschreven wat voor voorzorgsmaatregeln patiënten moeten krijgen, wanneer zij eerder een overgevoeligheidsreactie na contrastmiddel hebben gehad, maar nu opnieuw onderzoek met een contrastmiddeln moeten krijgen.

Er wordt in de richtlijn ook aandacht besteed aan voorzorgsmaatregelen voor een speciaal type contrast dat voor MRI-scans wordt gebruikt: gadolinium houden contrast.

In de richtlijn wordt beschreven hoe contrastmiddelen veilig kunnen worden toegediend, wanneer een patiënt al een toegang tot de bloedvaten heeft, bijvoorbeeld een centrale catheter.

Tenslotte beschrijft deze richtlijn ook hoe patiënten moeten worden behandeld, wanneer er per ongeluk contrastmiddel buiten de bloedvaten terechtkomt.

- Thuisarts informatie wordt nog ontwikkeld

Hoe is de richtlijn tot stand gekomen?

De Nederlandse Vereniging voor Radiologie heeft een nieuwe set richtlijnen op het gebied van veiligheid van contrastmiddelen geprioriteerd als een belangrijk onderwerp van kwaliteitsbeleid. Reden hiertoe is dat er recentelijk veel onderzoeken zijn gepubliceerd op het gebied van veiligheid van het toedienen van contrastmiddelen. Het streven is om drie richtlijnen te publiceren over dit onderwerp, waarvan dit het tweede deel is.

Toepassen

Voor deze richtlijn zijn er strooomschema's ontwikkeld waarin wordt beschreven:

- hoe een acute overgevoeligheidsreactie na contrasttoediening moet worden behandeld
- hoe zorgverleners moeten handelen bij patiënten die eerder een overgevoeligheidsreactie na een contrastmiddelen hebben gehad, en bij wie nu opnieuw een beeldvormend onderzoek met contrastmiddel geïndiceerd is
- hoe contrastmiddelen veilig kunnen worden geïnjecteerd via centrale catheters en ports

Verantwoording

Laatst beoordeeld   : 24-06-2020
Laatst geautoriseerd : 24-06-2020

Voor de volledige verantwoording, evidence tabellen en eventuele aanverwante producten raadpleegt u de Richtlijnendatabase.

Management of acute hypersensitivity reactions

Uitgangsvraag

What is the optimal treatment for acute hypersensitivity reactions to contrast media?

Aanbeveling

Preparation:

- Have the drugs (as a minimum requirement: adrenaline, salbutamol, H1-antihistamine (clemastine) IV, and corticosteroid IV (for example prednisolone), equipment and protocol for treatment of an acute adverse reaction readily available in every room where contrast agents are administered.
- Adhere to local protocols for accessibility of a resuscitation and emergency response team.
- Keep every patient with an acute hypersensitivity reaction to CM in a medical environment for at least 30 minutes after contrast agent injection. Moderate and severe reactions need a prolonged observation.

Acute management general principles:

- Check and stabilize patient according to the ABCDE method.
- Stop infusing contrast agent and replace IV line with crystalloid.
- Dyspnoea or stridor: let patient sit up.
- Hypotension: keep patient in prone position, raise legs.
- Consider measuring serum tryptase (see recommendations in chapter Laboratory Diagnosis of Hypersensitivity Reactions to Contrast Media).
- Record acute allergic reactions in allergy registry (see chapter Organisation of Healthcare).

Note: After administration of clemastine the patient may no longer be able (or insured) to drive a car/motorcycle or to operate machinery.

<u>Severe reactions</u>
<u>Cardiac or respiratory arrest:</u>

- Start CPR.
- Call the CPR team.

<u>Anaphylactic reaction or stridor:</u>

- Call rapid response team (SIT-team).
- Give oxygen 10 to 15L/min with non-rebreathing mask.
- Give 0.5mg adrenaline IM in lateral upper thigh.
- Give fluid bolus of crystalloid 500ml IV in 10 minutes, repeat as necessary.
- Consider nebulizing salbutamol 5mg or budesonide 2mg for stridor.
- Give clemastine 2mg IV.
- Consider to add corticosteroid, for example prednisolone 50mg IV.

*Or equivalent dose of other corticosteroid.

50 mg prednisolone is equivalent to:

- 40 mg methylprednisolone.
- 8mg dexamethasone.
- 200mg hydrocortisone.

*Consider adding corticosteroids to prevent a biphasic or protracted anaphylactic reaction if initial symptoms are severe

Moderate reactions
Consider transferring the patient to a department with facilities for monitoring of vital functions.

Isolated bronchospasm:

- Salbutamol 2.5 to 5mg nebulization in oxygen by facemask 10 to 15 L/min (nebulization is easier to administer and more effective than dose aerosol).
- In mild cases asthma patients may use their own salbutamol dose aerosol.
- In case of deterioration give adrenaline 0.5mg IM and consider calling rapid response team.

Isolated facial oedema without stridor:

- Give oxygen 10 to 15L/min with non-rebreathing mask.
- Give clemastine 2mg IV.
- If oedema is severe or near airways or if stridor develops: treat as anaphylaxis.

Isolated urticaria/diffuse erythema:

- Give clemastine 2mg IV.
- If accompanied by hypotension: treat as anaphylaxis.

Isolated hypotension:

- Give bolus of crystalloid 500ml IV, repeat as necessary.
- If accompanied by bradycardia, consider atropine 0.5mg IV.
- If accompanied by other symptoms: treat as anaphylaxis.

Mild reactions
General:

- Mild reactions may only need reassurance.
- Observe vital signs until symptoms resolve.

- Do not remove IV access during observation.

Consider:

- Prescribing a non-sedating antihistamine, for example desloratadine 5mg PO (once daily) for mild allergic reactions.
- Ondansetron 4mg IV for protracted vomiting.

Also see the flowchart.

Overwegingen

As there are no comparative studies investigating the research question, the recommendations in this national guideline are based mainly on results of observational studies and reviews (for example Cohan, 1996; Bang, 2013; Morzycki, 2017; Boyd, 2017) and of the recommendations of the American College of Radiology 2018 (Manual on Contrast Media v10.3) (ACR, 2018), the European Society of Urogenital Radiology 2018 (electronic v10) (ESUR, 2018), the International Consensus On Drug Allergy 2014 (Demoly, 2014), the World Allergy Organisation (WAO) Anaphylaxis Guidelines 2011, update 2015 (Simons, 2015), the European Association for Allergy and Clinical Immunology (EAACI) Guidelines 2014 (Moraro, 2014), and adapted to the Dutch situation (Het Acute Boekje, NIV 2017).

Because of the diminished frequency of acute adverse reactions to contrast media, there are now fewer opportunities for physicians to recognize and appropriately treat such adverse reactions. Reactions vary from very mild itching to anaphylactic shock. These reactions are often unpredictable; they can happen to people who have not been exposed to contrast media in the past. A mild reaction may be self-limited but can also develop quickly into a severe reaction. When a hypersensitivity reaction to a contrast medium occurs, there may be insufficient time or opportunity to study the treatment protocols and medication doses. It is therefore important for personnel to be prepared for any adverse reaction, to have clear treatment guidelines, and to have access to a rapid response team in case of an emergency. (Segal, 2011).

Because of this diminished frequency and lack of experience in treatment, major guidelines recommend to restricting adrenaline injection in the hands of non-experienced users to intramuscular administration route only.

Risk factors
Patients with a history of previous moderate or severe acute hypersensitivity reaction to an iodine-based contrast medium or gadolinium-based or ultrasound contrast agent, asthma requiring medical treatment and atopy requiring medical treatment are at increased risk (ESUR 2018; ACR 2018).

Prevention
Use a low-osmolar or iso-osmolar non-ionic iodine-based contrast medium. In patients at risk consider an alternative test not requiring a contrast agent of similar class.

For previous contrast agent reactors: use a different contrast medium/agent, preferably after consultation with a specialist in drug allergy

The radiology department should be prepared for an acute reaction. This requires regular and optimized training of personnel. See Chapter: Organisation of healthcare.

Note:
Instead of adrenaline 1:1,000 ampules for IM administration each department may also opt for selecting the (more expensive) adrenaline 1:1,000 auto-injectors, for example EpiPen (Asch 2017).

Inleiding

Acute hypersensitivity reactions often create stress and confusion and appropriate training and clear protocols are advisable. In addition, depending on the location where a patient suffers an acute hypersensitivity reaction to contrast media, the available expertise of the personnel that cares for such a patient may differ. Similarly, the availability of equipment and drugs to treat a (possible serious) hypersensitivity (or anaphylactic) reaction will be different. In a radiology or cardiology department the possibilities are different (and usually more limited) than in a department of emergency medicine or on a hospital ward. In addition, different treatments will have variable modes of action. What is the most appropriate management of a patient with an acute hypersensitivity reaction to contrast media?

Samenvatting literatuur

Not applicable. There were no studies investigating the research question. The non-comparative studies are briefly described in the table below.

Table 1 Treatment effects of acute adverse reaction

Abbreviations: CM contrast media; CPR Cardio-Pulmonary Resuscitation; IV intravenous;

Reference	Total n (n men)	CM type	Acute reaction(s)	Treatment	Outcome	Remarks

Collins, 2009	9 (3)	LOCM or Gadolinium	Ranged from laryngeal oedema, hypotension, tachycardia, dyspnoea to hypoxia	All patients received epinephrine; seven 0.1 mg (recommended initial dose) and two 0.3mg. Oxygen, diphenhydramine, steroids	7/9 discharged in good condition on same day of CM administration 1/9 Intubation during transport to emergency department, admitted to ICU, discharged 5 days later in good condition 1/9 Full cardiac arrest; autopsy showed retroperitoneal haemorrhage as cause of death	4/9 patients had some form of cardiovascular side effects attributed to epinephrine (such as "chest tightness")
Wang, 2008	11 (3)	Non-ionic iodinated contrast media	Ranged from erythema, hypotension, tachycardia, unresponsiveness, arrhythmia, cardiopulmonary arrest, nausea, diaphoresis, rash, hypotension, semi-responsiveness, dizziness, gagging and difficulty speaking, bronchospasm, chest pain, generalized seizure to facial oedema	Ranged from CPR, 1 mg of epinephrine IV, 1 mg of atropine IV, 50 mEq of sodium bicarbonate, 1 g 10% calcium chloride, 10 L of O2 by face mask, normal saline, 50% dextrose, 50 mg of diphenhydramine IV, 100 mg of diphenhydramine to 120 mg of methylprednisolone	2/10 returned to their normal baseline conditions within 1 hour. 6/10 manifestations resolved completely within 24 hours, despite their severe symptoms and often extensive treatment. 2/10 sequelae lasting more than 24 hours 1 unknown outcome	Allergic-type reactions occurred in 545/84,928 (0.6%) of IV injections of nonionic iodinated contrast media in adults. 221 received treatment.

Power, 2016	85 (sex unknown)	Gadobutrol	81 mild allergic-like reactions: urticaria, rash, pruritus, limited erythema, Localized facial oedema, itchy eyes, scratchy throat, sneezing, coughing 3 moderate reactions: erythema over the anterior chest with dyspnoea, rash and soft palate swelling, pruritic rash and throat tightness 1 severe: breathing and swallowing	Half of the patient with mild reaction received treatment with oral diphenhydramine All patients with moderate reactions received treatment with diphenhydramine. 50-minute resuscitation effort	All patients were discharged	
Piscaglia, 2006	29 (sex unknown)	SonoVue	Ranged from dyspnoea, bronchospasm, slight hypotension and bradycardia, clouding of consciousness, lumbar pain, severe hypotension, cutaneous rash to paraesthesia at the upper limbs	IV corticosteroids, antihistamines, 1 g of hydrocortisone, lying down with both legs raised, lying down.	All patients recovered	

Zoeken en selecteren

To answer the clinical question a systematic literature analysis was performed.

P (Patient): patients with acute hypersensitivity reaction after contrast media administration;

I (Intervention): treatment, antihistamines, corticosteroids, epinephrine, adrenalin, dopamine, norepinephrine, noradrenalin, histamine H1 antagonists, histamine H2 antagonists, H1 antihistamines, H2 antihistamines, adrenergic beta-2 receptor agonists, glucocorticoids, management/treatment of hypersensitivity reactions/allergic reactions after contrast media, antihistamines, volume resuscitation, bronchodilators;
C (Comparison): conservative treatment or comparison of interventions mentioned above;
O (Outcomes): duration of acute reaction, severity of complaints, morbidity, mortality, costs, hospitalization in an IC-unit, length of stay.

Relevant outcome measures
The working group considered morbidity, mortality, and hospitalization in an IC-unit, critical outcome measures for the decision-making process, and duration of acute reaction, length of stay and costs important outcomes for the decision-making process.

Methods
The databases Medline (OVID) and Embase were searched from 1^s of January 1985 to 28th of December 2017 using relevant search terms for systematic reviews (SRs), randomized controlled trials (RCTs) and observational studies (OBS).

Search terms are shown under the Tab "Literature Search". The literature search procured 328 hits: 20 SR, 64 RCTs and 224 OBS. Based on title and abstract a total of 47 studies were selected. After examination of full text all studies were excluded, and no studies definitely included in the literature summary.

4 studies describing treatment effects of acute adverse reactions were found. Although these studies did not fulfil the search criteria, a short description is included in the literature summary, due to lack of other evidence. Since no control groups were available, no evidence tables or risk of bias tables or conclusions of these studies are included.

Verantwoording

Laatst beoordeeld   : 24-06-2020
Laatst geautoriseerd : 24-06-2020

Voor de volledige verantwoording, evidence tabellen en eventuele aanverwante producten raadpleegt u de Richtlijnendatabase.

Referenties

Acute boekje 2017. Een initiatief van de Nederlandse Internisten Vereniging. Available at: https://www.hetacuteboekje.nl/hoofdstuk/anafylaxie/anafylaxie.html. Accessed: 11 March 2019
American College of Radiology. ACR Manual on contrast media. V.10.3. Available at: https://www.acr.org/Clinical-Resources/Contrast-Manual. Accessed: 11 March 2019.
Asch D, Pfeifer KE, Arango J, Staib L, Cavallo J, Kirsch JD, Arici M, Pahade J. Benefit of epinephrine autoinjector for treatment of contrast reactions: comparison of errors, administration times, and provider preferences. AJR Am J Roentgenol 2017; 209: W363-W369.
Bang TJ, Suby-Long T, Borgstede JP, et al. University of Colorado radiologist adult contrast reaction smartcard. J Am Coll Radiol 2013; 10: 467-469.

Boyd B, Leder RA, Castillo M. Managing adverse reactions to contrast agents. Magn Reson Imaging Clin North Am 2017; 25: 737-742.

Cohan RL, Leder RA, Ellis JH. Treatment of adverse reactions to radiographic contrast media in adults. Radiol Clin North Am 1996; 34: 1055-1076.

Collins MS, Hunt CH, Hartman RP. Use of IV epinephrine for treatment of patients with contrast reactions: lessons learned from a 5-year experience. AJR Am J Roentgenol 2009; 192: 455-461.

Demoly P, Adkinson NF, Brockow K, et al. International Consensus on drug allergy. Allergy 2014; 69: 420-437.

ESUR Contrast Media Safety Committee. ESUR Guidelines on contrast safety, v10. Available at: www.esur-cm.org. Accessed: 17 February 2019.

Muraro A, Roberts G, Worm M, et al. Anaphylaxis: guidelines of the European Association of Allergy and Clinical Immunology. Allergy 2014; 69: 1026-1045.

Morzycki A, Bhatia A, Murphy KJ. Adverse reactions to contrast material: A Canadian update. Can Assoc Rad J 2017; 68: 167-193.

Piscaglia F, Bolondi L; Italian Society for Ultrasound in Medicine and Biology (SIUMB) Study Group on Ultrasound Contrast Agents. The safety of Sonovue in abdominal applications: retrospective analysis of 23,188 examinations. Ultrasound Med Biol 2006; 32: 1369-1275

Power S, Talbot N, Kucharczyk W, Mandell DM. Allergic-like Reactions to the MR Imaging Contrast Agent Gadobutrol: A Prospective Study of 32 991 Consecutive Injections. Radiology 2016; 281: 72-77.

Segal AJ, Bush Jr. WH. Avoidable errors in dealing with anaphylactoid reactions to contrast media. Invest Radiol 2011, 46: 147-151.

Simons FER, Ebisawa M, Sanchez-Borges M, et al. 2015 update of the evidence base: World Allergy Organization anaphylaxis guidelines. World Allergy Organization Journal 2015; 8:32.

Wang CL, Cohan RL, Ellis JH, Caoli EM, Wang G, Francis IR. Frequency, outcome and appropriateness of treatment of nonionic iodinated contrast media reactions. AJR Am J Roentgenol 2008; 191: 409-415.

Treatment of late reactions to contrast media

Uitgangsvraag

What is the optimal treatment for late hypersensitivity reactions to contrast media?

Aanbeveling

Warn patients who have had a previous hypersensitivity reaction to contrast media, that a late hypersensitivity reaction may be possible, usually a skin reaction.

Patients should contact their general practitioner if they have a late hypersensitivity reaction after CM administration.

Consider informing the radiology department about the occurrence and symptoms of a late hypersensitivity reaction after CM administration.

When the symptoms of a late hypersensitivity reaction are mild, a wait-and-see approach can be justified.

Treat late hypersensitivity reactions symptomatically.

Consider treatment of skin reactions with oral or topical corticosteroids.

When severe symptoms develop, such as generalized pustulosis or painful cutaneous blisters, refer the patient to a dermatologist.

Overwegingen

There are no solid data on different management strategies of late hypersensitivity reactions to CM, especially no studies with a control group.

In many patients there are nonspecific symptoms, such as headache, nausea, dizziness, gastro-intestinal upset, mild fever and arm pain (Bellin, 2011; Christiansen, 2000; Egbert, 2014). Skin rashes with erythema and swelling and headache are the most frequent true late hypersensitivity reactions or symptoms (loh, 2010). Most rashes are macular or maculopapular exanthemas, which usually occurs 2-10 days after first exposure to CM and 1 to 2 days after re-exposure to the same CM. Most reactions are mild to moderate in severity, are usually self-limiting and resolve within 1 week.

Treatment is symptomatic, based on the type of reaction presented. More than 90% of the late hypersensitivity reactions involve the skin only. Usually oral antihistamines and topical corticosteroid crèmes or emollients treat these late skin reactions.. Antipyretics may be given for fever, and anti-emetics for nausea or GI symptoms.

Very rarely the patient may develop a severe reaction with generalized pustulosis or blistering of the skin, for which specialized dermatology care needs to be sought (Egbert, 2014).

It seems therefore to be rational to follow the recommendations from the ESUR v10 guideline (Bellin, 2011; ESUR, 2018) and/or the ACR Manual on Contrast Media v10.3 (ACR 2018)

Inleiding

Late (non-immediate) adverse reactions are heterogeneous. Because of the self-limiting character of most cutaneous adverse reactions to CM, the traditional mainstay of treatments follows that of cutaneous adverse reactions to other drugs: withdrawal of the drug and preventative measures for reuse of them, combined with symptomatic treatment.

Severe cutaneous reactions such as Stevens-Johnson syndrome (SJS), toxic epidermal necrolysis (TEN), acute generalized exanthematous pustulosis (AGEP), and drug reaction with eosinophilia and systemic symptoms (DRESS) may warrant specific therapeutic interventions by a dermatologist.

Samenvatting literatuur

Not applicable. There were no studies investigating the research question.

Zoeken en selecteren

To answer the clinical question a systematic literature analysis was performed.

P (Patients): patients with late hypersensitivity reaction after contrast media administration;
I (Intervention): diagnosis, treatment, management, steroid, cyclosporine, topical, emollients;
C (Comparison): conservative treatment or comparison of interventions above;
O (Outcomes): recovery, course, outcome, sequels, mortality, morbidity hospitalization.

Relevant outcome measures
The working group considered mortality and recovery critical outcome measures for the decision making process and course, sequel, morbidity and hospitalisation important outcomes for the decision making process.

Methods
The databases Medline (OVID), Embase and the Cochrane Library were searched from 1^{st} of January 1985 to 3^{th} of January 2018 using relevant search terms for systematic reviews (SRs), randomized controlled trials (RCTs) and observational studies (OBS). Search terms are shown under the Tab "Literature Search". The literature search procured 480 hits: 11 SR, 72 RCTs and 336 OBS. Based on title and abstract a total of 12 studies were selected. After examination of full text all studies were excluded and 0 studies definitely included in the literature summary.

Verantwoording

Laatst beoordeeld   : 24-06-2020
Laatst geautoriseerd : 24-06-2020

Voor de volledige verantwoording, evidence tabellen en eventuele aanverwante producten raadpleegt u de Richtlijnendatabase.

Referenties

American College of Radiology. ACR Manual of contrast media, v10.3. Available at: https://www.acr.org/Clinical-Resources/Contrast-Manual. Accessed: 11 July 2019.

Bellin MF, Stacul F, Webb JAW, et al. Late adverse reactions to iodine-based contrast media – an update. Eur Radiol 2011; 21: 2305-2310.

Christiansen C, Pichler WJ, Skotland T. Delayed allergy-like reactions to X-ray contrast media: mechanistic considerations. Eur Radiol 2000; 10: 1965-1975.

Egbert RE, De Cecco CN, Schoepf UJ, McQuiston AD, Meinel FG, Katzberg RW., Delayed adverse reactions to the parenteral administration of iodinated contrast media. AJR Am J Roentgenol 2014; 203: 1163-1170.

ESUR Contrast Media Safety Committee. ESUR Guidelines on contrast safety, v10. Available at: http://www.esur-cm.org. Accessed: 11 july 2019.

Loh S, Bagheri S, Katzberg RW, Fung MA, Li CS. Delayed adverse reaction to contrast-enhanced CT: a prospective single-center study comparison to control group without enhancement. Radiology 2010; 255:764–771.

Laboratory tests in patients with hypersensitivity reaction to contrast media

Uitgangsvraag

What is the diagnostic value of serum and/or urine testing for contrast media induced hypersensitivity reactions?

Sub questions

1. What is the diagnostic value of tryptase and/or urine (methyl-histamine, methyl-imidazolacetic acid) measurement at the time of the hypersensitivity reaction?
2. What is the diagnostic value of follow-up examination of serum (tryptase) and/or urine (methyl-histamine, methyl-imidazolacetic acid) in order to estimate the risk for a hypersensitivity reaction in the future?
3. What is the diagnostic value of the basophil activation test with contrast media?

Aanbeveling

Do not perform a Basophil Activation Test routinely in all patients with a history of hypersensitivity reactions receiving contrast medium.

Measure serum tryptase between 1 to 2 hours from the start of all moderately severe to severe acute hypersensitivity reactions to contrast media.

When tryptase is elevated, refer the patient to a drug allergy specialist.

Overwegingen

Basophil Activation Test
Although no literature was found that answered the search question, a number of studies provide indirect evidence, which will be further discussed here.

Böhm (2011) described that plasma histamine and basophil degranulation using CD63 expression and flow cytometry in blood samples of patients receiving iotrolan (n=12) or iopromide (n=19) injections were analysed before and up to 24 hours after CM injection. In 5 of 12 and 5 of 19 resp. a significant activation of basophils could be measured. No relation with clinical parameters was reported.

Philipse (2012) described a case report where a 28-year old female patient experienced an anaphylactic shock immediately after administration of iomeprol. The reaction was documented by clinical parameters and by an elevation of serum tryptase. Iomeprol induced a dose-dependent CD63 elevation on blood basophils. No activation was shown after stimulation with iohexol and iopromide. CD63 expression on basophils incubated with iomeprol in five controls individuals remained unchanged.

Salas (2013) described a cohort study in which patients with symptoms suggestive of an immediate hypersensitivity reaction to radio contrast media were evaluated with skin tests and a drug provocation test. If skin tests or drug provocation tests were positive a BAT was carried out with the same test panel as used for skin tests. 62.5% of patients considered positive either from skin test or drug provocation test had a positive

BAT. The authors suggested that the BAT test could contribute to diagnostic efficacy in patients with hypersensitivity reactions to contrast media. Chirumbolo (2013) responded to the above-mentioned publication (Salas, 2013) that the usefulness of a BAT test is limited due to technical problems in the laboratory and the possibility of delayed reactions to radio contrast media that are likely not to be detected in the BAT test.

Pinnobphun (2011) described a cohort study in which BAT tests were performed in 26 patients with immediate RCM (three different media) reactions and in 43 specimens from healthy volunteers. CD63 and CCR3 positive basophils were analysed by flow cytometry. The BAT test yielded a significantly higher percentage of activated basophils in patients than in normal controls. Both the percentage of activated basophils and the stimulation index had acceptable discrimination powers to diagnose RCM hypersensitivity according to the authors. The specificity of the test ranged from 88.4 to 100%, an ROC curve showed an area under the curve value of 0.79.

Trcka (2008) evaluated 96 patients with anaphylaxis symptoms after contrast media application. In 4 patients (anaphylaxis grade 2 or3) skin test and basophil activation tests suggested an IgE mediated allergy to contrast materials according to the authors. (iopromide, iomeprol, iopentol) Two patients were subsequently treated with an alternative compound that was well tolerated. CD63 and IgE double positive cells assessed the basophil activation. A positive response was dependant on an analysis of more than 5% activated basophils, provided a stimulation index equal or higher than 2.

Kolenda (2017) evaluated the value of BAT and skin test for the diagnosis of RCM hypersensitivity. Thirty-three patients had responded to an injection of GBCA during MRI. Skin test were performed according to EAACI–ENDA guidelines. BAT was performed using the Allergenicity kit (Beckman Coulter). Gadobenate, gadoteric acid and gadobutrol were analysed in three tenfold dilutions. Patients were considered as 'non allergic' when their skin tests were negative whereas they were considered 'allergic' when the skin tests were positive with an evocative clinical history. CD 203C expression induced in more than 6% of the basophil cells was considered as a positive response. In 13 of the 14 non-allergic patients the BAT was negative, corresponding to a specificity of 93%. When re-exposed five of 14 patients tolerated the culprit drug confirming the 'non-allergic' nature of the primary reaction. In the 'allergic' population BAT was positive in 13 of 19 for the pulled GBCA, sensitivity of 68%.

In conclusion:
To date four clinical studies, a case report and a mechanistic study have been published concerning application of the BAT in patients with hypersensitivity reactions to contrast media. Based on 3 studies two review articles concluded that: the literature demonstrated a sensitivity of 46 to 63% and specificity is of 89 to 100% (Mangodt, 2015; Steiner, 2016). This conclusion however bypasses heterogeneity in laboratory techniques, control groups and agents involved. It should be noted that these estimates of sensitivity and specificity were based on a low percentage of clinical reactors as were identified as hypersensitive by skin test or drug provocation tests. However, in the recent study of Kolenda almost half of the patients that had responded with symptoms within minutes after GBCA injections had positive skin tests (performed according the EAACI–ENDA guidelines). In these patients a high specificity and relatively high sensitivity was found.

Based on the earlier three studies, performing the BAT test in all patients with a history of hypersensitivity reactions to contrast media would probably only identify a very low percentage as 'allergic'. However recent

studies report a higher percentage of skin test positive patients. The diagnostic value of both skin testing and the BAT are dependent on studies with adequate power and an objective outcome parameter such as a graded dose challenge.

Serum Tryptase
Although no literature was found that answered the search question, a number of studies provide indirect evidence, which will be further discussed here.

Zhai (2017) described a cohort study in 27 adult patients presenting with at least a grade 2 immediate reaction after intravenous injection of ICM during CT. Blood samples were evaluated with multiple parameters. Tryptase levels were significantly elevated as compared to a control group of healthy adults

Clement (2018) reported a cohort study in 245 patients with a history of hypersensitivity who were skin tested, of whom 41 were identified as 'allergic' to iodinated agents and 10 to gadolinium based ones. Histamine and tryptase concentrations increased with the severity of the reaction.

Comment (2014) described a cohort study where in the realm of forensic pathology beta tryptase measurements for diagnostic purposes were performed in post-mortem serum obtained from femoral blood in 94 patient with different fatalities, among others death following contrast material administration (six cases). Values over 11.4 ng/mL were systematically identified in serum and pericardial fluid following contrast material anaphylaxis and in six cases unrelated to anaphylaxis.
Fellinger (2014) described that a cohort of 15298 individuals was tested for basal tryptase levels. Elevated serum tryptase (> 11.4 ng/mL, mean 20+/- 21 ng/mL) as a predictor of anaphylaxis was evaluated in 900 patients and compared to 900 patients with normal tryptase values. Elevated tryptase levels were significantly associated with adverse reactions to drugs, radio contrast media and insect sting reactions. Anaphylaxis was more common in patients with elevated tryptase levels.

Srivastava (2014) reported a systemic retrospective survey that was carried out in 171 individuals whose data were extracted from the emergency department and specialist allergy clinic records. Thirty-four patients had a grade 1 anaphylaxis reaction, 61 a grade 2 reaction, 27 a grade 3 reaction and six patients a grade 4 reaction. 24 patients could not be graded due to lack of adequate clinical details, 6 patients developed a biphasic response. 50% of cases were diagnosed with idiopathic systemic anaphylaxis and 28% triggered by drugs, foods, and other allergies. Serial tryptase measurements were not available in 117 of the cohort. A weak positive correlation was detected between acute serum tryptase and severity.

Palmiere (2014) performed a retrospective literature analysis on risk factors of causes of anaphylaxis due to contrast media. Moreover, fatal cases investigated in the author's own institution was evaluated. Only a minority of fatal cases had been previously exposed to contrast compounds. In eight cases with fatal anaphylaxis, post-mortem serum tryptase concentrations ranged from 51 to 979 ng/mL.

In conclusion:
Tryptase is the principal protein component of human mast cell secretory granules.
It was shown to be a marker of mast cell degranulation that is released together with histamine. Detecting

elevated levels of tryptase following a suspected hypersensitivity reaction may help to establish the final diagnosis of anaphylaxis. Tryptase levels peak at 0.5 to 1.5 hours and thereafter rapidly decline with a 1.5-2.5 hours half-life (Schwartz, 2006).

The ESUR guidelines suggest that: blood samples for tryptase are taken following suspected anaphylaxis, so that the diagnosis can be established. The minimum recommendation is one sample 1 to 2 hours after the reaction point. Ideally three samples should be obtained, the first one once this visitation is underway the second at 1 to 2 hours after the reaction and the third at 24 hours or during convalescence (ESUR v10)

An elevated level of tryptase is also a hallmark of systemic mastocytosis. Systemic mastocytosis is a risk factor for developing hypersensitivity reactions to multiple agents such as insect venom and drugs that tend to cause mast cell degranulation (ESUR v10). Contrast agents, notably iodinated products, may per se cause some extent of mast cell and/or basophil degranulation. However, the risk of modern contrast agents in mastocytosis seems to be limited (Hermans, 2017). Moreover, since mastocytosis is a rare disease, routine determination of tryptase does not seem warranted, notably not when other signs and symptoms of mastocytosis are absent (urticaria pigmentosa, osteoporosis at early age, insect sting and/or unexplained anaphylactic reactions).

When confronted with a patient responding with a presumed hypersensitivity reaction to infusion of contrast media the first care of course should be for the safety of the patient. However, once the patient is stabilized care should be taken that clinical parameters are documented according to standard procedures. These procedures include exact documentation of infusion materials, medication taken by the patient or given during the procedure and clinical parameters such as such as blood pressure, heart rate, oxygen saturation, auscultation of the lungs, inspection of the oral cavity and of the skin of the patient.

The signs and symptoms of hypersensitivity reactions are not always clear-cut or may be misleading initially. Therefore, objective documentation is sought for. Tryptase is a readily available marker for mast cell/basophil activation; serum levels are normally less than 11.5 ng/mL. Other studies have proposed a somewhat higher cut-off value (14 ng/mL). Elevated levels of serum tryptase occur in both anaphylactic and anaphylactoid (non IgE-mediated) reactions, but a negative test does not fully exclude anaphylaxis. Basal tryptase levels over 20 µg/L are suggestive of systemic mastocytosis. The utility of serum tryptase for the diagnosis of anaphylaxis has been published in the context of the NICE quality standard anaphylaxis 2016 (NICE QS119).

Serum tests in patients suspected of having experienced hypersensitivity reactions to contrast media in the past
Conclusions:
Laboratory tests aimed at detecting specific antibodies can be performed by using skin tests and/or an in vitro basophil activation test (BAT) with the suspected compound. In many cases it is not clear to which compound the patient has reacted in the past. Both skin testing and the BAT test may help to select an agent for future safe use. However, the diagnostic accuracy of these methods still is insufficiently documented. The final evaluation of the diagnostic power of these tests is dependent on the comparison with a 'golden standard', probably the graded dose challenge.

Concerning the documentation of hypersensitivity reactions to contrast media (grade II and III) patients should be followed up with at least one sample for blood tryptase 1 to 2 hours after the reaction and one at a later time point (ESUR v10).

Testing of baseline levels of tryptase before contrast studies are performed may be useful in patients who have previously developed hypersensitivity reactions to contrast media. Elevated baseline levels of serum tryptase in a steady state situation suggest the presence of a mast cell disorder. Already mildly elevated baseline tryptase levels somewhat increase the risk of anaphylaxis (Fellinger). Indolent systemic mastocytosis (ISM) is considered a risk factor for contrast agent anaphylaxis, but a recent study did not confirm this (Hermans, 2017). ISM is the most frequent form of mast cell disorders; its prevalence in the Netherlands is suggested to be around 1 in 10,000.

Detection of serum tryptase is relatively cheap, routinely performed in many laboratories, serum samples can be stored at -20°C and normal values are well established. If elevated baseline tryptase values are found (>20 µg/L) a further haematological analysis should be performed including C-kit analysis to further specify the type of mast cell disease.

Given the low frequency of hypersensitivity reactions to contrast agents, the low frequency of mastocytosis in the population and the still insufficiently documented sensitivity and specificity of serum tests (incl. BAT), routine testing of all patients prior to injection of contrast agents is not warranted.

It is important to have local protocols that describe which physician is responsible for measuring the tryptase levels during and after a hypersensitivity reaction (see Chapter Organisation of healthcare).

Inleiding

Serum/blood tests can be performed prior to first contact with the agent, immediately after a reaction and after a possible hypersensitivity reaction in the past.

Hypersensitivity reactions to contrast media are described as acute (immediate) or late (delayed). Reactions occurring within one hour after application of the agents are coined as immediate, reactions occurring later are called delayed. As delayed reactions are considered to be caused by cell-mediated immunity, serum/blood tests so far are only considered relevant to confirm the diagnosis of immediate hypersensitivity. Specific diagnosis of delayed type hypersensitivity can be performed using patch tests and/or in vitro tests such as lymphocyte activation test or other laboratory techniques. The latter tests require specialized laboratories. In order to predict the risk of immediate hypersensitivity reactions serum tests could be aimed at detecting specific antibodies (IgE) to contrast media. In reality this has not been shown to be a realistic option, partly due to technical difficulties.

Moreover, for many years reactions to contrast media were considered as not IgE-driven, although occasionally evidence for an IgE mechanism has been put forward (Carr, 1984; Mita, 1998) In recent years however positive skin tests to contrast media in patients having experienced hypersensitivity reactions have suggested a much larger role for specific IgE, at least in some patients (Clement, 2018). It should be noted however that positive skin tests not necessarily imply an IgE mediated mechanism. The same goes for positive results of the basophil activation test (BAT). Although a positive result of this *in vitro* test usually indicates the presence of specific IgE,

it again does not exclude other activation modes of these blood cells. To date there is no commercially available test for directly detecting circulating IgE anti-bodies to contrast media. Application of the BAT to heparin stabilized blood samples of patients shows interesting results but its availability is limited to specialized laboratories. The technique is based on detection of activation of basophils with flow cytometry. CD63 expression serves as a unique marker of identifying activated cells. The technique requires a small amount of fresh blood, less than 0.1 mL. The CD63 marker is located to the same secretory granule that contains histamine, in principle also histamine production could be used as a marker of basophil activation, but determination of histamine is generally more cumbersome than detecting CD63 up regulation (Hoffmann, 2015). Serum tests can also be performed in order to detect a tendency to develop immediate hyper reactivity reactions in general. Serum beta-tryptase (*tryptase*) is an indicator of mast cell activity and can readily be measured in hospital routine laboratories. Serum histamine determination is unpractical because of its short half-life in circulation. An alternative is detection of histamine metabolites in urine. (*N-τ-Methylhistamine*). Although this is a reliable parameter (Keyzer, 1984) very few laboratories have this test in their routine repertoire, and there are not enough data available with respect to contrast media. So, this parameter is not further discussed.

Samenvatting literatuur

Not applicable. There were no studies investigating the research question.

Zoeken en selecteren

To answer our clinical question a systematic literature analysis was performed for the following research question:
What is the diagnostic value of *serum/blood* testing for contrast media induced hypersensitivity reactions?

P (Patients): patients with hypersensitivity reactions after undergoing radiological examinations with contrast media;
I (Intervention): serum tests: tryptase, Blood test, basophil activation test;
C (Comparison): Clinical diagnosis of hypersensitivity reaction after contrast administration / no serum tests;
R (Reference test): drug provocation test;
O (Outcomes): correctly confirmed diagnosis of hypersensitivity reaction to
contrast media (sensitivity, specificity, area under the curve, positive predictive value, negative predictive value).

<u>Relevant outcome measures</u>
The working group considered sensitivity and specificity critical outcome measures for the decision-making process; and considered the area under the curve and the positive and negative predictive values important outcome measures.

<u>Search and select (method)</u>
The databases Medline (OVID), Embase and the Cochrane Library were searched from January 1985 to 11th of January 2018 using relevant search terms for systematic reviews (SRs), randomized controlled trials (RCTs) and observational studies (OBS). The literature search resulted in 368 hits: 12 SRs, 17 RCTs and 339 OBS.

Studies were selected based on the following criteria:

- adult patients with hypersensitivity reaction to radio contrast media;
- evaluation of diagnostic properties of serum tests to Contrast Media;
- application of a provocation test to confirm results of cutaneous testing;
- reports predefined outcome measures: sensitivity, specificity, area under the curve, positive predictive value, negative predictive value;
- serum tests tryptase and urine-metabolites should be performed within 24 hours after hypersensitivity reaction;
- no reports of case series or exploratory findings (n≥10).

Based on title and abstract a total of 2 studies were selected. After examination of full text all studies were excluded. Reason for exclusion is reported in exclusion table.

After examination of full text all studies were excluded, and no studies definitely included in the literature summary.

Verantwoording

Laatst beoordeeld   : 24-06-2020
Laatst geautoriseerd : 24-06-2020

Voor de volledige verantwoording, evidence tabellen en eventuele aanverwante producten raadpleegt u de Richtlijnendatabase.

Referenties

Böhm I, Speck U, Schild HH. Pilot study on basophil activation induced by contrast media. Fundam Clin Pharmacol 2011; 25: 267-276.
Brockow A, et al. Skin test concentrations for systemically administered drugs - an ENDA-EAACI Drug Allergy Interest group position paper. Allergy 2013;68:702-712.
Carr DH, Walker AC. Contrast media reactions: experimental evidence against the allergy theory. Br J Radiol 1984; 57: 469-473.
Clement O, Dewachter P, Mouton-Faivre C, et al. Immediate hypersensitivity to contrast media: the 5-year French CIRTACI study. EClinicalMedicine 2018; 1: 51-61.
Comment L, Reggiani Bonetti L, Mangin P, Palmiere C. Measurement of β-tryptase in postmortem serum, pericardial fluid, urine and vitreous humor in the forensic setting. Forensic Sci Int 2014; 240: 29-33.
ESUR Contrast Media Safety Committee. ESUR Guidelines on contrast safety, v10. Available at: www.esur-cm.org. Accessed: 11 march 2019.
Fellinger C, Hemmer W, Wöhrl S, Sesztak-Greinecker G, Jarisch R, Wantke F. Clinical characteristics and risk profile of patients with elevated baseline tryptase. Allergol Immunopathol (Madr) 2014; 42: 544-552.
Hermans MAW, Arends NJT, Gerth van Wijk R, et al. Management around invasive procedures in mastocytosis: an update. Ann Allergy Asthma Immunol 2017; 119: 304-309.
Hoffman HJ, et al. The clinical utility of basophil activation testing in diagnosis and monitoring of allergic disease. Allergy 2015: 70;1393 – 1405.
Keyzer JJ, Udding H, De Vries K. Measurement of N-τ-Methylhistamine concentrations in urine as a parameter for histamine release by radiographic contrast media. Diagn Imag Clin Med 1984; 53: 67-72.

Kolenda C, Dubost R, Hacard F, et al. Evaluation of basophil activation test in the management of immediate hypersensitivity reactions to gadolinium-based contrast agents: a five-year experience. J Allergy Clin Immunol Pract 2017; 5: 846-849.

Mangodt, E. A., Van Gasse, A. L., Decuyper, I., et al. In vitro diagnosis of immediate drug hypersensitivity: should we go with the flow? International archives of allergy and immunology, (2015) 168(1), 3-12.

Mita H, Tadkoro K, Akiyama K. Detection of IgE antibody to a radio contrast medium, Allergy 1998 ;53: 1133-1140.

National Institute for Health and Care Excellence. NICE anaphylaxis quality standard (QS 119). London: NICE, 2016.

Palmiere C, Comment L, Mangin P. Allergic reactions following contrast material administration: nomenclature, classification, and mechanisms. Int J Legal Med 2014; 128: 95-103.

Philipse E, Sabato V, Bridts C, et al. Basophil activation in the diagnosis of life-threatening hypersensitivity reaction to iodinated contrast media: case report. Acta Clin Belg 2013; 68: 140-142.

Pinnobphun P, Buranapraditkun S, Kampitak T, Hirankarn N, Klaewsongkram J. The diagnostic value of basophil activation test in patients with an immediate hypersensitivity reaction to radiocontrast media. Ann Allergy Asthma Immunol 2011; 106: 387-393

Salas M, Gomez F, Fernandez TD, Doña I, Aranda A, Ariza A, et al. Diagnosis of immediate hypersensitivity reactions to contrast media. Allergy 2013; 68: 1203-1206.

Srivastava S, Huissoon AP, Barrett V, Hackett S, Dorrian S, Cooke MW, et al. Systemic reactions and anaphylaxis with an acute serum tryptase ≥14 µg/L: retrospective characterisation of aetiology, severity and adherence to National Institute of Health and Care Excellence (NICE) guidelines for serial tryptasemeasurements and specialist referral. J Clin Pathol 2014; 67; 614-619.

NICE guideline Anaphylaxis. Quality standard (QS119) Published date: March 2016, update aug. 2018.

Schwartz LB. Value of tryptase in anaphylaxis and mastocytosis. Immunol All Clin North Am 2006;26:451-63.

Srivastava S, Huissoon AP, Barrett V, Hackett S, Dorrian S, Cooke MW, et al. Systemic reactions and anaphylaxis with an acute serum tryptase ≥14 µg/L: retrospective characterisation of aetiology, severity and adherence to National Institute of Health and Care Excellence (NICE) guidelines for serial tryptase measurements and specialist referral. J Clin Pathol 2014; 67; 614-619

Steiner, M., Harrer, A., & Himly, M. Basophil reactivity as biomarker in immediate drug hypersensitivity reactions—potential and limitations. Frontiers in pharmacology, 2016. 7, 171.

Thomsen HS, Webb JAW (eds). Contrast Media: Safety Issues and ESUR Guidelines, 3rd edition. Heidelberg, Springer Verlag, 2014.

Trcka J, Schmidt C, Seitz CS, Brocker EB, Gross GE, Trautmann A. Anaphylaxis to iodinated contrast material: nonallergic hypersensitivity or IgE-mediated allergy ? AJR Am J Roentgenol 2008; 190: 666-670.

Zhai L, Guo X, Zhang H, et al. Non-ionic iodinated contrast media related immediate reactions: A mechanism study of 27 patients. Leg Med (Tokyo) 2017; 24: 56-62.

Diagnostic value of skin testing for hypersensitivity reactions to contrast media

Uitgangsvraag

What is the diagnostic value of skin testing for hypersensitivity reactions to contrast media?

Aanbeveling

Do not perform skin tests routinely after every hypersensitivity reaction to a contrast medium.

Refer the patient to a specialist in drug allergy to perform skin tests within 6 months after the hypersensitivity reaction in the following patient groups:

- Severe hypersensitivity reactions to a contrast medium.
- Hypersensitivity reactions with increased tryptase levels.
- Hypersensitivity reactions to 2 or more different contrast media of the same type (for example 2 different iodine-based CM) or to 2 or more types of contrast media (for example iodine-based CM and gadolinium-based CA).

Specify the used contrast agent in the referral.

Refer the patient to a specialist in drug allergy to perform skin tests in all patients with breakthrough hypersensitivity reactions despite premedication with corticosteroids and H1-antihistamines.

Overwegingen

As hypersensitivity reactions to CM have traditionally been classified as non-allergic reactions, skin tests have been regarded as inappropriate tools in patients having experienced such reactions. However, increasing evidence suggests that immunological mechanisms may be involved in CM-induced hypersensitivity reactions to a much larger degree, partly based on the positive skin tests in patients with both immediate and nonimmediate hypersensitivity reactions after CM exposure.

Implementing the results of skin tests might be a more valid alternative to prophylactic medication for prevention of the recurrence of CM reactions (Rosado Ingelmo, 2016). Skin tests have good sensitivity when performed within 6 months after the hypersensitivity reaction. After this time, sensitivity decreases. Therefor a speedy referral to a drug allergy specialist is recommended.

Few studies were found that met the inclusion criteria and were all with iodinated contrast media. Even though, no hard evidence is available on skin testing for gadolinium based CA, the hypersensitivity reactions are more often IgE-mediated in reactions after gadolinium-based CA and very similar in symptomatology to hypersensitivity reactions after iodine-based CM and therefore it seems logical to extend skin testing to hypersensitivity reactions to all CM (Clement, 2018).

Since included studies were considerable heterogeneous regarding to study setup and applied skin tests, no pooled outcomes of diagnostic test properties could be assessed which limits the recommendations that can be made on the current literature study.

If a previous reaction had shown a delayed cutaneous response it is unknown if premedication and or skin testing would reduce the risk of subsequent reactions. Delayed skin reactions may be life threatening notably when blistering has occurred. Skin testing in such cases may not be safe.

Performing and Reporting Skin Testing for Contrast Media

Most hospitals nowadays have contracts with just a few contrast media vendors. For skin testing of contrast media, however, it is important to test a panel of contrast agents (ICM and/or GBCA), including the culprit contrast agent and potential alternatives. Such a panel could be individualized for the specific hospital (group) where the patient comes from.

In order to facilitate establishment of such a local panel of iodine-based and gadolinium-based agents for allergologic skin testing, we have listed the available agents in The Netherlands and their indications below.

(See for physicochemical characteristics of GBCA also Table 1 in the Introduction to Safe Use of Gadolinium).

Table 2 Contrast agents in The Netherlands registered with the Medicine Evaluation Board

Iodine-based contrast media			
Name	*Commercial Name*	*Company*	*Main Indication*
Iopromide	Ultravist	Bayer Healthcare	Intravascular CT/Angio
Iopamidol	Iopamiro	Bracco Imaging	Intravascular CT/Angio
Iomeprol	Iomeron	Bracco Imaging	Intravascular CT/Angio
Iohexol	Omnipaque	GE Healthcare	Intravascular CT/Angio
Iodixanol	Visipaque	GE Healthcare	Intravascular CT/Angio
Ioversol	Optiray	Guerbet	Intravascular CT/Angio
Iobitridol	Xenetix	Guerbet	Intravascular CT/Angio
Amidotrizoate meglumine	Gastrografine	Bayer Healthcare	Gastrointestinal RF/CT
Iopamidol	Gastromiro	Bracco Imaging	Gastrointestinal RF/CT
Ioxithalamate meglumine	Telebrix Gastro	Guerbet	Gastrointestinal RF/CT

Gadolinium-based contrast agents			
Name	*Commercial Name*	*Company*	*Allowed Indication*
Gadobutrol	Gadovist	Bayer Healthcare	Total Body MRI
Gadoteridol	ProHance	Bracco Imaging	Total Body MRI
Gadoterate meglumine	Dotarem/Artirem	Guerbet	Total Body MRI
	Clariscan	GE Healthcare	Total Body MRI
	Dotagraf	Bayer Healthcare	Total Body MRI
Gadoxetate disodium	Primovist	Bayer Healthcare	Liver MRI
Gadobenate dimeglumine	MultiHance	Bracco Imaging	Liver MRI
Gadopentetate meglumine	Magnevist	Bayer Healthcare	MR Arthrography

See also: https://www.geneesmiddeleninformatiebank.nl/nl/

When reporting skin tests, it is optimal that the allergologist gives a clear written recommendation in the electronic patient dossier about:

1. The possible ICM and/or GBCA that can be used in future CM-enhanced studies
2. The use of or need for premedication in future CM-enhanced studies

Inleiding

Hypersensitivity reactions to contrast media (CM) have traditionally been classified as non-allergic reactions, and skin tests have been regarded as inappropriate tools in patients having experienced such reactions. However, during the last few years several investigators have reported positive skin tests in patients with both immediate and non-immediate hypersensitivity reactions after CM exposure, which indicates that immunological mechanisms may be involved much more frequently. In this chapter the diagnostic value of cutaneous tests for CM hypersensitivity reactions is assessed, which may serve as a more valid alternative to prophylactic medication for CM reactions. Furthermore, the working group evaluates whether these skin tests should be recommended in clinical practice, and under which conditions.

Conclusies

Acute Hypersensitivity Reactions: Negative Predictive value

Very Low GRADE	The negative predictive value of the cutaneous test is estimated to be 80 to 97%. The sensitivity and specificity for the cutaneous test for immediate hypersensitivity reaction to contrast media is unknown in patients suspected of contrast media hypersensitivity. *Sources: (Caimmi, 2010; Kim, 2013; Salas, 2013; Sesé, 2016)*

Late Hypersensitivity Reactions: Negative Predictive value

Very Low GRADE	The negative predictive value of the cutaneous test is estimated to be 65%. The sensitivity and specificity for the cutaneous test for non-immediate hypersensitivity reaction to contrast media is unknown in patients suspected of contrast media hypersensitivity. *Sources: (Torres, 2012)*

Samenvatting literatuur

1. Skin testing for acute (immediate) hypersensitivity reactions to contrast media
The diagnostic properties of cutaneous tests for acute (immediate) hypersensitivity reactions (HSR) to Contrast Media (CM) were evaluated in 4 studies (Caimmi, 2010; Kim, 2013; Salas, 2013; Sesé, 2016).

Caimmi (2010) studied 159 patients. Patients were tested with the culprit iodine-based contrast medium (ICM) and a set of other ICM if they were positive for the culprit ICM or if its name was unknown. In order to know which ICM was involved, either patients already knew which drug had supposedly caused the reaction and provided us the name, or we contacted the hospital in which the reaction had occurred. The ICM used were: amidotrizoate, ioxithalamate, iopamidol, iohexol, ioversol, iopromide, iomeprol, iobitridol, iodixanol and ioxaglate. Skin tests were performed firstly as prick tests with the undiluted commercially available solution and then, if negative, by intradermal tests (IDT) at a 1: 10 dilution. Prick tests were considered positive if, after 15 min, the size of the weal was at least 3 mm in diameter. For IDT, positivity was considered when the size of the initial weal increased by at least 3 mm in diameter after 15 to 20 min, considering as non-irritant a maximum dilution of 1/10. The negative predictive value was defined as the proportion of patients with negative skin test results to at least one ICM at first testing who had a further injection with that ICM without reacting. One hundred participated (75.5% participation rate). Seventy-one of them (5 9.2%) were females of a median age of 56 (45–65) years. The majority of the reactions were immediate (101 out of 120, 84.2%), and in two cases, it was not possible to assess whether the reaction was immediate or non-immediate. For immediate reactions, 42 (41.6%) were of grade 1, 34 (33.7%) of grade 2, 20 (19.8%) of grades 3 and five (4.9%) of grade 4. Only one (5.9%) of the 17 non-immediate reactions was moderate, all the others were mild (16 to 94.1%).

Kim (2013) retrospectively included 1048 patients. The mean (SD) age was 55.1 (14.5) years; 501 (47.8%) were male. Intradermal test with the RCM that was to be used in the
pending nonionic CM-enhanced CT was performed just before the CT examinations. The nonionic CM used in our contrast CT scans was iopromide, iomeprol, iohexol, and iodixanol. Intradermal tests were conducted on the volar surface of the forearm with a negative control, saline. A 1:10 solution of contrast medium (0.03 to 0.05 mL), which has been accepted as a non-irritating concentration, was gently injected into the skin to produce a small superficial bleb of 2 to 4 mm. Skin test positivity was determined when the diameter of the wheal increased by at least 3 mm, and surrounding erythema was observed after 15 to 20 minutes. If a patient had a negative response to skin tests, CT was performed as scheduled (provocation). Of the 376 patients previously exposed to CM, 61 (16.2%) had a history of at least 1 mild CM-associated reaction: 56 (91.8%) had immediate and 5 (8.2%) non-immediate reactions.

Salas (2013) included 90 patients with a history of immediate HSR after contrast media (CM). Immediate HSR was classified according to the Ring and Messmer scale.

Skin Test (ST) was carried out using the following CM: iobitridol, iomeprol, iodixanol, iohexol, ioversol, iopromide and ioxaglate. Prick tests were performed using undiluted CM and IDT using 10-fold dilutions. In those with a negative ST, a single-blind placebo-controlled provocation test was performed with the CM involved, as described. In patients with a positive ST and/or provocation test, a basophil activation test (BAT) was performed with iohexol (3; 0.3 mg/ml), iodixanol (3; 0.3 mg/ml), iomeprol (3.5; 0.35 mg/ml) and ioxaglate (5.8; 0.58 mg/ml) (based on dose–response curves and cytotoxicity studies). The median age of the subjects evaluated was 54.50 ± 27 years; 63 (60%) were women. The CM involved in the reaction was iomeprol in 26 cases (28.89%), iodixanol in 19 (21.11%), iohexol in 11 (12.22%), iopromide in 9 (10.00%) and unknown in 25 (27.78%). According to the clinical history, most cases developed reactions with skin involvement (65.65% urticaria/ angioedema and 30% generalized erythema), and only 4.44% had airway or cardiovascular involvement. Regarding symptom severity, 69 cases (76.71%) had grade I reactions, 18 (20%) grade II and 3 (3.33%) grade III. No patients had grade IV reactions.

Sesé (2016) included 37 patients with a definite history of immediate HSR due to Iodine-based Contrast Media (ICM). Immediate HSR was classified according to the Ring and Messmer scale. Skin tests were performed at least 6 weeks after the HSR on the volar forearm with the suspected ICM and with four other ICM. Skin prick tests (SPTs) involved freshly prepared undiluted ICM commercial solutions, and intradermal tests (IDTs) were performed successively with 100-fold and then 10-fold solution diluted in 0.9% sterile saline. Saline and chlorhydrate histamine were negative and positive controls, respectively. In total, 37 patients (24 women, mean age 49.3 years at the time of the reaction) completed the tests. The clinical severity of the reaction was grade I for 26 (70%), grade II for 4 (11%), and grade III for 7 (19%); 35 (95%) reported skin or mucosal symptoms, including pruritus (n = 11), facial erythema (n = 6), generalized erythema (n = 20), urticaria (n = 7), and angioedema (n = 5).

2. Skin testing for late (delayed) hypersensitivity reactions to contrast media
The diagnostic property of cutaneous tests for late (non-immediate) hypersensitivity reactions (HSR) to Iodinated Contrast Media (ICM) was evaluated in one study (Torres, 2012). Torres included a total of 161 subjects with a history of a non-immediate reaction imputable to at least one CM was evaluated. One patient who developed Stevens–Johnson syndrome was not included. The median age was 58.5 years (IR: 48.85 to 66.5) with 82 men (50.9%). According to the information obtained from the clinical history, the CM involved in the reaction were iomeprol in 53 (32.9%), iodixanol in 46 (28.6%), iohexol in 27 (16.8%), iobitridol in 4 (2.5%), ioversol in 3 (1.9%), iopromide in 3 (1.9%), ioxaglate in 2 (1.2%) and unknown in 23 (14.3%). According to the clinical history, 108 cases (67.1%) developed symptoms compatible with exanthema and 53 (32.9%) with delayed urticaria. Regarding symptom severity, 16 cases (9.9%) had mild reactions, 143 (88.8%) moderate reactions, and 2 severe reactions (1.2%) consisting of desquamative exanthema. Concerning the number of episodes, 132 cases (82%) had one episode and 29 cases (18%) two episodes.

Results
1. Skin testing for acute hypersensitivity reactions
Negative predictive value

The rate of a positive skin test in the study of Sesé (2016) was 13.5% (95% CI 4 to 29%) and increased to 20% (95% CI 4 to 48%) for patients who consulted during the year after the HSR. Among the 32 patients with negative skin test results, 31 were challenged successfully, 15 with the culprit ICM. One grade I reaction occurred 2 h after challenge (generalized pruritus, erythema, and eyelid oedema lasting < 1 h) and was considered a positive intravenous challenge result. At 2 h after provocation test, two patients reported generalized and isolated pruritus that regressed with antihistamine therapy and was not considered a positive IPT result. None of five patients with positive skin test to ICM were re-exposed to contrast media during radiologic examination, positive predictive could not be calculated. For an immediate HSR to ICM, the negative predictive value for skin tests with low dose was 80% (95% CI 44 to 97%).

Kim (2013) showed that among the 1046 patients who had negative responses on skin tests, 52 (5.0%) showed immediate-type adverse reactions after CT using radio contrast media. However, most reactions were mild and cutaneous, such as pruritus, urticaria, and mild angioedema. Only 1 patient (0.1%) had a grade II moderate immediate reaction accompanied by breathing difficulty and mild laryngeal oedema, which were relieved with an antihistamine. The negative predictive value of the pre-screening skin test for immediate hypersensitivity reactions before contrast media administration was 95.0%. The negative predictive value of the skin test for immediate hypersensitivity reactions in patients with a history of contrast media hypersensitivity reactions was 80.3% (n= 49/61) and that in patients without a history was 95.9% (n= 945/985).

Results of Salas (2013) showed that five subjects (5.56%) had a positive skin test: three by prick test (one to iodixanol, one to iomeprol and one to iohexol) and five by intradermal testing (four to iohexol, three iodixanol and two to iomeprol). In cases with a negative skin test to all CM tested (N = 74), provocation test was carried out with the culprit CM if known, being positive in three cases; one to iodixanol, one to iomeprol and one to iodixanol, iohexol plus iomeprol. In total, 11 patients with a negative ST refused to undergo a provocation test, resulting in a negative predictive value to immediate hypersensitivity reactions of 95.26%. Eight (8.9%) cases were confirmed as having IHR, 5 (62.5%) by ST and 3 (37.5%) by provocation test. Five from those confirmed as IHR (62.5%) had a positive BAT.

The results of Caimmi (2010) revealed that ICM skin tests were positive in 21 patients (17.5%). Seventeen of them (80.9%) had a history of immediate reaction (four with grade 1, eight grade 2, four grade 3 and one grade 4). Prick tests were all negative. IDT were positive at 20 min for 15 patients with an immediate history and for the patient with unknown chronology. Caimmi (2010) found one single false negative; the negative predictive value of ICM skin tests was 96.6% (95% CI: 89.9 to 103.2).

Quality of evidence
The quality of certainty of evidence was graded as very low due to high risk of bias (see Tab Rob assessment, downgraded by two points) and low number of patients (imprecision downgraded by one point).

2. Skin testing for delayed hypersensitivity reactions
Negative predictive value
In the total group of cases evaluated (N = 161), 34 subjects (21.1%) developed a delayed reading of the intradermal tests positive (13 at 1/10 dilution and 29 undiluted). Of these, 27 were skin-test positive to just one CM, 6 to two CM and 1 to three. The immediate reading of the intradermal tests was negative in all cases. The

skin test was positive to iomeprol in 21 cases (50%), to iodixanol in 7 (16.7%), to iobitridol in 5 (11.9%), to ioxaglate in 4 (9.5%), to iohexol in 3 (7.1%) and to iopromide in 1 (2.4%). In the 34 cases with a positive intradermal test, 10 also had a positive patch test. No positive patch tests were detected in the patients with negative intradermal results. In the patients with a negative skin test to all the CM tested (N = 127), a provocation test was carried out with the CM involved. Provocation test was positive in 44 cases (34.6%), 19 to one CM and 3 to two CM. Thirty-eight cases (76%) were positive to iodixanol, 8 (16%) to iomeprol and 4 (8%) to iohexol. The time interval between administration and symptom development was: 1 to 6 h (13 cases), 7 to 12 h (27 cases), 13 to 24 h (68 cases), 25 to 48 h (41 cases) and > 48 h (12 cases).

Quality of evidence
The quality of certainty of evidence was graded as very low due to high risk of bias (see Tab Rob assessment, downgraded by two points) and low number of patients (imprecision downgraded by one point).

Positive rates of cutaneous tests
The positive rate of cutaneous tests was reported in 12 studies. Since these studies do not compare cutaneous tests with a provocation test, they are not in line with the PICO. However, studies on positive rates of skin tests in patients with HSR to ICM contain important clinical information. Therefore, we have additionally synthesized literature evaluating positive rates of cutaneous tests in patients with HSR to ICM. Since these studies do not describe comparative research, we did not create risk of bias and evidence tables for these studies.
In patients with immediate HSR to ICM, the pooled positive rate of skin tests was 17% (95% CI, 11–26%; I^2= 45%) and was identical to that of IDT (Table 1). The pooled positive rate of SPTs was 3% (95%CI= (1-5%); I^2= 0%). The pooled positive rates of IDT were shown to rise as the severity of reactions increased: pooled positive rate for mild HSR is 12% (95%CI= (6 to 23%); I^2= 38%); moderate HSR 16% (95%CI= (10 to 24%); I^2 = 6%) and for severe HSR, 52% (95%CI= (31 to 74%), I^2= 42%). Table 1 presents a detailed overview of positive rates across studies. Figure 1 presents an overview of per-test cross-reactivity rates between pairs of ICM in skin test positive patients with HSR to ICM.

Table 1 Positive rates of cutaneous tests in patients with immediate HSR to ICM

		Positive rate of skin tests, %		Test Site		Positive rate of IDT, % Severity of HSR		
		SPT[a]	IDT[b]	SPT[a]	IDT[b]	Mild	Moderate	Severe
Dewachter, 2001	ICM[c]	50 (2/4)	100 (4/4)	Forearm	Back	-	-	100 (4/4)
Trcka, 2008	ICM[c]	-	4 (4/96)	Not specified	Not specified	0 (0/40)	7 (3/44)	8 (1/12)
Brockow, 2009	ICM[c]	3 (4/122)	26 (32/121)	Forearm	Forearm	26 (24/92)	-	28 (8/29)
Caimmi, 2010	ICM[c]	0 (0/101)	15 (15/101)	Not specified	Not specified	-	-	-
Dewachter, 2011	ICM[c]	4 (1/24)	46 (12/26)	Forearm	Back	33 (3/9)	40 (4/10)	71 (5/7)
Goksel, 2011	ICM[c]	0 (0/14)	14 (2/14)	Forearm	Forearm	14 (1/7)	14 (1/7)	-
Pinnobphun, 2011	ICM[c]	0 (0/63)	24 (15/63)	Not specified	Not specified	23 (12/53)	0 (0/5)	60 (3/5)
Kim, 2013	ICM[c]	3 (1/32)	26 (12/46)	Not specified	Forearm	13 (4/31)	25 (2/8)	57 (4/7)
Kim, 2014	ICM[c]	2 (1/51)	65 (33/51)	Forearm	Forearm	-	18 (2/11)	78 (31/40)
Renaudin, 2013	ICM[c]	14 (1/7)	57 (4/7)	Not specified	Not specified	-	-	57 (4/7)
Prieto-Garcia, 2013	ICM[c]	0 (0/106)	10 (11/106)	Not specified	Not specified	9 (6/66)	14 (4/29)	9 (1/11)
Salas, 2013	ICM[c]	3 (3/90)	6 (5/90)	Not specified	Forearm	0 (0/69)	11 (2/18)	100 (3/3)
Sesé, 2016	ICM[c]	3 (1/37)	13.5% (5/37)	Forearm	Not specified	11 (4/37)	3 (1/37)	-

[a]SPT = Skin Prick Test; [b]IDT= Intradermal Test; [c]Iodine-based Contrast Media

Immediate HSR		Ionic monomers		Ionic dimer	Nonionic monomers					
		Amido-triozoate	Ioxita-lamate	Ioxaglate	Iobitridol	Iohexol	Iomeprol	Iopamidol	Iopentol	I...
Ionic monomers	Amido-triozoate		12%‡ (3-44%)	10%‡† (3-32%)	11%‡† (3-35%)	8%‡† (2-30%)	11%‡† (3-34%)	10%‡† (3-32%)	9%‡ (1-44%)	
	Ioxita-lamate			7%‡† (2-23%)	8%‡† (2-24%)	8%‡† (2-24%)	7%‡† (2-23%)	10%‡† (2-33%)	5%‡ (1-30%)	
Ionic dimer	Ioxaglate				11%‡†† (4-25%)	7%‡†† (2-19%)	8%‡†† (3-20%)	11%‡† (3-32%)	5%‡ (1-26%)	
Nonionic monomers	Iobitridol					7%‡†† (3-18%)	10%‡†† (5-21%)	10%‡† (5-22%)	9%‡ (2-35%)	
	Iohexol						11%‡†††† (5-22%)	8%‡†† (4-17%)	5%‡ (1-28%)	
	Iomeprol							6%‡†† (2-15%)	13%‡† (2-50%)	2...
	Iopamidol								7%‡† (1-29%)	
	Iopentol									
	Iopromide									
	Ioversol									
Nonionic dimers	Iodixanol									
	Iotrolan									

Figure 1 Cross-reactivity rates between pairs of ICM in skin test-positive patients with HSR to ICM. (from meta-analysis Yoon et al. Allergy 2015)

Cross-reactivity was extracted based on the results of intradermal test with 10^{-1} diluted ICM and patch test with undiluted ICM. If available, results of drug provocation test and graded challenge were also used. The number of † is the number of pooled studies. Pooled cross-reactivity rate is categorized and expressed in grey scale: white, pooled point estimate is ≤10%, and its upper limit of 95% CI is ≤30%; light grey, pooled point estimate is 11% and 15%, or pooled point estimate is ≤10 with its upper limit of 95% CI is >30%; grey, pooled point estimate ranged from 16% and 25%; dark grey, pooled point estimate ranged from 26% and 50%.

HSR, hypersensitivity reaction; ICM, iodinated contrast media; CI, confidence interval.

Zoeken en selecteren

To answer our clinical question a systematic literature analysis was performed for the following research question:

What is the diagnostic value of cutaneous testing for hypersensitivity reactions to contrast media?

P (patient category): patients with hypersensitivity reactions after radiological examinations with contrast media;
I (intervention): cutaneous tests: skin test, patch test (PT), Intradermal test (IDT), skin prick test (SPT) or scratch test;
C (comparison) clinical diagnosis of hypersensitivity reaction after contrast administration;
R (Reference) drug provocation test;
O (outcome) correctly confirmed diagnosis of hypersensitivity reaction to contrast media (sensitivity, specificity, area under the curve, positive predictive value, negative predictive value).

<u>Relevant outcome measures</u>
The working group considered sensitivity and specificity critical outcome measures for the decision-making process; and considered the area under the curve and the positive and negative predictive values important outcome measures.

<u>Search and select (method)</u>
The databases Medline (OVID), Embase and the Cochrane Library were searched from January 1985 to 4th of January 2018 using relevant search terms for systematic reviews (SRs), randomized controlled trials (RCTs) and observational studies (OBS). The literature search resulted in 358 hits: 7 SRs, 33 RCTs and 318 OBS.

Studies were selected based on the following criteria:

- adult patients with hypersensitivity reaction to contrast media;
- evaluation of diagnostic properties of cutaneous tests to contrast media;
- application of a provocation test to confirm results of cutaneous testing;
- reports predefined outcome measures: sensitivity, specificity, area under the curve, positive predictive value, negative predictive value;
- no reports of case series or exploratory findings (n ≥ 10).

Based on title and abstract a total of 37 studies were selected. After examination of full text a total of 33 studies were excluded and five studies were definitely included in the literature summary. Reason for exclusion is reported in exclusion table."). Cross-referencing leads to the inclusion of one additional study.

Five studies were included in the literature analysis; the most important study characteristics and results were included in the evidence tables. The evidence tables and assessment of individual study quality are included. Since study setup, and applied cutaneous tests differed across the studies, we were not able to pool the outcome of the diagnostic test properties.

A total of 13 studies did not fulfil the predefined selection criteria, but described the positive rates of cutaneous tests in patients that had a hypersensitivity reaction after CM administration. The positive rates in these studies are also described under *Positive rates of cutaneous tests*. Because these studies did not fulfil the selection criteria, and did not include a comparison to a reference test, only descriptive data of these studies was shown, and evidence tables and risk of bias tables of these studies are not included.

Verantwoording

Laatst beoordeeld   : 24-06-2020
Laatst geautoriseerd : 24-06-2020

Voor de volledige verantwoording, evidence tabellen en eventuele aanverwante producten raadpleegt u de Richtlijnendatabase.

Referenties

Brockow K, Romano A, Aberer W, Bircher AJ, Barbaud A, Bonadonna P, Faria E, Kanny G, Lerch M, Pichler WJ, Ring J, Rodrigues Cernadas J, Tomaz E, Demoly P, Christiansen C; European Network of Drug Allergy and the EAACI interest group on drug hypersensitivity. Skin testing in patients with hypersensitivity reactions to iodinated contrast media - a European multicenter study. Allergy. 2009 Feb;64(2):234-41. doi: 10.1111/j.1398-9995.2008.01832.x. PubMed PMID: 19178403.

Caimmi S, Benyahia B, Suau D, Bousquet-Rouanet L, Caimmi D, Bousquet PJ, Demoly P. Clinical value of negative skin tests to iodinated contrast media. Clin Exp Allergy. 2010 May;40(5):805-10. doi: 10.1111/j.1365-2222.2010.03493.x. Epub 2010 Mar 12. PubMed PMID: 20337646.

Clement O, Dewachter P, Mouton-Faivre C, Nevoret C, Guilloux L, Bloch Morot E, Katsahian S, Laroche D; investigators of the CIRTACI study. Immediate Hypersensitivity to Contrast Agents: The French 5-year CIRTACI Study. EClinicalMedicine 2018; 1: 51-61.

Dewachter P, Mouton-Faivre C, Felden F. Allergy and contrast media. Allergy. 2001 Mar;56(3):250-1. PubMed PMID: 11251409.

Dewachter P, Laroche D, Mouton-Faivre C, Bloch-Morot E, Cercueil JP, Metge L, Carette MF, Vergnaud MC, Clément O. Immediate reactions following iodinated contrast media injection: a study of 38 cases. Eur J Radiol. 2011; 77: 495-501.

Goksel O, Aydın O, Atasoy C, Akyar S, Demirel YS, Misirligil Z, Bavbek S. Hypersensitivity reactions to contrast media: prevalence, risk factors and the role of skin tests in diagnosis--a cross-sectional survey. Int Arch Allergy Immunol. 2011;155(3):297-305. doi: 10.1159/000320760. Epub 2011 Feb 3. PubMed PMID: 21293150.

Kim MH, Lee SY, Lee SE, Yang MS, Jung JW, Park CM, Lee W, Cho SH, Kang HR. Anaphylaxis to iodinated contrast media: clinical characteristics related with development of anaphylactic shock. PLoS One. 2014 Jun 16;9(6):e100154. doi:10.1371/journal.pone.0100154. eCollection 2014. PubMed PMID: 24932635; PubMed Central PMCID: PMC4059752.

Kim SH, Jo EJ, Kim MY, Lee SE, Kim MH, Yang MS, Song WJ, Choi SI, Kim JH, Chang YS. Clinical value of radiocontrast media skin tests as a prescreening and diagnostic tool in hypersensitivity reactions. Ann Allergy Asthma Immunol. 2013 Apr;110(4):258-62. doi: 10.1016/j.anai.2013.01.004. Epub 2013 Feb 4. PubMed PMID: 23535089.

Pinnobphun P, Buranapraditkun S, Kampitak T, Hirankarn N, Klaewsongkram J. The diagnostic value of basophil activation test in patients with an immediate hypersensitivity reaction to radiocontrast media. Ann Allergy Asthma Immunol. 2011 May;106(5):387-93. doi: 10.1016/j.anai.2010.12.020. Epub 2011 Feb 5. PubMed PMID: 21530870.

Prieto-García A, Tomás M, Pineda R, Tornero P, Herrero T, Fuentes V, Zapatero L, de Barrio M. Skin test-positive immediate hypersensitivity reaction to iodinated contrast media: the role of controlled challenge testing. J Investig Allergol Clin Immunol. 2013;23(3):183-9. PubMed PMID: 23967757.

Renaudin JM, Beaudouin E, Ponvert C, Demoly P, Moneret-Vautrin DA. Severe drug-induced anaphylaxis: analysis of 333 cases recorded by the Allergy Vigilance Network from 2002 to 2010. Allergy. 2013 Jul;68(7):929-37. doi:10.1111/all.12168. Epub 2013 Jun 6. PubMed PMID: 23741979.

Rosado Ingelmo A, Doña Diaz I, Cabañas Moreno R, Moya Quesada MC, García-Avilés C, García Nuñez I, et al. Clinical Practice Guidelines for Diagnosis and Management of Hypersensitivity Reactions to Contrast Media. J Investig Allergol Clin Immunol. 2016;26(3):144-155.

Salas M, Gomez F, Fernandez TD, Doña I, Aranda A, Ariza A, Blanca-López N, Mayorga C, Blanca M, Torres MJ. Diagnosis of immediate hypersensitivity reactions to radiocontrast media. Allergy. 2013 Sep;68(9):1203-1206.

Sesé L, Gaouar H, Autegarden JE, Alari A, Amsler E, Vial-Dupuy A, Pecquet C, Francès C, Soria A. Immediate

hypersensitivity to iodinated contrast media: diagnostic accuracy of skin tests and intravenous provocation test with low dose. Clin Exp Allergy. 2016 Mar;46(3):472-8. doi: 10.1111/cea.12703. PubMed PMID: 26750091.

Torres MJ, Gomez F, Doña I, Rosado A, Mayorga C, Garcia I, Blanca-Lopez N, Canto G, Blanca M. Diagnostic evaluation of patients with nonimmediate cutaneous hypersensitivity reactions to iodinated contrast media. Allergy. 2012 Jul;67(7):929-35. doi: 10.1111/j.1398-9995.2012.02840.x. Epub 2012 May 15. PubMed PMID: 22583135.

Trcka J, Schmidt C, Seitz CS, Bröcker EB, Gross GE, Trautmann A. Anaphylaxis to iodinated contrast material: nonallergic hypersensitivity or IgE-mediated allergy? AJR Am J Roentgenol. 2008 Mar;190(3):666-70. doi: 10.2214/AJR.07.2872. PubMed PMID: 18287437.

Prophylaxis of hypersensitivity reactions after contrast administration

Uitgangsvraag

Which prophylactic measures should be taken in patients with increased risk of hypersensitivity reactions after contrast administration?

Aanbeveling

I Patients with a previous (acute) hypersensitivity reaction to a known ICM or GBCA
A Elective (plannable) examinations with ICM or GBCA
In all patients with a (documented) history of a hypersensitivity reaction to an iodine-based or gadolinium-based CM, consider an alternative imaging modality. When this is not possible, consider performing an unenhanced exam, but only if this has an acceptable reduction in diagnostic quality.

If the previous hypersensitivity reaction was mild:

- Choose a different ICM or GBCA*.
- Observe the patient ≥ 30 min with IV in place.

If the previous hypersensitivity reaction was moderate:

- Choose a different ICM or GBCA*.
- Observe the patient ≥ 30 min with IV in place.
- Be vigilant to react to a possible new hypersensitivity reaction.

If the previous hypersensitivity reaction was severe:

- If clinically reasonable, defer the imaging study until the results of allergologic skin testing are available.
- Refer the patient to a drug allergy specialist for allegologic skin testing with a panel of different iodine-based or gadolinium-based CM.
- Apply the advice of the drug allergy specialist for future CM administration.
- Premedicate with 2 x 25 mg prednisolone PO/IV** 12h and 2h before CM administration and 2mg clemastine IV within 1h before CM administration.
- Observe the patient ≥ 30 min with IV in place.
- Be vigilant to react to a possible new hypersensitivity reaction.

B Acute (within hours) or emergency (direct) examinations with ICM or GBCA
In all patients with a (documented) history of a hypersensitivity reaction to an iodine-based CM, consider an alternative imaging modality. When this is not possible, consider performing unenhanced exam, if this has an acceptable reduction in diagnostic quality.

If the previous hypersensitivity reaction was mild:

- Choose a different ICM or GBCA*.
- Observe the patient ≥ 30 min with IV in place.
- Be vigilant to react to a possible new hypersensitivity reaction.

If the previous hypersensitivity reaction was moderate:

- Premedicate with 50 mg prednisolone IV** and 2mg clemastine IV within 30min before CM administration.
- Choose a different ICM or GBCA*.
- Observe the patient ≥ 30 min with IV in place.
- Be vigilant to react to a possible new hypersensitivity reaction.

If the previous hypersensitivity reaction was severe:

- Premedicate with 50 mg prednisolone IV** and 2mg clemastine IV within 30min before CM administration.
- Choose a different ICM or GBCA*.
- Observe the patient ≥ 30 min with IV in place.
- Be vigilant to react to a possible new hypersensitivity reaction.

II Patients with a previous (acute) hypersensitivity reaction to an unknown ICM or GBCA
A Elective (plannable) examinations with ICM or GBCA
In all patients with a (documented) history of a hypersensitivity reaction to an iodine-based or gadolinium-based CM, consider an alternative imaging modality. When this is not possible, consider performing an unenhanced exam, but only if this has an acceptable reduction in diagnostic quality.

If the previous hypersensitivity reaction was mild:

- Proceed with the radiologic examination normally.
- Observe the patient ≥ 30 min with IV in place.
- Be vigilant to react to a possible new hypersensitivity reaction.

If the previous hypersensitivity reaction was moderate:

- Proceed with the radiologic examination normally.
- Observe the patient ≥ 30 min with IV in place.
- Be vigilant to react to a possible new hypersensitivity reaction.

In cases of doubtful severity consider referring the patient to a drug allergy specialist for allergologic skin testing with a panel of different iodine-based or gadolinium-based CM.

If the previous hypersensitivity reaction was severe:

- If clinically reasonable, defer the imaging study until results of allergologic skin testing are available.
- Refer the patient to a drug allergy specialist for allergologic skin testing with a panel of different iodine-based or gadolinium-based CM.
- Apply the advice of the drug allergy specialist for future CM administration.
- Premedicate with 2 x 25 mg prednisolone PO/IV** 12h and 2h before CM administration and 2mg clemastine IV within 1h before CM administration.
- Observe the patient ≥ 30 min with IV in place.
- Be vigilant to react to a possible new hypersensitivity reaction.

B Acute (within hours) or emergency (direct) examinations with ICM or GBCA
In all patients with a (documented) history of a hypersensitivity reaction to an iodine-based or gadolinium-based CM, consider an alternative imaging modality. When this is not possible, consider performing unenhanced exam, if this has an acceptable reduction in diagnostic quality.

If the previous hypersensitivity reaction was mild:

- Proceed with the radiologic examination normally.
- Observe the patient ≥ 30 min with IV in place.
- Be vigilant to react to a possible new hypersensitivity reaction.

If the previous hypersensitivity reaction was moderate:

- Premedicate with 50 mg prednisolone IV** and 2mg clemastine IV within 30min before CM administration
- Proceed with the radiologic examination normally.
- Observe the patient ≥ 30 min with IV in place.
- Be vigilant to react to a possible new hypersensitivity reaction.

If the previous hypersensitivity reaction was severe:

- Premedicate with 50 mg prednisolone IV** and 2mg clemastine IV within 30min before CM administration
- Proceed with the radiologic examination normally.
- Observe the patient ≥ 30 min with IV in place.
- Be vigilant to react to a possible new hypersensitivity reaction.

III Patients with a previous breakthrough reaction to CM
In patients with breakthrough hypersensitivity reactions to iodine-based or gadolinium-based CM apply the same as above, but always refer the patient to a drug allergy specialist for allergologic skin testing with a panel of different ICM or GBCA.

IV Patients with previous (acute) hypersensitivity reactions to multiple CM
In patients with hypersensitivity reactions to multiple iodine-based or gadolinium-based CM (either 2 or more

different iodine-based CM or gadolinium-based CA or to an iodine-based CM and a gadolinium-based CA) apply the same as above, but always refer the patient to a drug allergy specialist for allergologic skin testing with a panel of different ICM and GBCA.

<u>V Patients with previous non-severe late hypersensitivity reactions to CM</u>
In patients with previous mild or moderate late hypersensitivity reactions to iodine-based CM or gadolinium-based CA premedication is not recommended, even in acute or emergency examinations.

Notes
* Consider cross-reactivity of iodine-based CM (see Introduction to this section, table 2).

**Or equivalent dose of another glucocorticosteroid
25 or 50 mg prednisolone is equivalent to:

- 20 or 40 mg methylprednisolone.
- 4 or 8mg dexamethasone.
- 100 or 200mg hydrocortisone.

Also see the flowcharts.

Overwegingen

First and foremost, in patients with a (documented) history of a hypersensitivity reaction to a contrast medium, consider an alternative imaging modality first. In many cases, CT with iodinated contrast media can be replaced by ultrasound, with or without contrast media, or MRI, with or without contrast media. When this is not possible, consider performing the examination without a contrast medium, but only if this has an acceptable degree of diagnostic quality. For this, close communication with the referring specialist is mandatory.

When evaluating hypersensitivity reactions, it is difficult to compare literature. In the literature, adverse effects or adverse reactions are often reported which also include (severe) physiologic effects to contrast medium administration and chemotoxic effects. Anxiety may play a role in hypersensitivity reactions (Lalli, 1974).

Based on the available literature it is not possible to conclusively identify a group of patients that is at increased risk for hypersensitivity and should routinely receive premedication prior to contrast administration. In the ACR Manual on Contrast Media v.10.3 (ACR, 2017) and the ESUR v10 guidelines (Clement, 2014; ESUR 2017), the most significant risk factor for increased risk of hypersensitivity reactions remains a documented history of a previous hypersensitivity reaction to a contrast medium. Patients with atopy/ bronchial asthma or multiple allergies could not be established as a consistent risk factor (Chen, 2015; Jung, 2016).

The evidence regarding the effectivity of corticosteroids and antihistamines for pharmacological prevention is very heterogeneous and of low quality (Tramer, 2006; Dawson, 2006; Davenport, 2015). It seems that prophylactic premedication can prevent the number of hypersensitivity reactions after contrast administration,

but premedication mainly reduces the number of mild reactions and therefore the total number of reactions (Lasser, 1994). There is little data that premedication reduces the number of moderate and severe hypersensitivity reactions, and its use should therefore be limited.

It was believed that premedication with corticosteroids and H1-antihistamines do not have serious side effects and is not costly. However, recently it has been shown that premedication was associated with brief hyperglycaemia (Davenport, 2010), but also with longer hospital stay, increased costs, and worse clinical outcomes (Davenport, 2016).

The old protocols for premedication (Greenberger, 1984; Greenberger, 1986; Lasser, 1994) are still in widespread use (often slightly modified), but there is no literature to establish an optimal indication or protocol. Recently the Greenberger protocol has been challenged by newer, shorter options for inpatients (Mervak, 2017).

Greenberger protocol (elective examinations 1984):

- Prednisolone 50 mg IV - 13h, 7h and 1h before the procedure.
- Diphenhydramine 50 mg IV - 1h before the procedure.

Greenberger protocol (emergency examinations 1986):

- Hydrocortisone 200 mg IV - immediately and every 4h until procedure is finished
- Diphenhydramine 50 mg IV - 1h before the procedure

Lasser protocol (elective examinations 1994):

- Methylprednisolone 32 mg IV - 12h and 2h before the procedure.

In addition, premedication is not perfect. In 2 to 17% of premedicated patients so-called "breakthrough" hypersensitivity reactions can occur despite premedication. These are usually of similar severity as the original culprit reaction for which premedication was prescribed and seldom severe (Davenport, 2009; Mervak, 2015; Lee, 2017).

Another main problem is the registration of contrast media in radiology information systems. For a long time, contrast media have not been treated as drugs. Therefore, in many hospitals iodine-based and other contrast media are "doomed" as a group when a single hypersensitivity reaction to one specific agent occurs, without much testing of the specific culprit agent. Like all drugs, hypersensitivity should nowadays be approached at agent level and not at group level. There is growing evidence that suggests that switching to another agent may be an effective strategy (Abe, 2016; Lee, 2017; Park, 2017).

Premedication of late hypersensitivity reactions
There is a paucity of data on the benefits of premedication for non-severe late hypersensitivity reactions. Most of these reactions are self-limiting or can be treated symptomatically. Major international guidelines suggest to

perform allergologic skin testing, but do not recommend the use of premedication for non-severe late reactions (ESUR 2018, ACR 2018).

Inleiding

Patients report hypersensitivity reactions to contrast media, and often these have occurred in the past. This can involve objective signs or symptoms that fit well with a hypersensitivity reaction. However, in many cases other complaints are reported, such as hyperventilation, vasovagal reactions or panic attacks. These may not fit accurately with a hypersensitivity reaction to CM. In addition, patient's history can include diseases like severe asthma, mastocytosis or the use of medication that may be associated with an increased risk to hypersensitivity reactions.

For the physician administering the CM it is often not clear how to deal with this kind of situations and whether prophylactic medication is indicated. In addition, the literature on the effectiveness of premedication prior to CM administration remains unclear.

All types of contrast media can give hypersensitivity reactions. See further the Introduction to this section.

All types of contrast media will be evaluated: iodine-based, gadolinium-based, microbubble, CM. Also, all types of administration routes will be covered, intravascular (intravenous or intra-arterial), oral and rectal, intracavitary (joints or bladder), and intraductal (bile or pancreatic ducts). See the submodule ' Hypersensitivity Reactions after Nonvascular CM Administration'.

Conclusies

Factors related to the risk of hypersensitivity reactions after contrast administration.

Low GRADE	The following factors were associated with an increased risk of adverse drug reaction in patients undergoing coronary angiography or percutaneous coronary intervention and receiving iopromide contrast:
	
	  ○ age < 50 years;
	  ○ no premedication with corticosteroids;
	  ○ contrast dose < 100mL;
	  ○ no pre-procedural hydration;
	  ○ left main coronary disease;
	  ○ previous ADR to contrast.
	
	Allergic constitution, asthma and sex were not independently associated with the risk of developing an adverse reaction.
	
	Source: (Chen, 2015)

Low GRADE	The following factors were associated with an increased risk for developing this second acute allergic-like adverse reaction in patients with a history of a hypersensitivity reaction after low-osmolality contrast administration, who were undergoing another enhanced computed tomography with low-osmolality contrast medium and receiving premedication: - younger age; - previous severe reaction; - no corticosteroid premedication. The following factors were not independently associated with the risk of acute allergic-like adverse reactions: sex, bronchial asthma, allergic rhinitis, chronic urticaria, food allergy, other drug allergy, H2-antihistamines premedication. *Source: (Jung, 2016)*

Low GRADE	The following factors were associated with an increased risk for developing this second hypersensitivity reaction in patients with a history of a moderate or severe hypersensitivity reaction after low-osmolality contrast administration, who were undergoing another enhanced computed tomography with low-osmolality contrast medium and receiving premedication: - younger age; - diabetes mellitus; - chronic urticaria; - drug allergy; - not changing the iodinated contrast medium; - Initial hypersensitivity reaction was severe. The following factors were not independently associated with the risk of developing a recurrent hypersensitivity reaction: sex, use of premedication. *Source: (Park, 2017)*

Prophylactic measures to prevent hypersensitivity reactions after contrast administration

Very low GRADE	It is unclear whether the use of premedication decreases the risk of life-threatening anaphylactic reactions.

The administration of H1-antihistamines immediately prior to the administration of contrast may decrease the risk of developing hypersensitivity reactions due to iodinated contrast.

The administration of corticosteroids given in two doses, 6 hours prior and 2 hours prior to the administration of contrast, both iodinated and non-iodinated, may decrease the risk of developing hypersensitivity reactions due to contrast administration.

Source: (Tramer, 2006) |

Samenvatting literatuur

1. Factors related to the risk of hypersensitivity reactions after contrast administration.
Description of studies
A total of 3 studies described factors independently related to the risk of hypersensitivity reactions after contrast administration. All studies presented multivariate models, but no internal or external validation of these models, or the results of application of these models in clinical practice.

Chen (2015) described the risk factors associated with adverse reactions (occurring within 1 hour after contrast administration) in 17,513 patients who were administered iopromide (300 or 370 mgI/mL) contrast during coronary angiography or Pecutaneous Coronary Intervention (PCI). All patients (not high-risk patients only) were included in this multicentre (63 centres in China) study.

Jung (2016) described risk factors for developing a hypersensitivity reaction after re-administration of low-osmolality iodinated contrast medium for enhanced computed tomography in 322 patients with a history of hypersensitivity reactions after low-osmolality contrast administration. A total of 219 (68%) of the patients had a mild reaction, while 82 (26%) had a moderate reaction, and 21 (7%) a severe reaction in their history. Premedication was decided on an individual basis by clinicians and could consist of oral and/or intravenous H1-antihistamines, H2-antihistamins and corticosteroids.

Park (2017) described risk factors for developing a hypersensitivity reaction after administration of low-osmolar iodinated contrast medium for enhanced computed tomography in 150 patients with a history of moderate 130 (87%) to severe 20 (13%) hypersensitivity reactions after contrast administration in 328 instances of re-exposure. Patients received antihistamines and/or corticosteroids as pre-medication, the exact premedication was decided on an individual basis.

Results
Chen (2015) reported that acute adverse drug reactions (ADRs) occurred in 66/17,513 (0.38%) patients undergoing iopromide (300 or 370 mgI/mL) administration during coronary angiography or Percutaneous Coronary Intervention (PCI), out of which 2 ADRs (0.01%) were severe. Most ADRs manifested as nausea vomiting (0.22%) and rash (0.09%).

The following factors were associated with risk of ADR:

- age 50 to 69 versus age < 50 (OR: 0.48, 95% CI: 0.27 to 0.85);
- premedication with corticosteroids (OR: 0.41, 95% CI: 0.18 to 0.97);
- contrast dose ≥ 100mL (OR 0.50, 95% CI 0.30 to 0.82);
- pre-procedural hydration (OR: 0.11, 95% CI: 0.04 to 0.33);
- left main coronary disease (OR: 2.27, 95% CI: 1.15 to 4.48);
- previous ADR to contrast (OR: 9.30, 95% CI: 1.10 to78.84).

Allergic constitution, asthma and sex were not independently associated with the risk of developing an adverse reaction.

Jung (2016) described that 47/322 (15%) of the patients experienced a recurrence of an allergic reaction after low-osmolality iodinated contrast medium administration for computed tomography, despite premedication.

The following factors were associated with an increased risk for developing this second acute allergic-like adverse reaction:

- age (OR: 0.97, 95% CI: 0.94 to 0.99);
- previous severe reaction (OR: 8.88, 95% CI: 2.11 to 37.42);
- not using corticosteroid premedication (OR: 0.28, 95% CI: 0.10 to 0.78) - people that used corticosteroid medications had a lower risk to experience an allergic reaction.

The following factors were not independently associated with the risk of acute allergic-like adverse reactions: sex, bronchial asthma, allergic rhinitis, chronic urticaria, food allergy, other drug allergy, H2-antihistamines premedication.

Park (2017) reported that a recurrence of hypersensitivity reactions after contrast exposure occurred in 64/328 (20%) of the instances of re-exposure to low-osmolar iodinated contrast in patients with a history of moderate or severe reactions.

The following factors were associated with an increased risk for developing this second hypersensitivity reaction:

- age (OR: 0.97, 95% CI 0.94 to 0.99);
- diabetes mellitus (OR: 6.49, 95% CI: 2.38 to 17.71);
- chronic urticaria (OR: 7.61, 95% CI: 1.63 to 35.59);
- drug allergy (OR: 3.69, 95% CI: 1.18 to 11.56);
- Changing the iodinated contrast medium (OR: 0.33, 95% CI: 0.17 to 0.64);
- initial hypersensitivity reaction was severe (OR: 2.67, 95% CI: 1.05 to 6.79).

The following factors were not independently associated with the risk of developing a recurrent hypersensitivity reaction: sex, use of premedication.

Level of evidence

For all the included patient populations the quality of certainty of evidence for the prognostic factors was downgraded from high to low by two points, due to risk of bias and indirectness: the prognostic factors were identified, but the prognostics model was not validated internally and externally. The value of the applicability of the multivariate models in a clinical decision-making process was not evaluated.

2. Prophylactic measures to prevent hypersensitivity reactions after contrast administration

Description of studies

One systematic review (Tramer, 2006) that included 9 RCTs was included in this analysis. The goal of this review was to review the efficacy of pharmacological prevention of serious reactions to iodinated contrast media. A systematic search was performed up to October 2005. The pre-specified inclusion criteria were random allocation of patients, use of premedication alone or in combination, presence of a placebo or a no treatment control group, and reporting of presence or absence of allergic reactions. A total of 9 trials with 10,011 adult patients were included in the review analysis. No RCTs that answered the search question were found that were published after Tramer, 2006.

Results

Tramer (2006) reported 9 trials (including 10,011 adults) tested H1 antihistamines, corticosteroids, and an H1 to H2 combination. No trial included exclusively patients with a history of allergic reactions. Many outcomes were not allergy related, and only a few were potentially life threatening. No reports on death, cardiopulmonary resuscitation, irreversible neurological deficit, or prolonged hospital stays were found. In two trials, 3/778 (0.4%) patients who received oral methylprednisolone 2×32 mg or intravenous prednisolone 250 mg had laryngeal oedema compared with 11/769 (1.4%) controls (odds ratio 0.31, 95% confidence interval 0.11 to 0.88). In two trials, 7/3093 (0.2%) patients who received oral methylprednisolone 2×32 mg had a composite outcome (including shock, bronchospasm, and laryngospasm) compared with 20/2178 (0.9%) controls (odds ratio 0.28, 0.13 to 0.60). In one trial, 1/196 (0.5%) patient who received intravenous clemastine 0.03 mg/kg and cimetidine 2 to 5 mg/kg had angio-oedema compared with 8/194 (4.1%) controls (odds ratio 0.20, 0.05 to 0.76).

Table 1 Details of included trials

References	Quality of data reporting (R-C-B-F)*	Premedication and control (No analysed)	Radiological intervention (No analysed)
Bertrand et al, 1992[w3]	1-0-2-0	Hydroxyzine 100 mg PO 12 h before (200); placebo PO (200)	IV urography (297); CT scan (93); venography (10)
Chevrot et al, 1988[w4]	1-0-0-0	Betamethasone 8 mg IV with CM (109); no treatment (112)	IV urography; CT scan; venography
Ginsberg et al, 1996[w5]	1-0-1-0	Dexamethasone 4 mg PO 4×/d for 24 h (42); placebo PO (44)	Myelography
Lasser et al, 1987[w1]	1-1-2-0	Methylprednisolone 2×32 mg PO evening and 2 h before (2513, group 1); methylprednisolone 32 mg PO 2 h before (1759, group 2); placebo PO as for group 1 (1603); placebo PO as for group 2 (888)	IV injection
Lasser et al, 1994[w2]	1-0-2-1	Methylprednisolone 2×32 mg PO 6-24 h and 2 h before (580); placebo PO (575)	Urography; CT scan
Ring et al, 1985[w6]	1-0-0-1	Prednisolone 250 mg IV (198); clemastine 0.03 mg/kg IV (191); clemastine 0.03 mg/kg + cimetidine 2-5 mg/kg (according to renal function) IV (196); placebo (saline) IV (194); timing not specified	IV urography
Small et al, 1982[w7]	1-0-0-0	Chlorpheniramine 10 mg SC 15 min before (78); placebo (saline) SC (71); no treatment (71)	IV pyelography
Smith et al, 1995[w8]	1-0-2-1	Dimenhydrinate 25 mg IV 15 to 45 min before (150); placebo (saline) IV (149)	Arteriography
Wicke et al, 1975[w9]	1-0-1-0	Clemastine 2 mg IV with CM (92); placebo (saline) IV (116)	Urography (148); cholangiography (60)

CM=contrast medium; CT=computed tomography; IV=intravenously; PO=orally; SC=subcutaneously.
*Randomisation (R): 0=none, 1=mentioned but not specified, 2=mentioned and adequate. Concealment of treatment allocation (C): 0=none; 1: and caregiver and observer blinded. Follow-up (F): 0=none reported, 1=incomplete, 2=complete (intention to treat analysis possible).

Federatie
Medisch
Specialisten

			No with symptoms/total No (%)		Odds ratio
Haemodynamic symptoms			Premedication	Control	
Chevrot 1988[w4]	Betamethasone	Hypotension	0/109 (0.0)	1/112 (0.9)	
Lasser 1994[w2]	Methylprednisolone	Hypotension	0/580 (0.0)	2/575 (0.3)	
		Steroid combined	0/689 (0.0)	3/687 (0.4)	
Respiratory symptoms					
Bertrand 1992[w3]	Hydroxyzine	Bronchospasm	0/200 (0.0)	1/200 (0.5)	
Ring 1985[w6]	Clemastine	Angio-oedema	4/191 (2.1)	8/194 (4.1)	
		Anti-H$_1$ combined	4/391 (1.0)	9/394 (2.3)	
Lasser 1994[w2]	Methylprednisolone	Laryngeal oedema	0/580 (0.0)	3/575 (0.5)	
Ring 1985[w6]	Prednisolone	Angio-oedema	3/198 (1.5)	8/194 (4.1)	
		Steroid combined	3/778 (0.4)	11/769 (1.4)	
Cutaneous symptoms					
Bertrand 1992[w3]	Hydroxyzine	Urticaria	0/200 (0.0)	17/200 (8.5)	
Smith 1995[w8]	Dimenhydrinate	Pruritus	7/150 (4.7)	9/149 (6.0)	
Small 1982[w7]	Chlorpheniramine	Hives, pruritus	1/78 (1.3)	15/142 (10.6)	
Wicke 1975[w9]	Clemastine	Urticaria	0/92 (0.0)	2/116 (1.7)	
Ring 1985[w6]	Clemastine	Flush	6/191 (3.1)	6/194 (3.1)	
		Anti-H$_1$ combined	14/711 (2.0)	49/801 (6.1)	
Ring 1985[w6]	Prednisolone	Flush	2/198 (1.0)	6/194 (3.1)	
Lasser 1994[w2]	Methylprednisolone	Hives	3/580 (0.5)	9/575 (1.6)	
		Steroid combined	5/778 (0.6)	15/769 (2.0)	

0.02   0.1

Favours
premedication

Fig 2 Distinct haemodynamic, respiratory, and cutaneous symptoms. Hypotension, bronchospasm, angio-oedema, a potentially life threatening. Anti-H=antihistamine. *P for heterogeneity=0.03, I^2=62%

	No with symptoms/total No (%)		Odds ratio (95
Grade 1	**Premedication**	**Control**	
Lasser 1987[w1] MP 32 mg, 2 h before	94/1759 (5.3)	45/888 (5.1)	
Lasser 1987[w1] MP 2 x 32 mg, evening and 2 h before	86/2513 (3.4)	79/1603 (4.9)	
Lasser 1994[w2] MP 2 x 32 mg, 6 to 24 h and 2 h before	1/580 (0.2)	10/575 (1.7)	
Combined MP 2 x 32 mg	87/3093 (2.8)	89/2178 (4.1)	
Grade 2			
Lasser 1987[w1] MP 32 mg, 2 h before	63/1759 (3.6)	41/888 (4.6)	
Lasser 1987[w1] MP 2 x 32 mg, evening and 2 h before	72/2513 (2.9)	55/1603 (3.4)	
Lasser 1994[w2] MP 2 x 32 mg, 6 to 24 h and 2 h before	7/580 (1.2)	9/575 (1.6)	
Combined MP 2 x 32 mg	79/3093 (2.6)	64/2178 (2.9)	
Grade 3			
Lasser 1987[w1] MP 32 mg, 2 h before	9/1759 (0.5)	2/888 (0.2)	
Lasser 1987[w1] MP 2 x 32 mg, evening and 2 h before	5/2513 (0.2)	11/1603 (0.7)	
Lasser 1994[w2] MP 2 x 32 mg, 6 to 24 h and 2 h before	2/580 (0.3)	9/575 (1.6)	
Combined MP 2 x 32 mg	7/3093 (0.2)	20/2178 (0.9)	

0.02   0.1   1

Favours premedication

Fig 3   Arbitrary symptom combinations ("grades") as defined in the original reports.[w1] [w2] Grade 1=single episode of eme: 2=hives, erythema, emesis more than once, or fever or chills (or both); grade 3=shock, bronchospasm, laryngospasm or convulsions, fall or rise in blood pressure, cardiac arrhythmia, angina, angio-oedema, or pulmonary oedema. Grade 3 wa: MP=methylprednisolone (oral)

Level of evidence

The quality of certainty of evidence for the outcome hypersensitivity reaction was downgraded from high to very low due to risk of bias (as described below), heterogeneity of included studies, inconsistency of results and imprecision of outcome measures (low numbers of events).

The risk of bias of the included studies was deemed high: in no report was an adequate randomisation method described, and only in one was treatment allocation concealed. In four reports, evidence existed of adequate blinding of patients, caregivers, and observers. No report described a complete patient follow-up that enabled an intention to treat analysis.

Zoeken en selecteren

To answer our clinical question a systematic literature analysis was performed for the following research questions:

1) What factors are related to an increased risk of developing hypersensitivity reactions after contrast administration?

P (patient category): patients undergoing radiological examinations with contrast media;
I (intervention): presence of prognostic factors;
C (comparison): absence of prognostic factors;
O (outcome) allergic reactions to contrast, hypersensitivity reaction, type I / type IV, severe allergic reaction.

2) What are the effects of a prophylactic measure to prevent hypersensitivity reactions after contrast administration compared to a different measure to prevent hypersensitivity reactions after contrast administration or no prophylactic measure, in patients undergoing radiological examinations with contrast media?

P (patients): patients undergoing radiological examinations with contrast media;
I (intervention): prophylactic measure to prevent hypersensitivity reactions after contrast administration;
C (comparison): no prophylactic measure or a different prophylactic measure to prevent hypersensitivity reactions after contrast administration;
O (outcome): allergic reactions to contrast, hypersensitivity reaction, type I/ type IV, severe allergic reaction.

Relevant outcome measures
The working group considered allergic reactions to contrast/ hypersensitivity reactions critical outcome measures for the decision-making process.

Search and select (method)
The databases Medline (OVID), Embase and the Cochrane Library were searched from 1st of December 1980 to 4th of December 2017 using relevant search terms for systematic reviews (SRs), randomized controlled trials (RCTs) and observational studies (OBS). The literature search resulted in 478 hits: 42 SRs, 129 RCTs and 307 OBS.

Studies were selected based on the following criteria:

- adult patients undergoing radiological examinations with contrast media;
- evaluation of effectiveness of prophylactic measures to prevent hypersensitivity reactions after contrast administration;
- or: Evaluation or identification of factors associated with an increased risk of hypersensitivity reactions after contrast administration. These factors could be treatment related, or patient related. Studies were only included when the identified risk factors were corrected for confounders (multivariate models);
- reports predefined outcome measure: hypersensitivity reactions;
- no reports of case series or exploratory findings (n ≥ 10).

Based on title and abstract a total of 123 studies were selected. After examination of full text, a total of 119 studies were excluded and 4 studies were definitely included in the literature summary. Reason for exclusion is reported in the exclusion table.

Three studies were included for the research question regarding the identification of factors related to associated with an increased risk of hypersensitivity reactions after contrast administration. One systematic review (Tramer, 2006) was included for the research question regarding the comparison of the different prophylactic measures to prevent hypersensitivity reactions after contrast administration. The most important study characteristics and results were included in the evidence tables. The evidence tables and assessment of individual study quality are included.

Verantwoording

Laatst beoordeeld   : 24-06-2020
Laatst geautoriseerd : 24-06-2020

Voor de volledige verantwoording, evidence tabellen en eventuele aanverwante producten raadpleegt u de Richtlijnendatabase.

Referenties

Abe S, Fukuda H, Tobe K, Ibukuro K. Protective effect against repeat adverse reactions to iodinated contrast medium: Premedication versus. changing the contrast medium. Eur Radiol 2016; 26: 2148-2154.
<p align="left">American College of Radiology. ACR Manual on contrast media, v10.3. Available at: www.acr.org/Clinical-Resources/Contrast-Manual. Accessed: 11 July 2019.
Chen JY, Liu Y, Zhou YL, et al. Safety and tolerability of iopromide in patients undergoing cardiac catherization: real-world multicenter experience with 17,513 patients from the TRUST trial. Int J Cardiovasc Imaging 2015; 31: 1281-1291
Clement O, Webb JAW. Acute Adverse Reactions to Contrast Media: Mechanisms and Prevention. In: Thomsen HS, Webb JAW (eds). Contrast media: safety issues and ESUR guidelines, 3rd edition. Heidelberg: Springer Nature, 2014, 51-60.
Davenport MS, Cohan RH, Caoili EM, Ellis JH. Repeat contrast medium reactions in premedicated patients: frequency and severity. Radiology 2009; 253:372-379.
Davenport MS, Cohan RH, Caoili EM, Ellis JH. Hyperglycemic consequences of corticosteroid premedication in an outpatient population. AJR Am J Roentgenol 2010; 194 (6):W483-488,
Davenport MS, Mervak BM, Ellis JH, Dillman JR, Dunnick NR, Cohan RH. Indirect Cost and Harm Attributable to Oral 13-Hour Inpatient Corticosteroid Prophylaxis before Contrast-enhanced CT. Radiology 2016; 279: 492-501
Davenport MS, Cohan RH, Ellis JM. Contrast media controversies in 2015: Imaging patients with renal impairment or risk of contrast reaction. AJR Am J Roentgenol 2015; 204: 1-8
Dawson P. Adverse reactions to intravascular contrast agents: routine prophylaxis is not supported by evidence. BMJ 2006; 333: 663-664
European Society of Urogenital Radiology Contrast Media Safety Committee. ESUR Guidelines on contrast safety, v10. Available at: www.esur-cm.org. Accessed: 11 July 2019
Greenberger PA, Patterson R, Radin RC. Two pretreatment regimens for high-risk patients receiving radiographic contrast media. J Allergy Clin Immunol 1984; 74 (4 Pt 1):540-543.
Greenberger PA, Halwig JM, Patterson R, Wallemark CB. Emergency administration of radiocontrast media in high risk patients. J Allergy Clin Immunol 1986; 77: 630-634
Jingu A, Fukuda J, Taketomi-Takahashi A, et al. Breakthrough reactions of iodinated and gadolinium contrast media after oral steroid premedication protocol. BMC Med Imaging. 2014;14:34.
Jung JW, Choi YH, Park CM, Park HW, Cho SH, Kang HR. Outcomes of corticosteroid prophylaxis for hypersensitivity reactions to low osmolar contrast media in high-risk patients. Ann Allergy Asthma Immunol 2016; 117: 304-309
Katayama H, Yamguchi K, Kozuka T, Takashima T, Seez P, Matsuura K. Adverse reactions to ionic and nonionic contrast media. A report from the Japanese committee on the safety of contrast media. Radiology 1990; 175: 621-628.
Lalli AF. Urographic contrast media reactions and anxiety. Radiology 1974; 112:267-271

Lasser EC, Berry CC, Mishkin MM, Williamson B, Zheutlin N, Silverman JM. Pretreatment with corticosteroids to prevent adverse reactions to nonionic contrast media. AJR Am J Roentgenol 1994; 162: 523-526.

Lee SY, Yang MS, Choi YH, et al. Stratified premedication strategy for the prevention of contrast media hypersensitivity in high risk patients. Ann Allergy Asthma Immunol 2017; 118: 339-344.e1.

Mervak BM, Davenport MS, Ellis JH, et al. Rates of breakthrough reactions in inpatients at high risk receiving premedication before contrast-enhanced CT. AJR Am J Roentgenol. 2015; 205: 77-84.

Mervak BM, Cohan RH, Ellis JH, Khalatbari S, Davenport MS. 5-hour intravenous corticosteroid premedication has a breakthrough reaction rate that is non-inferior to that of a traditional 13-hour oral regimen. Radiology 2017; 285: 425-433

Park HJ, Park JW, Yang MS, Kim MY, Kim SH, Jang GC, Nam YH, Kim GW, Kim S, Park HK, Jung JW, Park JS, Kang HR. Re-exposure to low osmolar iodinated contrast media in patients with prior moderate-to-severe hypersensitivity reactions: A multicentre retrospective cohort study. Eur Radiol 2017; 27: 2886-2893

Tramer MR, von Elm E, Loubeyre P, Hauser C. Pharmacological prevention of serious anaphylactic reactions due to iodinated contrast media: systematic review. BMJ 2006; 333: 675-682.

Hypersensitivity Reactions after Nonvascular CM Administration

Uitgangsvraag

Hypersensitivity Reactions after Nonvascular CM Administration

Aanbeveling

Small amounts of ICM or GBCA can be absorbed by mucosa and enter the systemic circulation after all types of nonvascular CM administration.

Hypersensitivity reactions after nonvascular administration of ICM and GBCA can occur, but their incidence is low to very low.

No preventive measures are indicated for ERCP or for nonvascular GBCA administration.

For other indications using ICM no firm recommendations can be given for patients that have experienced hypersensitivity reactions to CM in the past.

In patients that have experienced *severe* hypersensitivity reactions to CM in the past, alternative imaging or contrast agents should be explored with the radiologist, and a strict indication for examinations using nonvascular CM administration is needed.

In patients that have experienced *severe* hypersensitivity reactions to CM in the past, preventive measures for severe reactions as outlined in the module 'Prophylaxis of hypersensitivity reactions after contrast administration' may be followed prior to examinations using nonvascular CM administration, if possible after laboratory and skin testing by a specialist in drug allergy prior to the examination.

Overwegingen

1. Gastro-intestinal administration

Barium sulphate suspensions are used more and more infrequently in fluoroscopy than in the 1970 and 1990s. Commercial barium sulphate suspensions are inert and not absorbed by the gastrointestinal mucosa. Trace amounts of barium ions may be absorbed by mucosa and stored in soft tissue or bone (Skucas 1997). Hypersensitivity reactions to barium sulphate are exceedingly rare and are usually mild. They have been estimated to occur in about 1 : 1,000,000 cases (Janower, 1986). Yet, severe reactions have been published as case reports in the heyday of barium use, but are exceedingly rare (Seymour, 1997).

It is probable that hypersensitivity reactions are not true reactions to barium sulphate but rather to additives of the commercial barium preparations such as methylparaben or carboxymethylcellulose. In addition, they may also be attributed to the use of glucagon in upper or lower GI studies (Gelfand, 1985).

Iodine-based contrast media (ICM) are widely used in CT to opacify and/or distend the stomach and bowel structures, either via oral intake, via a nasogastric or nasoduodenal tube, or via direct rectal administration. The use of fluoroscopy of the GI system is rapidly declining. The use of (CT) fistulography for entero-cutaneous

fistula is also included here.

For high-density (positive) contrast, the older high-osmolar ionic ioxithalamate meglumine and sodium meglumine amidotrizoate are still widely used for this purpose. In CT, water or low-density (negative) CM (Mannitol or PEG) are used more frequently.

In contrast to barium sulphate, small amounts of iodine-based CM are absorbed by the gastro-intestinal mucosa (in the order of 0 to 2%) (Sohn, 2002), with relatively more absorption in the upper than in the lower gastrointestinal system. This absorption may be slow. Therefore, also iodine-based CM can elicit hypersensitivity reactions of all severities, both acute and delayed reactions (Miller, 1997; Schmidt, 1998; Davis, 2015; Böhm, 2017). There is no convincing data that inflammation or ischemia of bowel walls lead to more hypersensitivity reactions.

Angioedema may also occur in the small bowel and is often under diagnosed as it results in atypical abdominal discomfort (Chen, 2012; Hu, 2012). It is probably more frequently caused by intravascular ICM and GBCA administration, and may be mediated via the gut-associated lymphoid tissue (GALT) in the bowel wall (Böhm, 2017).

Because iodine-based CM in CT is usually administered intravenously and orally, the true incidence of gastro-intestinal CM administration is difficult to determine. As published cases are limited to case reports, the incidence is probably very low, much lower than the incidence after intravascular iodine-based CM administration.

Gadolinium-based contrast agents (GBCA) are only rarely used for gastrointestinal use in everyday practice. These GBCA can be absorbed by gastro-intestinal mucosa in small amounts. Given the very low incidence of hypersensitivity reactions to intravascular GBCA, the risk of hypersensitivity reactions is largely theoretical.

2. Urogenital administration

Iodine-based contrast media are used for a variety of fluoroscopic urologic procedures such as cystography, pyelography, nephrostomography, urinary diversions and neobladders, urodynamic examinations, or retrograde urethrography.

As in gastro-intestinal applications, the urothelium can also absorb these CM in small amounts (Davis, 2015), with a potentially higher rate if CM is injected under pressure or if drainage of CM is slow. Therefore, urologic administration can elicit hypersensitivity reactions of variable severity (Weese, 1993; Miller, 1995), even breakthrough reactions (Armstrong, 2005). As shown by one large published series and selected case reports, the incidence of reactions is low (Cartwright, 2008). Nevertheless, in a recent survey with a low response rate by members of the Society of Endourology, hypersensitivity reactions were reported by a considerable number of selected respondents during their careers (Dai ,2018).

In hysterosalpingography the incidence of hypersensitivity reactions following use iodine-based CM is very low, even after venous intravasation (Sanfilippo, 1978; Lindequist, 1991; La Fianza, 2005).

Gadolinium-based contrast agents are virtually never used directly for urogenital procedures and no data on hypersensitivity is available.

3. Biliary system administration

Iodine-based contrast media are mainly used during diagnostic or interventional endoscopic retrograde cholangiopancreatography (ERCP) and in percutaneous transhepatic cholangiography (PTC) with or without drain (PTCD) placements.

There is some systemic absorption of CM after ERCP in the biliary tract, in which the contrast can be detected in the kidneys afterwards. Therefore, also biliary procedures may elicit hypersensitivity reactions to iodine-based CM. However, as shown in the largest published series, the incidence of hypersensitivity reactions during ERCP is very low, even in high-risk patients (Dragonov, 2008; Trottier-Tellier, 2018).

Gadolinium-based contrast agents are virtually never used directly for biliary procedures and no data on hypersensitivity is available.

4. Intra-articular administration

Iodine-based contrast media are frequently used for arthrography, single/double-contrast CT arthrography or to help guide needle placement in MR Arthrography.

The intra-articular contrast can be absorbed in small amounts by the synovium. Hypersensitivity reactions have been described with severe reactions occurring in incidental patients (Newberg, 1985; Westesson, 1990; Hugo III, 1998). However, in two large surveys of 126,000 and 262,000 arthrograms the risk of hypersensitivity reactions was low, and most reactions were mild (Newberg, 1985; Hugo III, 1998).

Gadolinium-based contrast agents are used for MR arthography in a very diluted amount (2 mmol/L or a 1:250 dilution).

Similar to iodine-based CM, trace amounts of GBCA can be absorbed by synovium. However due to the dilution the number of hypersensitivity reactions following MR arthrography is almost non-existent (Schulte-Altedorneburg, 2003).

5. Miscellaneous

Iodine-based contrast media are or have been used for a number of miscellaneous procedures like (CT) discography, sialography, et cetera.

Hypersensitivity reactions in most of these procedures are not documented well enough to discuss them in this guideline, or have fallen in disfavour.

Inleiding

There was few good data to structurally search and critically assess the literature on hypersensitivity reactions after nonvascular contrast media (CM) administration, such as gastro-intestinal administration, urogenital administration, intrabiliairy administration, and intra-articular administration.

Therefore, the guideline committee decided that it was more appropriate to provide an expert-opinion review of the available literature separately and to try to provide recommendations for practice.

Verantwoording

Laatst beoordeeld   : 24-06-2020
Laatst geautoriseerd : 24-06-2020

Voor de volledige verantwoording, evidence tabellen en eventuele aanverwante producten raadpleegt u de Richtlijnendatabase.

Referenties

Armstrong PA, Pazona JF, Schaeffer AJ. Anaphylactoid reaction after retrograde pyelography despite preoperative steroid preparation. Urology 2005; 66: 880.

Böhm I, Morelli J, Nairz K, Silva Hasembank Keller P, Heverhagen JT. Risks of contrast media applied via the gastrointestinal route. Eur J Intern Med 2017; 42: e19-e21

Cartwright R, Cardozo L, Durling R. A retrospective review of a series of video-urodynamic procedures, with respect to the risk of anaphylactoid reactions. Neurourol Urodyn 2008; 27: 559

Chen CK, Chang HT, Chen CW, et al. Dynamic computed tomography of angioedema of the small bowel induced by iodinated contrast medium: prompted by coughing-related motion artifact. Clin Imaging 2012; 36: 386-389

Dai JC, Brisbane WG, Chang HC, Hsi RS, Harper JD. Anaphylactoid reactions after instillation of contrast material into the urinary tract: a survey of contemporary practice patterns and review of the literature. Urology 2018; 122: 58-63.

Davis PL. Anaphylactoid reactions to the nonvascular administration of water-soluble iodinated contrast media. AJR Am J Roentgenol 2015; 204: 1140–1145.

Draganov PV, Forsmark CE. Prospective evaluation of adverse reactions to iodine-containing contrast media after ERCP. Gastrointest Endosc 2008; 68: 1098-1101.

Gelfand DW, Sowers JC, DePonte KA, Sumner TE, Ott DJ. Anaphylactic and allergic reactions during double-contrast studies: is glucagon or barium suspension the allergen? AJR Am J Roentgenol 1985; 144: 405-406.

Hu XH, Gong XY, Hu P. Transient small bowel angioedema due to intravenous iodinated contrast media. World J Gastroenterol 2012; 18: 999–1002.

Hugo III PC, Newberg AH, Newman JS, Wetzner SM. Complications of arthrography. Semin Musculoskelet Radiol 1998; 2: 345–348.

Janower ML. Hypersensitivity reactions after barium studies of the upper and lower gastrointestinal tract. Radiology 1986; 161: 139-140.

La Fianza A, Camilla F. Venous-lymphatic intravasation during hysterosalpingography using hydrosoluble contrast medium: a technique with no complications. J Women's Imaging 2005; 7: 38–43.

Lindequist S, Justesen P, Larsen C, Rasmussen F. Diagnostic quality and complications of hysterosalpingography: oil- versus water-soluble contrast media--a randomized prospective study. Radiology 1991; 179: 69-74.

Miller KT, Moshyedi AC. Systemic reaction to contrast media during cystography. AJR Am J Roentgenol 1995; 164: 1551.

Miller SH. Anaphylactoid reaction after oral administration of diatrizoate meglumine and diatrizoate sodium solution. AJR Am J Roentgenol 1997; 168: 959–961.

Newberg AH, Munn CS, Robbins AH. Complications of arthrography. Radiology 1985; 155: 605–606.

Sanfilippo JS, Yussman M, Smith O. Hysterosalpingography in the evaluation of infertility: a six year review. Fertil Steril 1978; 30: 636–643.

Schmidt BJ, Foley WD, Bohorfoush AG. Toxic epidermal necrolysis related to oral administration of diluted diatrizoate meglumine and diatrizoate sodium. AJR 1998; 171: 1215–1216.

Schulte-Altedorneburg G, Gebhard M, Wohlgemuth WA, et al. MR arthrography: pharmacology, efficacy and safety in

clinical trials. Skelet Radiol 2003; 32: 1–12.

Seymour PC, Kesack CD. Anaphylactic shock during a routine upper gastrointestinal series. AJR Am J Roentgenol 1997;168:957–958.

Skucas J. Anaphylactoid reactions with gastrointestinal contrast media. AJR Am J Roentgenol 1997; 168: 962–964.

Sohn KM, Lee SY, Kwon OH. Renal excretion of ingested Gastrografin: clinical relevance in early postoperative treatment of patients who have undergone gastric surgery. AJR 2002; 178: 1129–1132.

Trottier-Tellier F, Harvey L, Baillargeon JD. Risk evaluation of endoscopic retrograde cholangiopancreatography-related contrast media allergic-like reaction: a single centre experience. Can J Gastroenterol Hepatol 2018; 2018: 6296071.

Weese DL, Greenberg HM, Zimmern PE. Contrast media reactions during voiding cystourethrography or retrograde pyelography. Urology 1993; 41: 81–84.

Westesson PL, Manzione JV. Reaction to nonionic contrast medium during arthrography of the temporomandibular joint. AJR Am J Roentgenol 1990; 154: 1344.

Nephrotoxicity of Gadolinium-Based Contrast Agents

Uitgangsvraag

How can PC-AKI be prevented after administration of Gadolinium-Based (Gd) Contrast Agents (GBCA)?

Subquestions:

1. Is administration of Gadolinium-Based (Gd) Contrast Agents (GBCA) associated with an increased risk of post contrast acute kidney injury (PC-AKI) compared to placebo/unenhanced imaging?
2. Is there a difference in the risk of PC-AKI between high and low dosage of GBCA?
3. Is there a difference in the risk of PC-AKI between different GBCA?

Aanbeveling

Make an individual risk-benefit analysis with the patient's requesting physician and nephrologist to ensure a strict indication for gadolinium-enhanced MRI with linear GBCA in patients with eGFR < 30 ml/min/1.73m2.

Take optimal CM dosing based on patient weight into account in local dosing protocols for diagnostic MRI examinations.

Do not use prophylactic measures to avoid the development of PC-AKI in high-risk patients (eGFR<30ml/min/1.73m2) receiving GBCA intravenously at the appropriate dose.

Do not substitute ICM with GBCA in order to avoid PC-AKI in computed tomography and/or digital subtraction angiography.

Overwegingen

Compared to the large amount of literature of the incidence and prevention of PC-AKI after administration of Iodine-based contrast media (ICM), little is known on this subject after administration of GBCA. In general, it is said that GBCA are less nephrotoxic than ICM, and the above-described literature seems to acknowledge that.

It is generally recommendable to use the lowest GBCA dose needed to achieve a diagnostic examination, and usually the standard dose of 0.1 mmol/kg suffices for most clinical indications (ESUR 2017).

Looking more deeply into the chemistry of CM and the results of experimental studies, another picture emerges (Nyman, 2002). First of all, ICM concentrations are expressed in mgI/ml and GBCA concentrations in mmol/ml, a fundamental difference. One mol of Iodine atoms corresponds to 126.9g of I, whereas 1 mol of Gd atoms corresponds to 157.3g of Gd. As most of the commercially available GBCA are 0.5mmol/ml, they thus contain 78.65 mg/ml of Gd. When it comes to Iodine, 0.5mmol/ml I, corresponds to 63mgI/ml. But ICM are usually used in concentrations ranging from 300mg/ml - 400mg/ml, i.e. 2.36mmol/ml - 3.15 mmol/ml. The commercially available iodine doses are thus much higher than the commercially available gadolinium doses (Nyman, 2002).

Furthermore, GBCA contain one attenuating Gd atom per molecule, whereas ICM monomers contain 3

attenuating I atoms per molecule and ICM dimers contain 6 attenuating I atoms per molecule. The combination of more attenuating atoms per molecule and the difference in attenuation of Gd and I at different photon energies, results in the fact that at 120 kVp CT, approximately 110mgI/ml monomer equally attenuates with 0.5mmol/ml Gd. At 80kVp CT, approximately 95mgI/ml monomer equally attenuates with 0.5mmol/ml Gd (Nyman 2002). For DSA a concentration of 60 to 80mg/ml I monomer, produces the same attenuation as 0.5mmol/l GBCA at commonly used 70-90 kVp range (Nyman, 2002).

Thus, in order to achieve the same amount of attenuation in CT with an ICM monomer 300mg/ml, a triple Gd 0.5mmol/ml dose has to be administered. This also means that DSA attenuation produced by an ICM monomer 300mg/ml is achieved with a 4 - 5 times higher Gd 0.5mmol/ml dose. The above results show that changing from ICM to GBCA in CT and DSA is not a safe option due the 3 to 5 times higher GBCA doses necessary to achieve the same amount of attenuation.

Therefore, the working group concludes that, especially in interventional radiology, using GBCA would potentially lead to more harmful effects compared to ICM, and would not recommend substituting ICM with GBCA. This is in line with a systematic review in which the authors concluded that GBCA does not appear to be safer than iodinated contrast in patients at risk of PC-AKI (Boyden, 2008).

As the dose to achieve significant enhancement for GBCA in MRI is much lower as in CT and DSA, it is not a surprise that the small amount of available literature shows no indication of PC-AKI after the administration of GBCA at the recommend standard dose of 0,1 mmol/kg.

Therefore, the working group sees no additive value in using any prophylactic measures (such as hydration, as described in part 1 of the guideline), and recommends not to use any. A recent Canadian guideline on GBCA in chronic kidney disease states that a standard dose of GBCA in patients with eGFR 30 to 60 is safe and no additional measures are necessary. In patients with eGFR <30 ml/min/1.73m^2 and patients on dialysis, administration of GBCA should be considered individually (Schieda, 2019). Thus an individual risk-benefit analysis with the patient's requesting physician and nephrologist should be made to ensure a strict indication for gadolinium-enhanced MRI with linear agents in patients with eGFR < 30 ml/min/1.73m^2.

Inleiding

From laboratory testing on cell lines and animals, it is known that Gd chelates are nephrotoxic. In daily practice, this nephrotoxicity is not an issue, as the required dose of these chelates is usually too low to lead to nephrotoxicity in patients.

Conclusies

Very low GRADE	Administration of macrocyclic gadolinium-based contrast agents does not seem to be associated with an increased risk of PC-AKI. *Sources: (Deray, 2013; Kroencke 2001; Tombach 2001; Tombach 2002)*

Very low GRADE	Administration of linear gadolinium-based contrast agents does not seem to be associated with an increased risk of PC-AKI. *Sources: (Broome 2007; Deray, 2013; Gok Oguz, 2013; Kittner 2007; Naito 2017; Townsend, 2000; Trivedi, 2009)*

Very low GRADE	It is unknown whether administration of macrocyclic gadolinium-based contrast agents is associated with an increased requirement of dialysis. *Source: (Deray, 2013)*

Very low GRADE	It is unknown whether administration of linear gadolinium-based contrast agents is associated with an increased requirement of dialysis. *Source: (Townsend, 2000)*

Very low GRADE	There seems to be no dose-response association between macrocyclic gadolinium-based contrast agents and PC-AKI. *Sources: (Kroencke, 2001; Tombach, 2001; Tombach, 2000)*

Very low GRADE	There seems to be no dose-response association between gadolinium-based contrast agents and PC-AKI. *Sources: (Broome 2007; Kittner 2007)*

Very low GRADE	It is unknown whether there is a difference in the risk of PC-AKI between different gadolinium based contrast agents *Source: (Naito, 2017)*

Samenvatting literatuur

1. Gadolinium- Based Contrast Agents versus placebo/unenhanced imaging

Macrocyclic GBCA

Deray (2013) describe a prospective multicentre non-randomized study, comparing the renal safety of Gd-DOTA (macrocyclic GBCA) enhanced MRI with non-enhanced MRI in 114 patients with eGFR 15 - 60 ml/min/1.73 m^2(Deray, 2013).Gd-DOTA was injected intravenously by a power injector at a dose of 0.1 mmol/kg. PC-AKI was defined as an increase in SC of at least 25% or 44.2mmol/kg above the baseline value. Serum creatinine levels were measured 72±24 hours after the MRI.

Linear GBCA

In a randomized controlled trial by Townsend (2000) 32 patients were included. They were divided into 2 categories, eGFR 30-60 (group 1) and eGFR 10 to 29 ml/min/1.73m^2 (group 2) (Townsend, 2000). Patients in both groups were randomized to be infused with either Gd-BOPTA (linear GBCA) or saline, both at a dose of 0.2 mmol/kg. Both groups maintained saline infusion after the initial bolus and received a total of 250-300 ml saline. No MRI took place after the injection. PC-AKI was defined as an increase in serum creatinine (SC) > 44,2 μmol/l above the baseline value. SC was measured before the injection and for 7 consecutive days after the injection. In group 1, 9 patients received Gd and 6 saline, in group 2, 11 patients received Gd and 6 saline.

Gok Oguz (2013) describes 144 patients with 1 or more risk factors for AKI (advanced age (> 75 years), diabetes mellitus, chronic kidney disease, congestive heart failure, using other nephrotoxins, and hypotension) in a prospective case-control study (Gok Oguz, 2013). Patients were divided into 2 groups, but the article does not state clearly what the criteria are to be included in either one of the groups. All 72 patients (mean eGFR 36 ml/min/1.73m^2) in group 1 received intravenous injection with Gd-DTPA (linear GBCA), whereas all 72 patients (mean eGFR 39 ml/min/1.73m^2) in group 2 received no Gd contrast. PC-AKI was defined as an increase of SC of at least 26.4 μmol/l or ≥ 50% from baseline. Before the MRI and at 6 h, 24 h, 72 h, and 168 h after the MRI, SC was measured.

Trivedi (2009) describe a retrospective study that included 162 patients who underwent MRI with gadodiamide (linear GBCA) and 125 controls that underwent unenhanced MRI (Trivedi, 2009). Patients were included when SC measurements were available during 7 days preceding MRI and 48 to 72 hours after MRI. Baseline eGFR was 103.1 +/- 49.5 ml/min/1.73m^2 in the group receiving Gd and 103.4 +/- 48.4 ml/min/1.73m^2 in the control group. PC-AKI was defined as SC >44.2 micromol/l compared to baseline.

<u>Results</u>
Outcome Post-Contrast Acute Kidney Injury (PC-AKI)
Four studies (Townsend, 2000, Deray, 2013, Gok Oguz, 2013 and Trivedi, 2009) reported on the incidence of PC-AKI after administration of GBCA. Due to the heterogeneity in study designs the results were not pooled.

Macrocyclic GBCA
Deray (2013) reported PC-AKI in one patient after injection with macrocyclic Gd-DOTA (1.4%).

Linear GBCA
There were no cases of PC-AKI in the studies Gok Oguz (2013), Townsend (2000) and Trivedi (2015) using a variety of linear GBCA.
<u>Quality of evidence</u>
The quality of certainty of evidence was graded as very low due to high risk of bias (see Table Risk of Bias assessment, downgraded by one point) and low number of patients (imprecision downgraded by two points).

<u>Outcome Dialysis</u>
Two studies reported on the requirement of dialysis after administration of GBCA. Both studies (Townsend, 2003 (linear GBCA) and Deray, 2013 (Macrocyclic GBCA)) reported that no subjects required dialysis.

<u>Quality of evidence</u>

The quality of certainty of evidence was graded as very low due to the low number of patients (imprecision downgraded by two points).

No studies reported on the outcome mortality.

2. High versus low dose of Gadolinium-Based Contrast Agents
Macrocyclic GBCA
Kroencke (2001) randomized 94 patients with suspected abnormality of the abdominal aorta or renal arteries to MR angiography after the IV injection of one of four doses of gadobenate dimeglumine (0.025, 0.05, 0.1, and 0.2 mmol/kg of body weight), a macrocyclic GBCA (Kroencke, 2001). SC was obtained pre-dose and at the 24-hr follow-up examination.

Tombach (2001) describe 21 patients in a randomized controlled, open-label trial. Patients were classified into two subgroups according to their creatinine clearance: group 1 (n=12), eGFR 30 to 80 ml/min/1.73m^2 and group 2 (n =9), eGFR<30 ml/min/1.73m^2(Tombach, 2001). Then, patients were randomly assigned to receive the higher dose of 0.3 mmol/kg of the macrocyclic GBCA gadobutrol (group 1, n=6/12; group 2, n=4/9) or the lower dose of gadobutrol of 0.1 mmol/kg (group 1, n=6/12; group 2,n=5/9). Changes in vital signs, clinical chemistry, and urinalysis results, including creatinine clearance, were monitored before, at 6 hours, and then every 24 hours until 72 hours (group 1) or 120 hours (group 2) after intravenous injection of gadobutrol.

Tombach (2002) enrolled 11 patients with end-stage renal failure who required haemodialysis treatment (Tombach, 2002). Purpose of the study was to assess the safety and dialysability of gadobutrol. Gadobutrol (1 mol/L) was injected intravenously at randomly assigned doses of either 0.3 or 0.1 mmol of gadolinium per kilogram of body weight for contrast-enhanced MR imaging.

Linear GBCA
Kittner(2007) randomized patients with suspected renal artery stenosis to 0.01, 0.05, 0.1, or 0.2 mmol/kg of the linear GBCA gadodiamide (n=69, 67, 69 and 61, respectively) (Kittner, 2007).Safety of gadodiamide was monitored by comparing the data of 12-lead ECGs, vital signs (blood pressure, body temperature, heart and respiratory rate), serum biochemistry (including renal parameters), and physical examinations collected immediately before and 24 h after gadodiamide administration.

Broome (2007) retrospectively studied the dialysis and MRI records (Broome, 2007). One hundred eighty six dialysis patients underwent 559 MRI exams; including 301 Gd enhanced MRI between 2000 and 2006. The linear GBCA gadodiamide was the sole Gd chelate used in either 0.1 mmol/kg or 0.2 mmol/kg.

Results
Outcome Post-Contrast Acute Kidney Injury (PC-AKI)
Five studies reported on the incidence of PC-AKI (Kroencke, 2001; Tombach, 2001, Tombach, 2002, Kittner, 2007 and Broome 2007). All five studies reported no cases of PC-AKI, using either linear or macrocyclic GBCA.

Quality of evidence

The quality of certainty of evidence was graded as very low due to high risk of bias (see Table Risk of Bias assessment, downgraded by one point) and the low number of patients (imprecision downgraded by two points).

No studies reported on the outcomes dialysis and mortality.

<u>3. Nephrotoxicity of different gadolinium-based contrast agents</u>
One study investigated the difference in nephrotoxicity between different gadolinium-based contrast agents.

Naito (2017) describes a prospective randomized study including 102 patients that were randomized to either receive 0.1 mmol/kg gadodiamide (linear GBCA) or 0.1 mmol/kg Gd-DTPA (linear GBCA) (Naito, 2017). eGFR in the gadodiamide group was 90.5 +/- 19.5 ml/min/1.73m^2 and 94.1 +/- 26.4 ml/min/1.73m^2 in the Gd-DTPA group. SC was measured 16-80 hour after the procedure. PC-AKI was defined as SC ≥ 44.2 micromol/l or ≥ 30% above baseline.

<u>Results</u>
Outcome Post-Contrast Acute Kidney Injury (PC-AKI)
In both groups, no PC-AKI occurred.

<u>Quality of evidence</u>
The quality of certainty of evidence was graded as very low due to high risk of bias (see Table Risk of Bias assessment, downgraded by one point) and the low number of patients (imprecision downgraded by two points).

No studies reported on the outcomes: dialysis and mortality.

Zoeken en selecteren

To answer our clinical question a systematic literature analysis was performed.

P (Patient): patients who received Gadolinium-Based Contrast Agents (GBCA);
I (Intervention): gadolinium based contrast agents, gadoterate meglumine, gadodiamide, gadobenate dimeglumine, gadopentetate dimeglumine, gadoteridol, gadoversetamide, gadobutrol;
C (Comparison): no GBCA or another type of GBCA, gadoterate meglumine, gadodiamide, gadobenate dimeglumine, gadopentetate dimeglumine, gadoteridol, gadoversetamide, gadobutrol;
O (Outcomes): nephrotoxicity (acute and permanent), dialysis, mortality.

<u>Relevance of outcome measures</u>
The working group considered the outcomes nephrotoxicity, mortality and dialysis critical measures and outcome for the decision-making process.

The working group did not define the criteria for the outcomes a priori, but used the outcomes as defined in the studies. The working group considered a clinically relevant difference according to the standards of GRADE: a difference in relative risk of 25% for dichotomous outcomes and a difference of 10% for continuous outcomes

(GRADE handbook, web-link in references).

Methods
The databases Medline (OVID), Embase and the Cochrane Library were searched from 1st of January 1996 to March 2018 using relevant search terms for systematic reviews (SRs), randomized controlled trials (RCTs) and observational studies (OBS). The literature search produced 245 hits: 22 SR, 51 RCTs and 172 OBS. Based on title and abstract a total of 15 studies were selected. After examination of full text 7 articles were selected: 4 for subquestion 1, 2 for subquestion 2 and 1 for subquestion 3. Reasons for exclusion are reported in exclusion table (under the Tab "exclusion table"). The most relevant study characteristics of the included studies can be found in the evidence tables.

Verantwoording

Laatst beoordeeld   : 24-06-2020
Laatst geautoriseerd : 24-06-2020

Voor de volledige verantwoording, evidence tabellen en eventuele aanverwante producten raadpleegt u de Richtlijnendatabase.

Referenties

Boyden TF, Gurm HS. Does gadolinium-based angiography protect against contrast-induced nephropathy?: A systematic review of the literature. Catheter Cardiovasc Interv 2008; 71: 687 – 693.
Broome DR, Girguis MS, Baron PW, Cottrell AC, Kjellin I, et al. Gadodiamide-associated nephrogenic systemic fibrosis: why radiologists should be concerned. AJR Am J Roentgenol 2007; 188: 586–592.
Deray G, Rouviere O, Bacigalupo L, Maes B, Hannedouche T, et al. Safety of meglumine gadoterate (Gd-DOTA)-enhanced MRI compared to unenhanced MRI in patients with chronic kidney disease (RESCUE study). Eur Radiol 2013; 23: 1250–1259.
Gok Oguz E, Kiykim A, Turgutalp K, Olmaz R, Ozhan O, Muslu N, Horoz M, Bardak S, Sungur MA. Lack of nephrotoxicity of gadopentetate dimeglumine-enhanced non-vascular MRI and MRI without contrast agent in patients at high-risk for acute kidney injury. Med Sci Monit 2013; 19: 942-8.
GRADE handbook: https://gdt.gradepro.org/app/handbook/handbook.html
Kittner T, Rudolf J, Fages JF, Legmann P, Aschauer M, Repa I, et al. Efficacy and safety of gadodiamide (Gd-DTPA-BMA) in renal 3D-magnetic resonance angiography (MRA): a phase II study. Eur J Radiol. 2007; 64: 456-64.
Kroencke TJ, Wasser MN, Pattynama PM, Barentsz JO, Grabbe E, Marchal G, et al. Gadobenate dimeglumine-enhanced MR angiography of the abdominal aorta and renal arteries. AJR Am J Roentgenol. 2002; 179: 1573-1582.
Naito S, Tazaki H, Okamoto T, Takeuchi K, Kan S, Takeuchi Y, Kamata K. Comparison of nephrotoxicity between two gadolinium-contrasts, gadodiamide and gadopentetate in patients with mildy diminished renal failure. J Toxicol Sci 2017; 42: 379 – 384.
Nyman U, Elmståhl B, Leander P, Nilsson M, Golman K, Almén T. Are Gadolinium-based contrast media really safer than iodinated media for digital subtraction angiography in patients with azotemia? Radiology 2002; 223: 311- 318.
Schieda N, Maralani PJ, Hurrell C, Tsampalieros AK, Hiremath S. Updated clinical practice guideline on use of Gadolinium-Based Contrast Agents in kidney disease issued by the Canadian Association of Radiologists. Can Assoc Radiol J 2019; in press. doi: 10.1016/j.carj.2019.04.001Tombach B, Bremer C, Reimer P, Kisters K, Schaefer RM, Geens V, Heindel W.Renal tolerance of a neutral gadolinium chelate (gadobutrol) in patients with chronic renal failure: results of a randomized study. Radiology 2001; 218(3): 651-7.
Tombach B, Bremer C, Reimer P, Matzkies F, Schaefer RM, Ebert W, Geens V, Eisele J, Heindel W. Using highly concentrated gadobutrol as an MR contrast agent in patients also requiring hemodialysis: safety and dialysability. AJR Am J Roentgenol. 2002; 178: 105-9.

Townsend RR, Cohen DL, Katholi R, Swan SK, Davies BE, Bensel K, Lambrecht L, Parker J. Safety of intravenous gadolinium (Gd-BOPTA) infusion in patients with renal insufficiency. Am J Kidney Dis. 2000; 36:1207-12.

Trivedi H, Raman L, Benjamin H, Batwara R. Lack of nephrotoxicity of gadiodiamide in unselected hospitalized patients. Postgrad Med 2009; 121: 166 – 170.

Risk Factors and Prevention of NSF

Uitgangsvraag

a. Which patients are at-risk for Nephrogenic Systemic Fibrosis (NSF)?
b. Which measures are necessary to prevent Nephrogenic systemic fibrosis?

Aanbeveling

Use low-risk (ionic and non-ionic) **macrocyclic** GBCAs for medical imaging in all patients. Linear GBCAs have been associated with NSF, therefore, consider **linear** agents only if a macrocyclic agents cannot answer the diagnostic question.

Make an individual risk-benefit analysis with the patient's requesting physician and nephrologist to ensure a strict indication for gadolinium-enhanced MRI using **linear** agents in patients with eGFR < 30 ml/min/1.73m^2.

For prevention of NSF in patients who are already dependent on haemodialysis or peritoneal dialysis, the administration of **macrocyclic** GBCA does not have to be followed by an immediate haemodialysis session.

To limit the amount of circulating GBCA, in hemodialysis patients the administration of **linear** GBCA should be followed immediately by a (high-flux) haemodialysis session, which is repeated on the following two days.

In predialysis patients (eGFR<15 ml/min/1.73m^2) and peritoneal dialysis patients, the risk of NSF due to **linear** GBCA should be weighed against the risk of placement of a temporary haemodialysis catheter.

Overwegingen

Prevalence and risk of NSF and type of GBCA

The majority of histology proven NSF cases has been described between 1997 and 2007, which largely consisted of cases with a temporal relation with high dose linear gadolinium-based contrast agent (GBCA) administrations (Attari, 2019). Several meta-analysis have shown a positive correlation between GBCA and NSF, predominantly based on studies using linear GBCA (Agarwal, 2009; Zhang, 2015). The risk of NSF relate to the administered dose and physiochemical characteristics of GBCAs, including pharmacodynamic stability, kinetic stability, and the amount of excess ligand (Khawaja, 2015).

In a risk-factor analysis of 370 biopsy-proven published NSF cases following use of linear GBCA it was concluded that reductions in risk may be attained with: 1) avoiding high doses of GBCA (> 0.1 mmol/kg); 2) avoiding nonionic linear GBCA in patients undergoing dialysis and patients with eGFR < 30 ml/min/1.73m^2, especially in the setting of pro-inflammatory conditions; 3) dialyzing quickly after GBCA administration for patients already on dialysis; and 4) avoiding GBCA in acute renal failure (Zou, 2011).

By combining pharmacovigilance (Food and Drug Administration Adverse Event Reporting System (FAERS)) and legal databases, a total of 382 biopsy-proven, product-specific cases of NSF were analysed. Of these, 279 cases were unconfounded and all involved a linear GBCA, nonionic more than ionic, and most frequently

gadodiamide. No unconfounded cases were found for gadoteridol or gadobenate (Edwards, 2014).

A very recent study based on a legal database containing biopsy-proven, unconfounded NSF cases has estimated that a total of 197 and 8 cases have been reported for the linear GBCAs gadodiamide and gadoversetamide, respectively. Estimated incidences of NSF based on the FAERS analysis are 13.1/million and 5.0/million administrations for the linear non-ionic GBCAs gadodiamide and gadoversetamide worldwide (Semelka, 2019).

Considering the hypothesized pathophysiology of NSF involving free circulating gadolinium ions, macrocyclic GBCAs are considered to have a higher thermodynamic and kinetic stability and thus less associated with the risk of NSF (Sherry, 2009).

The prevalence of NSF after use of macrocyclic GBCA is very low. No cases of NSF have been found in large studies using gadobenate (Bruce, 2016), gadobutrol (Michaely, 2017), and gadoteridol or gadobenate (Soulez, 2015). Using the Girardi criteria for diagnosis, the worldwide total number of unconfounded cases for gadobutrol is 3 (Elmholdt, 2010; Endrikat, 2018), while there were no cases for gadoteridol (Reilly, 2008; Edwards, 2014), or gadoterate (Soyer, 2017).

In addition, there have been no unconfounded cases reported for the hepatobiliary linear GBCA gadobenate (Edwards, 2014) and gadoxetate (Endrikat, 2018). Patients with chronic liver diseases that are awaiting or undergoing liver transplantation are no longer consider to be an independent risk factor for NSF (Smorodinsky, 2015).

On March 17, 2016, the European Medicines Agency (EMA) initiated a review of the risk of gadolinium deposition in brain tissue following the repeated use of GBCAs in patients undergoing contrast-enhanced MRI scans. Following an in-depth review, the EMA issued its final recommendations on July 21, 2017, endorsed by the European Commission on November 23, 2017, and now applicable in all EU Member States limiting the use of GBCAs to macrocyclic GBCAs and restricting the use of linear GBCAs to selected indications, such as hepatobiliary MRI or MR arthrography (EMA, 2017; Dekkers, 2018). See Table 1 for overview of GBCAs and recommendations of the EMA.

Table 1 Overview of available GBCAs and the EMA recommendation (Dekkers, 2018)

Gadopentetate

Gadobenate
Gadoxetate
Gadodiamide
Gadoversetamide
Gadoterate

| Gadoteridol |
| Gadobutrol |

Considering these new regulations, previous perceived risks for NSF based on linear GBCAs should be differentiated from the risks that apply to macrocyclic GBCAs. From the data currently available, for the GBCA currently allowable in Europe the risk of NSF is extremely low, even in patients with eGFR < 30 ml/min/1.73m^2 and patients on dialysis.

Haemodialysis to prevent NSF
Several studies have been performed to investigate the dialysability of GBCAs. These studies have shown that a single haemodialysis session can remove around 65-97% of circulating GBCA, whereby success depends on dialysis technique (high flux, large pore membranes (Ueda 1999)). Approximately 98% is eliminated after three consecutive dialysis sessions (Joffe 1998; Tombach 2002; Gheuens 2014). Based on these data, early haemodialysis would be an effective treatment for preventing NSF. However, this hasn't been proven. For example, a retrospective chart review described ten haemodialysis patients who developed NSF after administration of GBCA. In none of these patients, immediate haemodialysis after injection with GBCA could prevent NSF (Broome 2007).

Based on the dialysability of GBCAs and the fact that NSF is a potential lethal condition, many guidelines recommend scheduling GBCA administration shortly before the next haemodialysis session (ACR Manual 10.3; ESUR Guideline v10).

Peritoneal dialysis does not effectively remove gadolinium (Rodby 2018). However, instituting haemodialysis in a peritoneal dialysis patient without a functioning vascular access goes with a significant risk, as it is an invasive treatment that requires placement of a temporary haemodialysis catheter. The same accounts for predialysis patients (eGFR<15 ml/min/1.73m^2).

Inleiding

Nephrogenic systemic fibrosis (NSF) is a very rare, idiopathic, progressive, systemic fibrosis disease that has been associated with renal insufficiency and could result in significant disability due to scleromyxedema-like cutaneous manifestations and mortality. Since there is currently no consistently effective treatment, NSF prevention would be essential, ideally by confirming risk factors for the disease.

Risk factors for NSF
Little is known about the pathophysiology of NSF and it has been postulated that the deposition of free gadolinium causes fibrous connective tissue formation (Ting, 2003). It has been described to occur after exposure to linear gadolinium based contrast agents (GBCA) in particular. Literature published prior to 2007 has not only suggested that free gadolinium, particularly gadodiamide, is a trigger of NSF, but has reported a strong causal relationship between gadolinium exposure and the development of NSF (Thomsen, 2016). However, this association may be affected by other factors or cofactors, such as dosage or type of GBCA, dialysis modality, renal disease severity, liver transplantation, chronic inflammation, or accelerated atherosclerosis.

Prevention of NSF
Several measures to prevent the development of NSF can be taken. As such, the use of high risk and high dose GBCAs should be avoided. An alternative to scanning with GBCA is to scan with the use of iodinated contrast media, however this carries the risk of post-contrast acute kidney injury (see Module 6). Since the connection between NSF and GBCA has become known, changes in CM administration protocols with lower GBCA concentration and use of macrocyclic GBCAs has led to a decrease in NSF incidence. Reports are showing virtually no new NSF cases since 2008 in both patients with normal renal function and patients with renal impairment, in spite of continued use of GBCA, albeit at lower doses and by using preferentially the macrocyclic preparations.

Conclusies

Very low GRADE	There seems to be no association between co-morbidities (history of hypothyroidism or deep venous thrombosis, and dependent oedema) and risk of nephrogenic systemic fibrosis in patients on dialysis receiving linear GBCAs. *Source: (Kallen, 2008))*

Samenvatting literatuur

Research question a: Risk factors for NSF
Studies that assessed risk factors related to administration of type and dose of gadolinium-based contrast agents (GBCA) have been described in the module nephrotoxicity of gadolinium-based contrast agents. There was 1 additional study included investigating other potential factors associated to NSF. Kallen (2008) performed a matched case-control study (19 cases and 57 controls), however this study was restricted to linear GBCAs only. Participants were dialysis patients with and without a diagnosis of NSF treated at an academic medical centre.

Results

Outcome- comorbidities
In a multivariate analysis Kallen (2008) found no association between NSF and selected exposures (history of hypothyroidism (OR, 95% CI: 4.18 0.66 to 26.57); history of deep venous thrombosis (OR, 95% CI: 3.37 0.60-18.85), and dependent oedema (OR, 95% CI: 3.15 0.67 to 14.77).

Quality of evidence
The quality of certainty of evidence was downgraded from high to very low: downgraded by two levels due to imprecision (small number of patients), and indirectness (NB. only linear GBCAs were administered to the patients in the study which are no longer available on the European Market).

Research question b: Prevention of NSF
Not applicable. There were no studies investigating the research question and meeting the selection criteria.

Zoeken en selecteren

Research question a: Risk factors for NSF
To answer the clinical question a systematic literature analysis was performed:
Search question: What factors are related to an increased risk on Nephrogenic systemic fibrosis?

P (Patient): patients with reduced kidney function or other potential risk factors that are scheduled to receive intravascular contrast media;
I (Intervention): patients with potential risk factors for NSF: Patient-related, pre-existing chronic kidney disease, Renal insufficiency, chronic CKD, Age 70 years and older, Liver transplantation, Liver failure, Kidney transplantation, Chronic inflammation, Atherosclerosis, Peripheral arterial disease, Dialysis, Renal replacement therapy, Diabetes Mellitus, type 1 or type 2, Congestive heart failure NYHA grade III-IV, Dehydration, Multimorbidity, Concurrent use of nephrotoxic medications: NSAIDs, Cox-2 inhibitors, ACE-inhibitor, ARB-blocker, other Dialysis modality (Peritoneal or haemodialysis), Recent dialysis shunt / PD catheter, Acidosis, EPO use, Dose of contrast and type of contrast (GBCA);
C (Comparison): patients without potential risk factors for NSF;
O (Outcomes): frequency of NSF, systemic fibrosis, scleroderma, dialysis-associated systemic fibrosis.

Relevant outcome measures
The working group considered nephrogenic systemic fibrosis as a critical outcome measure for the decision making process.

Methods
The databases Medline (OVID) and Embase were searched from January 2000 till February 23th 2018 using relevant search terms for systematic reviews (SRs), randomized controlled trials (RCTs) and observational studies (OBS).

The literature search procured 228 hits: 22 SR, 20 RCTs and 186 OBS. Based on title and abstract a total of 20 studies were selected. After examination of full text 19 studies were excluded and 1 study involving linear

GBCAs was included in the literature summary. No studies were identified involving macrocyclic GBCAs, which are currently the only agents available in the European market.

Research question b: Prevention of NSF

To answer the clinical question a systematic literature analysis was performed for the search question: What is the effect of the different measures to prevent nephrogenic systemic fibrosis in patients who have an increased risk of developing nephrogenic systemic fibrosis and who receive contrast with gadolinium?

P (Patient): patients exposed to gadolinium-based contrast agents who have an increased risk of developing nephrogenic systemic fibrosis (NSF);
I (Intervention): measures for prevention of NSF;
C (Comparison): no measures or other measures for prevention of NSF;
O (Outcomes): nephrogenic systemic fibrosis (NSF), mortality.

Relevant outcome measures

The working group considered Nephrogenic systemic fibrosis (NSF) and mortality as critical outcome measures for the decision making process.

Methods

The databases Medline (OVID) and Embase were searched from January 1996 till March 23th 2018 using relevant search terms for systematic reviews (SRs), randomized controlled trials (RCTs) and observational studies (OBS).

The literature search procured 142 hits. 7 SR, 10 RCTs, 43 OBS, and 82 other types of studies. Based on title and abstract a total of 29 studies were selected. After examination of full text all studies were excluded and no studies have definitely been included in the literature summary.

Verantwoording

Laatst beoordeeld   : 24-06-2020
Laatst geautoriseerd : 24-06-2020

Voor de volledige verantwoording, evidence tabellen en eventuele aanverwante producten raadpleegt u de Richtlijnendatabase.

Referenties

American College of Radiology. ACR Manual on contrast media, v10.3. Available at: www.acr.org/Clinical-Resources/Contrast-Manual. Accessed: 11 july 2019

Agarwal R, Brunelli SM, Williams K, Mitchell MD, Feldman HI, Umscheid CA. Gadolinium-based contrast agents and nephrogenic systemic fibrosis: a systematic review and meta-analysis. Nephrol Dial Transplant 2009;24: 856-863.

Attari H, Cao Y, Elmholdt TR, Zhao Y, Prince MR. A systematic review of 639 patients with biopsy-confirmed Nephrogenic Systemic Fibrosis. Radiology 2019; in press. Doi: 10.1148/radiol.2019182916

Broome DR, Girguis MS, Baron PW, Cottrell AC, Kjellin I, Kirk GA. Gadodiamide-associated nephrogenic systemic fibrosis: why radiologists should be concerned. AJR Am J Roentgenol 2007; 188: 586-592 (see also correspondence)

Bruce R, Wentland AL, Haemel AK, Garrett RW, Sadowski DR, Djamali A, et al. Incidence of nephrogenic systemic fibrosis

using gadobenate dimeglumine in 1423 patients with renal insufficiency compared with gadodiamide. Invest Radiol 2016; 51:701-705

Dekkers IA, Roos R, van der Molen AJ. Gadolinium retention after administration of contrast agents based on linear chelators and the recommendations of the European Medicines Agency. Eur Radiol 2018; 28:1579-1584

Edwards BJ, Laumann AE, Nardone B, Miller FH, Restaino J, Raisch DW, et al. Advancing pharmacovigilance through academic-legal collaboration: the case of gadolinium-based contrast agents and nephrogenic systemic fibrosis-a Research on Adverse Drug Events and Reports (RADAR) report. Br J Radiol 2014; 87(1042): 20140307

Elmholdt TR, Jørgensen B, Ramsing M, Pedersen M, Olesen AB. Two cases of nephrogenic systemic fibrosis after exposure to the macrocyclic compound gadobutrol. NDT Plus. 2010; 3: 285-287 (Correspondence in NDT Plus. 2010; 3: 501-504)

Endrikat J, Dohanish S, Schleyer N, Schwenke S, Agarwal S, Balzer T. 10 years of nephrogenic systemic fibrosis: a comprehensive analysis of nephrogenic systemic fibrosis reports received by a pharmaceutical company from 2006 to 2016. Invest Radiol 2018; 53: 541-550

European Medicines Agency. EMA's final opinion confirms restrictions on use of linear gadolinium agents in body scans (21 july 2017). Available at: https://www.ema.europa.eu/en/documents/referral/gadolinium-article-31-referral-emas-final-opinion-confirms-restrictions-use-linear-gadolinium-agents_en-0.pdf

European Society of Urogenital Radiology Contrast Media Safety Committee. ESUR Guidelines on contrast safety, v10. Available at: www.esur-cm.org. Accessed: 11 july 2019

Haustein J, Schuhmann-Giampieri G. Elimination of Gd-DTPA by means of hemodialysis. Eur J Radiol 1990; 11: 227-229.

Joffe P, Thomsen HS, Meusel M. Pharmacokinetics of gadodiamide injection in patients with severe renal insufficiency and patients undergoing hemodialysis or continuous ambulatory peritoneal dialysis. Acta Radiol 1998; 5: 491–502.

Kallen AJ, Jhung MA, Cheng S, Hess T, Turabelidze G, Abramova L, et al. Gadolinium-containing magnetic resonance imaging contrast and nephrogenic systemic fibrosis: a case-control study. Am J Kidney Dis 2008; 51: 966-975.

Khawaja AZ, Cassidy DB, Al Shakarchi J, McGrogan DG, Inston NG, Jones RG. Revisiting the risks of MRI with Gadolinium based contrast agents - review of literature and guidelines. Insights Imaging 2015; 6: 553-558.

Michaely HJ, Aschauer M, Deutschmann H, Bongartz G, Gutberlet M, Woitek R, et al. Gadobutrol in renally impaired patients: results of the GRIP Study. Invest Radiol 2017; 52: 55-60

Reilly RF. Risk for nephrogenic systemic fibrosis with gadoteridol (ProHance) in patients who are on long-term hemodialysis. Clin J Am Soc Nephrol 2008; 3: 747-751.

Rodby RA. Dialytic therapies to prevent NSF following gadolinium exposure in high-risk patients. Semin Dial 2008; 21: 145-149

Semelka RC, Prybylski JP, Ramalho M. Influence of excess ligand on Nephrogenic Systemic Fibrosis associated with nonionic, linear gadolinium-based contrast agents. Magn Reson Imaging 2019; 58: 174-178.

Sherry AD, Caravan P, Lenkinski RE. Primer on gadolinium chemistry. J Magn Reson Imaging 2009; 30: 1240–1248.

Soulez G, Bloomgarden DC, Rofsky NM, Smith MP, Abujudeh HH, Morgan DE, et al. Prospective cohort study of nephrogenic systemic fibrosis in patients with stage 3–5 chronic kidney disease undergoing MRI with injected gadobenate dimeglumine or gadoteridol. AJR Am J Roentgenol 2015; 205: 469-478.

Smorodinsky E, Ansdell DS, Foster ZW, Mazhar SM, Cruite I, Wolfson T, et al. Risk of nephrogenic systemic fibrosis is low in patients with chronic liver disease exposed to gadolinium-based contrast agents. J Magn Reson Imaging 2015; 41: 1259-1267.

Soyer P, Dohan A, Patkar D, Gottschalk A. Observational study on the safety profile of gadoterate meglumine in 35,499 patients: The SECURE study. J Magn Reson Imaging. 2017 Apr;45(4):988-997.

Thomsen HS, Morcos SK, Almén T, et al. Nephrogenic systemic fibrosis and gadolinium-based contrast media: updated ESUR Contrast Medium Safety Committee guidelines. Eur Radiol 2013; 23: 307-318.

Thomsen HS. Nephrogenic systemic fibrosis: a serious adverse reaction to gadolinium – 1997-2006-2016. Part 1 Acta Radiol 2016; 57: 515-520.

Thomsen HS. Nephrogenic systemic fibrosis: a serious adverse reaction to gadolinium – 1997-2006-2016. Part 2 Acta Radiol 2016; 57: 643-648.

Ting WW, Stone MS, Madison KC, Kurtz K. Nephrogenic fibrosing dermopathy with systemic involvement. Arch Dermatol 2003; 139: 903-906.

Tombach B, Bremer C, Reimer P, Matzkies F, Schaefer RM, Ebert W, et al. Using highly concentrated gadobutrol as an MR contrast agent in patients also requiring hemodialysis: safety and dialysability. AJR Am J Roentgenol. 2002; 178: 105-109

Ueda J, Furukawa T, Higashino K, Yamamoto T, Ujita H, Sakaguchi K, Araki Y. Permeability of iodinated and MR contrast media through two types of hemodialysis membrane. Eur J Radiol. 1999; 31: 76-80

Zhang B, Liang L, Chen W, Liang C, Zhang S.An Updated Study to Determine Association between Gadolinium-Based Contrast Agents and Nephrogenic Systemic Fibrosis. PLoS One 2015; 10: e0129720.

Gadolinium Deposition in the Body and T1w Hyperintensity in the Brain

Uitgangsvraag

What is the clinical relevance of gadolinium-based contrast agent (GBCA) induced T1w hyperintensity of the nucleus dentatus and the globus pallidus in the brain?

Aanbeveling

Ensure a strict indication for gadolinium-enhanced MRI and use EMA-approved GBCA in all patients to minimize possible gadolinium deposition.

Overwegingen

The following is a short overview of the current state of gadolinium retention in the brain and body. See also the Introduction to Safe Use of Gadolinium-Based Contrast Agents.

Increased SI due to Gd deposition
Two autopsy studies, both published in 2015, showed that the increased SI on T_1-weighted sequences (T_1w) in the dentate nucleus and globus pallidus was indeed due to the presence of retained Gd (Kanda, 2015; McDonald, 2015). The majority of the Gd was localized in the perivascular spaces (4), whereas a much smaller fraction crossed the blood-brain barrier and was situated in the neural interstitium and cellular organelles (Fingerhut, 2018; McDonald 2015; McDonald, 2017_1; McDonald, 2017_2).

Difference between linear and macrocyclic chelates
Subsequent studies confirmed progressive T1 SI increases after intravenous administration of linear GBCA (Errante, 2014; Kanda, 2015_1; Radbruch, 2015; Ramalho, 2015; Quattrocchi, 2015; Quattrocchi, 2015_1). The majority of the publications do not show dose-dependent changes in T1w SI after macrocyclic GBCA exposure (Cao, 2016; Kanda, 2015_1; Kromrey, 2017; Radbruch, 2017; Ramalho, 2015; Quattrocchi, 2015_1; Tibussek, 2017). Others report a weak T1w SI increase after administration of macrocyclic GBCA (Bjornerud, 2017; Kang, 2018; Rossi, 2017; Spelndiani, 2018; Stojanov, 2016;). A study of human brain tissue demonstrated measurable Gd after single dose intravenous administration of both linear and macrocyclic chelates (Murata, 2016). Significant less Gd retention was observed after macrocyclic chelate exposure, compared to linear chelate exposure (Murata, 2016).

These results led to a European Medicines Agency (EMA) directory regarding GBCA, stating to suspend the use of linear GBCA in order to prevent any risks that could potentially be associated with Gd brain deposition (EMA's final opinion confirms restrictions on use of linear gadolinium agents in body scans, 2019). Only the liver specific linear GBCA gadoxetate and gadobenate are allowed to be used in these situations where they meet a specific diagnostic need (EMA's final opinion confirms restrictions on use of linear GBCA in body scans, 2017).

Gd deposition in other tissues than brain.
Besides the brain and skin in patients with NSF, Gd retention has been reported in many other tissues including the bone, muscles, tendons, nerves, blood vessels and visceral organs (Gibby, 2004; Murata, 2016; Sanyal, 2011).

Pathophysiology of Gd deposition

Stability of Gd chelates is determined by their thermodynamic and kinetic stability. Thermodynamic stability of a chemical system means that this system is neither consuming nor releasing heat, i.e. thermal energy. In the absence of a change in thermal energy, the system is not undergoing a chemical reaction. Kinetic stability refers to the fact that a chemical reaction can occur at a certain speed. If a chemical system is kinetically stable, it means that reactions within this system occur very slowly. In general, macrocyclic GBCA have higher thermodynamic and kinetic stability constants and are therefore more stable than linear Gd chelates and therefore release less amount of Gd^{3+} out of the chelate (McDonald, 2018). Very little is known about the fate of free Gd^{3+} within the human body, and how biologically active and potentially toxic chemical forms of retained Gd in tissues are formed (McDonald, 2018). After intravenous injection in patients with normal kidney function, 73% to 99% of the dose is excreted within 24 hours after injection. Biodistribution data of GBCA suggest the presence of a longer lasting phase of residual excretion from other tissues, from which Gd is slowly eliminated (McDonald, 2018). The potential toxicities of this small pool of retained Gd are largely unknown (McDonald, 2018).

Clinical importance of Gd deposition

After hundred millions of Gd chelate administered doses, 139 patients with normal or minimally impaired kidney function reported effects that they associate with Gd exposure. The symptoms include chronic pain, fatigue, dermal changes, musculoskeletal disturbances, cognitive impairment, and visual impairment (Burke, 2016). An association between these symptoms and Gd chelate exposure has been postulated and the term "gadolinium deposition disease" has been proposed (Semelka, 2016). The Food and Drug Administration (FDA) could not find a causal relationship between Gd deposition and symptoms. If Gd deposition is associated with clinical harm, the harm is likely to be rare or occult for the vast majority of exposed patients (McDonald, 2018).

Future directions

Today, many question marks exist when it comes to the explanation of how Gd deposition occurs and what the clinical consequences, if any, are. In 2018, a research roadmap on Gd deposition was proposed, with the highest priorities to determine a) if Gd deposition adversely affects the function of human tissues, b) if deposition is causally associated with short- or long-term clinical manifestations of disease and c) if vulnerable populations are at greater risk for developing clinical disease (McDonald, 2018).

Inleiding

In 2014, Kanda observed progressive unenhanced T_1-weighted (T_1w) signal intensity (SI) increases in the dentate nucleus and globus pallidus in patients who received at least 6 doses of Gadolinium (Gd) chelates (Kanda, 2014). This publication triggered a huge amount of research on this subject, which is still going on today. Weekly, new publications arise, which make it impossible to give an up to date overview in this guideline. The broad outlines of gadolinium deposition will be discussed.

Samenvatting literatuur

Not Applicable.

Zoeken en selecteren

To answer our clinical question a systematic literature analysis was performed. This was an orientatational search, to examine the clinical relevance of the T1w hyperintensity of the nucleus dentatus and the globus pallidus.

P (Patient): patients who have repeatedly received gadolinium-based contrast agents and have signs of gadolinium retention such as T_1w hyperintensity of the nucleus dentatus and the globus pallidus, but also gadolinium retention in the bones, liver and skin;
I (Intervention): not applicable;
C (Comparison): not applicable;
O (Outcomes): signal intensity, signal increase, hyperintensity, hypersignal. Central torso and peripheral arm and leg pain. Distal arm and leg skin thickening. Rubbery subcutaneous tissues. Clouded mentation or brain fog.

Relevance of outcome measures
Signal intensity, signal increase, hyperintensity, hypersignal were considered critical outcomes and central torso, peripheral arm and leg pain, distal arm and leg skin thickening and rubbery subcutaneous tissues and clouded mentation or brain fog were considered important outcome measures.

Methods
The databases Medline (OVID), Embase and the Cochrane Library were searched from 1st of January 1996 to 11th of November 2018 using relevant search terms for systematic reviews (SRs), randomized controlled trials (RCTs) and observational studies (OBS).

The literature search produced 722 hits. A total of 99 abstracts were selected. When the full texts were examined, none of them fulfilled the selection criteria. Based on this, it was concluded that no conclusions on the clinical aspect could be drawn. Based on the literature, the narrative review shown below was written by the guideline committee.

Verantwoording

Laatst beoordeeld   : 24-06-2020
Laatst geautoriseerd : 24-06-2020

Voor de volledige verantwoording, evidence tabellen en eventuele aanverwante producten raadpleegt u de Richtlijnendatabase.

Referenties

Bjornerud A, Vatnehof SAS, Larsson C, Due-Tonnessen P, Hol PK, Groote IR. Signal enhancement of the dentate nucleus at unenhanced MR imaging after very high cumulative doses of the macrocyclic gadolinium-based contrast agent gadobutrol: an observational study. Radiology 2017; 285: 434 – 444.
Burke LM, Ramalho M, Al Obaidy M, Chang E, Jay M, Semelka RC. Self-reported gadolinium toxicity: a survey of patients with chronic symptoms. Magn Reson Imaging 2016; 34: 1078 – 1080.
Cao Y, Huang DQ, Shih G, Prince MR. Signal change in the dentate nucleus on T1-weigthed MR images after multiple administrations of gadopentetate dimeglumine versus gadobutrol. AJR 2016; 206: 414 – 419.

European Medicines Agency. EMA's final opinion confirms restrictions on use of linear gadolinium agents in body scans (21 July 2017). Available at: https://www.ema.europa.eu/en/documents/referral/gadolinium-article-31-referral-emas-final-opinion-confirms-restrictions-use-linear-gadolinium-agents_en-0.pdf Accessed: 11 July 2019.

Fingerhut S, Sperling M, Holling M, Niederstadt T, Allkemper T, Radbruch A, et al. Gadolinium-based contrast agents induce gadolinium deposits in cerebral vessel walls, while the neuropil is not affected: an autopsy study. Acta Neuropathol 2018; 136: 127-138.

Gibby WA, Gibby KA, Gibby WA. Comparison of Gd DTPA-BMA (Omniscan) versus Gd HP-DO3A (ProHance) retention in human bone tissue by inductively coupled plasma atomic emission spectroscopy. Invest Radiol 2004; 39: 138 – 142.

Kanda T, Ishii K, Kawaguchi H, Ketajima K, Takenaka D. High signal intensity in the dentate nucleus and globus pallidus on unenhanced T1-weighted MR images: Relationship with increasing cumulative dose of a gadolinium-based contrast material. Radiology 2014; 270: 834 – 841.

Kanda T, Fukusato T, Matsuda M et al. Gadolinium-based contrast agents accumulates in the brain even in subjects without severe renal dysfunction: evaluation of autopsy brain specimens with inductively coupled plasma mass spectroscopy. Radiology 2015; 276: 228-232.

Kanda T_1, Osawa M , Oba H, et al. High signal intensity in dentate nucleus on unenhanced T1-weighted MR images: association with linear versus macrocyclic gadolinium chelate administration. Radiology 2015; 275: 803 – 809.

Kang KM Choi SH, Hwang M, Yun TJ, Kim JH, Sohn CH. T1 shortening in the globus pallidus after multiple administrations of gadobutrol: assessment with a multidynamic multiecho sequence. Radiol 2018; 287: 258 – 266.

Kromrey ML, Liedtke KR, Ittermann T, et al. Intravenous injection of gadobutrol in an epidemiological study group did not lead to a difference in relative signal intensities of certain brain structures after 5 years. Eur Radiol 2017; 27: 772 – 777.

McDonald RJ, McDonald JS, Kallmes DF, et al. Intracranial gadolinium deposition after contrast-enhanced MR imaging. Radiology 2015; 275: 772 – 782.

McDonald JS_1, McDonald RJ, Jentoft ME, et al. Intracranial gadolinium deposition following gadodiamide-enhanced magnetic resonance imaging in pediatric patients: a case-control study. JAMA Pediatr 2017; 171; 705 – 707.

McDonald RJ_2, McDonald JS, Kallmes DF, et al. Gadolinium deposition in human brain tissues after contrast-enhanced MR imaging in adult patients without intracranial abnormalities. Radiology 2017; 285; 546 – 554.

McDonald RJ, Levine D, Weinreb J, Kanal E, Davenport MS, Ellis JH, et al. Gadolinium retention: a research roadmap from the 2018 NIH/ACR/RSNA workshop on gadolinium chelates. Radiology 2018; 289: 517-534.

Murata N, Gonzalez-Cuyar LF, Murata K, et al. Macrocyclic and other non-group 1 gadolinium contrast agents deposit low levels of gadolinium in brain and bone tissue: preliminary results from 9 patients with normal renal function. Invest Radiol 2016; 51: 447 – 453

Quattrocchi CC_1, Mallio CA, Errante Y, Beomonte Zobel B. High T1 signal intensity in dentate nucleus after multiple injections of linear gadolinium chelates. Radiology 2015; 276: 616 – 617.

Quattrocchi CC_2, Mallio CA, Errante Y et al. Gadodiamide and dentate nucleus T1 hyperintensity in patients with meningioma evaluated by multiple follow-up contrast-enhanced magnetic resonance examinations with no systemic interval therapy. Invest Radiol 2015; 50: 470 – 472.

Radbruch A, Weberling LD, Kieslich PJ, et al. Gadolinium retention in the dentate nucleus and globus pallidus is dependent on the class of contrast agent. Radiology 2015; 275: 783 – 791.

Radbruch A, Haase R, Kieslich PJ, et al. No signal intensity increase in the dentate nucleus on unenhanced T1-weigthed MR images after more than 20 serial injections of macrocyclic gadolinium-based contrast agents. Radiology 2017; 282: 699 – 707.

Ramalho J, Castillo M, AlOaidy M, et al. High signal intensity in globus pallidus and dentate nucleus on unenhanced T1-weighted MR images: evaluation of two linear gadolinium-based contrast agents. Radiology 2015; 276: 836 – 844.

Rossi Espagnet MR, Bernardi B, Pasquini L, Figa-Talamanca L, Toma P, Napolitano A. Signal intensity at unenhanced T1-weigthed magnetic resonance in the globus pallidus and dentate nucleus after serial administrations of a macrocyclic gadolinium-based contrast agent in children. Pediatr Radiol 2017; 47: 1345 – 1352.

Sanyal S, Marckmann P, Scherer S, Abraham JL. Multiorgan gadolinium (Gd) deposition and fibrosis in a patient with nephrogenic systemic fibrosis: an autopsy-based review. Nephrol Dail Transplant 2011; 26: 3616 – 3626.

Semelka RC, Ramalho J, Vakharia A, et al. Gadolinium deposition disease: initial description of a disease that has been around for a while. Magn Reson Imaging 2016; 34: 1383 – 1390.

Splendiani A, Perri M, Marsecano C, et al. Effects of serial macrocyclic-based contrast materials gadoterate meglumine and gadobutrol administration on gadolinium-related dentate nuclei signal increases on unenhanced T1-weigthed brain: a retrospective study in 158 multiple sclerosis (MS) patients. Radiol Med 2018; 123: 125 – 134.

Stojanov DA, Aracki-Trenkic A, Vojinovic S, Benedeto-Stojanov D, Ljubisavljevic S. Increasing signal intensity within the dentate nucleus and globus pallidus on unenhanced T1W magnetic resonance images in patients with relapsing-remitting multiple sclerosis: correlation with cumulative dose of a macrocyclic gadolinium-based contrast agent, gadobutrol. Eur Radiol 2016; 26: 807 – 815.

Tibussek D, Rademacher C, Caspers J, et al. Gadolinium brian deposition after macrocyclic gadolinium administration: a pediatric case-control study. Radiology 2017; 285: 223 – 230.

Safe use of Central Venous Catheters, Haemodialysis Catheters, Peripherally Inserted Central Catheters, and Totally Implantable Venous Access Devices for contrast administration using power injectors

Uitgangsvraag

How can central venous catheters (CVC), haemodialysis catheters (HC), peripherally inserted central catheters (PICC), and totally implantable venous access devices (TIVAD) be safely used for the administration of intravenous contrast agents, particularly using power injectors and higher injection rates for obtaining high-quality images?

Aanbeveling

Note: High quality of imaging is generally needed for low-contrast situations, such as in staging studies in brain, head & neck, hepatobiliary, genitourinary or colorectal imaging. Lower quality may be acceptable for high-contrast situations such as in follow-up studies of lymph nodes (lymphoma, testicular cancer) or in pulmonary or musculoskeletal imaging.

Use a power injector and a peripheral venous access catheter for IV contrast media administration to obtain the best level of quality of contrast-enhanced imaging, especially in low-contrast situations (see Note).

When a peripheral venous catheter is unavailable: Check the position of the CVC, TIVAD, or PICC line and its patency before and after the power-injected contrast administration.

Power-injectable central venous catheters may be safely used for administration of CM using a power injector, when recommendations of the catheter manufacturer are followed.

Power-injectable haemodialysis catheters may be safely used for administration of CM using a power injector, when recommendations of the catheter manufacturer are followed.

Especially in haemodialysis patients, vein preservation should weigh heavily in the choice of access for CM administration. When the use of a peripheral vein for contrast administration in haemodialysis patients is inevitable, the veins in the elbow fold should be used as much as possible. If this is impossible, veins on the back of the hand or the use of dialysis fistula for contrast administration should be considered in consultation with a nephrologist.

There is a risk of catheter tip migration of PICCs and TIVADs when CM is injected via a power injector in patients with a catheter tip position above the tracheobronchial angle.

When a power-injectable PICC or TIVAD is used for CM administration, check the position of the catheter tip with DX, CT or fluoroscopy before and after power-injection of CM.

When a power-injectable CVC, HC, PICC or TIVAD is used for CM administration with a power injector, check the patency of the catheter after the procedure by manual flush of 20ml normal saline.

When a power-injectable HC is used for CM administration, immediately after power-injection a patient-specific lock solution should be installed by a certified dialysis nurse.

See the Appendix for recommendations on flow rates and injection pressures for a large number of commercially available CVCs, HCs, PICCs, and TIVADs in The Netherlands.

Also see the flowcharts.

Overwegingen

A patent intravenous access site is needed for the administration of intravenous contrast through power injection in order to obtain high quality contrast enhanced or angiographic images. Local hospital guidelines should be available to guide the proper and safe administration technique for the applied contrast medium, but these a frequently limited to peripheral venous injection only. Possible complications of IV contrast injection are: contrast medium extravasation, air embolism, catheter rupture, catheter weakening, and loss of catheter patency.

With the use of power injectors, injection pressure is also a function of the injected CM. In general, the use of lower concentrations of the CM, low viscosity of the CM, and high temperature of CM are beneficial to keep injection pressures as low as possible (Macha, 2009; Kok, 2014).

There are only a limited number of studies that compare the safety and efficacy of different venous access sites. No difference is reported in patency between CVCs or peripheral venous access catheters, however there seems to be a difference in the level of the contrast enhancement of large vessels, which affects the image quality in favour of a peripheral venous access. A short peripheral IV catheter in the antecubital or forearm is therefore the preferred route for contrast administration. However other routes may be needed and each is considered separately below.

Central Venous Catheters (CVC)
In the comparative studies, there is no difference in reported complications in terms of patency related to the contrast medium power injection compared to peripheral venous access sites. However, image quality is limited compared to peripheral venous access sites.

Herts (Herts, 1996) also performed an in vitro study with 10F Hickman and Leonard CVCs, and found that CM, flow rate and catheter type were main determinants of peak injection pressures. The peak injection pressures remained well within manufacturer limits of 25 psi (175 kPa).

In an in vitro study with a 3-lumen 16G (4.9F) Arrow CVC, a significant safety margin was shown for CVCs, with bursting pressures depending on catheter dwell time, 262 PSI for new and 213 PSI for used catheters. Lowest flow rate associated with bursting was 9 ml/s. Ruptures occurred always *outside* the patient (Macha, 2009).

Similar high bursting pressures were seen in other studies. A study using 3-lumen 16G CVCs showed pressure to be above 175 PSI, whereas high flow injections 4,5 to 7,0 ml/s were associated with injection pressures of 48 to 81 PSI (Beckingham, 2017). An older study found no catheter failures at flow rates of 5 to 25ml/s with an even higher bursting pressure of 920 psi (Zamos, 2007).

To help prevent the rupture of vascular access devices when they are used with power injectors, the FDA long

ago has already issued recommendations (FDA, 2004).
Users of central vascular access devices should:

1. Check the labelling of each vascular access device for its maximum pressure and flow rate. If none is provided, assume device is NOT intended for power injection and do not use.
2. Know the pressure limit setting for your power injector and how to adjust it.
3. Ensure that the pressure limit set for the power injector does not exceed the maximum labelled pressure for the vascular access device(s).

Haemodialysis Catheters (HC)
There are no patient controlled studies available that compare the usability and safety of dialysis catheters for IV contrast administration through power injection versus peripheral IV catheters or central venous catheters. However, haemodialysis catheters have larger diameters than other venous catheters. An in vitro study on cuffed and non-cuffed catheters for haemodialysis showed that pressure inside the catheters (14,0 ± 3,3 PSI) was 23x lower than the pressures indicated by the power injectors (338 ± 8,7 PSI). It is believed that the high pressures in the injector are mainly caused by the long, small calibre connection tubing that connects the injector to the HC (Hollander, 2012). Therefore, their use for power injection should be safe when adhering to the recommendations of the manufacturer.
Adjustments to the scan protocol may be needed to preserve optimal image quality. Especially in chronic dialysis patients with poor vascular conditions vein preservation has a high priority.

Peripherally inserted catheters (PICC)
Spontaneous migration of PICCs is a known complication in 1.5 to 3% with multifactorial aetiology (Seckold, 2015). Multiple other case series have confirmed that the catheter tip of power-injectable PICCs can migrate due to the power injection during CT (Lambeth, 2012; Craigie, 2018).
Tubing ruptures during power injection are reported when there is a mechanical obstruction such as a clamped port or kinking of the line. Silicone catheters are have higher failure rates than polyurethane catheters and are unsuitable for power injection (Salis, 2004).
Strict protocols are recommended to check its position via CT scout/scanogram radiograph before and after power injection during CT, and to check patency of the catheter after CM injection.

Totally Implantable Venous Access Devices (TIVAD)
A retrospective analysis of TIVADs with silicone catheters showed a 3.4% rate of complications (Busch 2012; Busch, 2017). Newer power-injectable TIVADs have a high patient satisfaction rate and with no device failures during power injections (Alexander, 2012; Chang, 2013).

There are no data on catheter tip migration in TIVADs, mainly because they are tunneled catheters inserted surgically with a deep position of the catheter tip. Theoretically, for devices with high positions of the catheter tip, the same risks for migration as in PICCs would exist.

The GAVeCeLT group formulated already in 2011 recommendations to prevent complications with TIVADs and recommends only using systems specifically suitable for power injection with adequate check of catheter position (Bonciarelli, 2011.

A Canadian study on CT image quality showed that contrast injection via a CVC or port system has equivalent image quality when compared to conventional peripheral intravenous injection technique. (Haggag, 2016)

Inleiding

Power injection of contrast through CVCs, HCs, PICCs, and TIVADs holds a risk for device failure and secondary contrast extravasation. The exact method how to "power-inject" with respect to applied pressure limitations remains part of local practice guidelines combined with the central catheter line manufacturer's instructions.

Conclusies

Very Low GRADE	The frequency of complications following contrast injection via CVCs, without safety protocols, varies from 0,6% to 15,4% across studies. *Sources: (Coyle, 2004; Goltz, 2011; Herts, 2001; Lozano, 2012; Morden, 2014)*

Very Low GRADE	It seems that contrast injections via CVCs are a safe alternative to peripheral injection if safety protocols are followed. *Sources: (Coyle, 2004; Goltz, 2011; Herts, 2001; Lozano, 2012; Morden, 2014)*

Very Low GRADE	There were no complications reported following contrast injection via CVCs when strict safety protocols were implemented. *Sources: (Macht, 2012 and Sanelli, 2004)*

Very Low GRADE	Safety protocols are warranted when contrast injections are performed via central venous catheters, and should include aspirating blood before injecting contrast media, localizing the CVC before and after injection, making sure no kinking of the CVC and attached lines occurs, using sterile syringes, and making sure the CVC is patent after scanning. *Sources: (Macht, 2012 and Sanelli, 2004)*

Very Low GRADE	It is unknown whether contrast injections via CVCs result in successful contrast media examination as quality of scans varies among studies. *Sources: (Coyle, 2004; Goltz, 2011 and Herts, 2001)*

Very low. GRADE	It seems that power injectable PICCs positioned in the proximal SVC (cephalic to tracheobronchial angle) before contrast administration had a higher risk of displacement compared to catheters positioned in the distal SVC (caudal to tracheobronchial angle) before contrast administration. *Source: (Lozano, 2012)*

Samenvatting literatuur

Buijs (2017) described a systematic literature review on the efficacy of contrast injection via central venous catheters for contrast enhanced computed tomography. A search query was built by linking two content areas: 'central catheter' and 'contrast enhanced' with relevant synonyms for both areas. Publications were selected, describing original research on the use of CVCs for contrast administration for CT-scans focusing on safety, efficacy, and complications. Exclusion criteria included: no full-text available, publication not written in English or Dutch, review articles, case reports, and studies focusing on the use of CVCs in paediatrics. Two independent assessors screened titles and abstracts for full-text selection. Studies were classified as having low risk of bias if they satisfied all criteria and high risk of bias if they satisfied less than three criteria. The remaining studies were classified as having a moderate risk of bias. (See risk of bias assessment). Frequencies of complications were extracted from the selected studies were tabulated and presented as percentages. Data on quality of images was extracted where applicable. Twenty-three articles were considered eligible for answering the research question after selection based on title and abstract. Seventeen articles were excluded during full text screening. During cross-referencing, one study was included missed by the initial search (Carlson, 1992; Goltz, 2011). Eventually, eight studies were included for critical appraisal (Coyle, 2004; Goltz, 2011; Herts, 2001; Lozano, 2012; Macht, 2012; Morden, 2014; Sanelli, 2004). Carlson (1992) evaluated the system pressure in thirteen patients with a Port-A-Cath. The pressure measurement was not standardized: five patients' injection pressures were measured with a pressure gauge that was placed in-line during injection and eight patients' injection pressures were not. The lack of standardization and limited relevance led to the exclusion of this study. Finally, seven studies were included for further analysis (Coyle, 2004; Goltz, 2011; Herts, 2001; Lozano, 2012; Macht, 2012; Morden, 2014; Sanelli, 2004). Table 1 presents study characteristics and main outcome measures on safety and image quality. Individual outcome measures among studies on safety and efficacy are described separately.

Table 1 Study characteristics and main findings for complications and image quality

Study (year)	N	Study	Type catheter	Injection rate and peak pressure	Safety	Image quality
Central Venous Catheters						
Herts, 2001	174 versus. 51 peripheral	RCT	117 port-type, 41 3L, 10 DL, 6 unknown	CVC: 1.5–2 mL/s, pressure cut-off 100 psi Peripheral: 2.5–3 mL/s, pressure cut-off 300 psi	1 (0.6%) CVC no longer patent1 positive blood culture	Less contrast enhancement in thoracic aorta, pulmonary artery, liver in CVC group

Macht, 2012	104	Retrospective	Distal 16G lumen of Arrow multi-lumen (3L, 5L)	3L: 4.4 ± 0.5 mL/s; 200.7 ± 17.5 psi5L: 4.6 ± 0.6 mL/s; 194.5 ± 6.5 psi	No complications	-
Sanelli, 2004	104	Prospective	Arrow multi-lumen CVC (n = 89) Percutaneous sheaths IJV (n =15)	3 mL/s (n =15); 4 mL/s (n =8); 4 mL/s (n = 79); 5 mL/s (n = 2) Pressure limit 300 psi; 5/43 pressure-limited (306–316 psi)	13/60 (21,7%) blood cultures positive during ICU course	-
Peripherally Inserted Catheters						
Coyle, 2004	110	Prospective	12 SL 5F PICC 98 DL 5F PICC	1–2 mL/s (n = 8), 2 mL/s (n =89), 2–3 mL/s (n = 9), 4 mL/s (n = 4) SL: 16–79 psi, DL: 40–135 psi.	2 (1.8%) ruptured 1 balloon (DL, 4 mL/s)	81 average; 23 above average; 6 below average
Lozano, 2012	78	Prospective	Power injectable PICC (4–6F, SL/DL)	Mean injection rate 4.13 ± 0.855 mL/s (range 3–5); pressure limit 300 psi	12/78 (15.4%) dislocation	-
Morden, 2014	243 high rate versus. 138 rate increase	Retrospective	CT-PICC (4–6F, SL/ DL/3L)	Injection rates 2–5 mL/s Pressure limit 300 psi	20/243 (8.2%) displaced versus. 3/138 (2.2%)	-
Totally Implantable Venous Access Devices						
Goltz, 2011	141 versus. 50 peripheral catheter	Retrospective	141 TIVAP forearm	TIVAP: Max 1.5 mL/s; mean pressure 121.9±24.1 psi Peripheral: 3 mL/s, pressure limit 300 psi	1 (0.7%) dislocation with rupture3 (2.1%) suspected systemic infection <4 weeks	31/44 (70.4%) trigger threshold not reached Significant higher aortic contrast via peripheral catheter

Legend: CVC =central venous catheter, SL= single lumen, F= French, PICC= peripherally inserted central catheter, DL= double lumen, TIVAP= totally implantable venous access port, 3L= triple-lumen, G= gauge, 5L= quintuple-lumen, IJV= inferior jugular vein, ICU= intensive care unit.

Results

1. Complications following contrast injection via central catheters

Central Venous Catheters (CVC)
Herts (2001) randomized 225 patients, after reassignment because of inability to obtain access, in a central venous access group (n= 174) and a peripheral venous access group (n= 51). No significant differences in early, delayed, and late complications were found. In the central venous access group, one (1/174; 0.6%) patient reported that her device was no longer patent, while being successfully used for chemotherapy after contrast injection. In one (1/174; 0.6%) patient an infection was reported. Macht (2012) and Sanelli (2004) implemented a strict safety protocol, in which they verified the correct position of the CVC in the superior vena cava (SVC) on scout view before contrast injection, checked for adequate blood return, and checked the patency of the catheter afterwards. They did not report complications relating to the injection using the CVC.

Peripherally inserted catheters (PICC)
Coyle (2004) found two (2/110; 1.8%) externally ruptured PICCs while injected at a rate of 2 mL/sec. Ruptures were caused by mechanic obstructions; i.e. one of the ruptured PICCs was clamped, the other kinked at the venous entry site. Another PICC ballooned without rupturing and further injected was stopped.

Lozano (2012) evaluated the frequency of displacement of power-injectable PICC (PI-PICC) after contrast injection. Correct catheter position was defined as cephalic to or caudal to the right tracheobronchial angle. A total of 12/78 (15.4%) PI-PICC tips changed in position after injection of contrast medium. Seven displaced toward the brachiocephalic veins. They found that PI-PICCs positioned in the proximal SVC (cephalic to tracheobronchial angle) before contrast administration had a higher risk of displacement compared to catheters positioned in the distal SVC (caudal to tracheobronchial angle) before contrast administration (5/8 (62.5%) versus 7/69 (10.1%)). Distal location in the SVC decreased this risk by 89% (RR= 0.11; 95%CI= (0,026; 0,487); p= 0.006).

Morden (2014) evaluated a rate increase technique of the saline flush after contrast injection via power-injectable PICCs (PI-PICC), in which they started with a saline flush at 2 mL/s and progressively increased to the rate of contrast injection. With this technique, they found a lower percentage of PI-PICC tip displacement (20/243 (8.2%) without rate increase technique versus. 3/138 (2.2%) with rate increase technique).

Totally Implantable Venous Access Devices (TIVAD)
Goltz (2011) evaluated power injections in 141 patients with totally implantable venous access ports (TIVADs) in their forearm. One (1/141; 0.7%) TIVAD catheter tip was dislocated into the brachiocephalic vein and revealed a catheter rupture during an interventional retrieval attempt. Three (3/141; 2.1%) catheter tips were suspected of a systemic infection within four weeks.

2. Contrast enhancement and image quality
Central Venous Catheters (CVC)
In Herts (2001), two reviewers who were blinded for route of injection measured the enhancement of the large vessels. The level of enhancement of the thoracic aorta, pulmonary artery, and liver vasculature was significantly less dense in the central venous access group compared to the peripheral venous access group. No significant difference was seen in the enhancement of the abdominal aorta.

Totally Implantable Venous Access Devices (TIVAD)

In Coyle (2004) CT images were assessed subjectively by the radiologist supervising the CT examination, which resulted in categorizing the quality of CT images as average in 81/110 (74%) of cases and above average in 23/110 (21%) of cases.

Goltz (2011) found a significantly lower arterial contrast density in patients with TIVADs compared with classic peripheral cannula, resulting in limited image quality. In 31/44 (70.4%) examinations, manual initialization was necessary, while initial arterial bolus tracking was performed, because the trigger threshold had not been reached in time. This might be the result of the lower flow rate of 1.5 mL/s through TIVADs. Triggering with automatic scan initiation resulted in significantly higher contrast in the aorta compared to manual scan initiation (163 HU versus 144 HU, p =0.039).

Quality of evidence
The quality of certainty of evidence was graded as very low due to high risk of bias (see Table Risk of Bias assessment, downgraded by one point) and low number of patients (imprecision, downgraded by two points) and lack of studies where a control group was present.

Zoeken en selecteren

A systematic literature analysis was performed to answer the research question: How can central venous catheters (CVC), haemodialysis catheters (HC), peripherally inserted central catheters (PICC), and totally implantable venous access devices (TIVAD) be safely used for the administration of intravenous contrast agents, particularly using power injectors and higher injection rates for obtaining high-quality images?

P (Patient): patients with central venous catheters (CVCs) or Peripheral inserted central catheters (PICCs) and an indication for administration of iodine-based contrast for performing computed tomography examinations;
I (Intervention): non-tunneled central venous catheters (CVCs), tunneled CVCs, implantable ports, peripherally inserted central catheters (PICC).
C (Comparison): normal Venflon, normal peripheral infusion;
O (Outcomes): failure contrast media examination, contrast extravasation, failure of examination, damaged CVCs or PICCs, complication rates, device failure, and device dwell times.

Relevance of outcome measures
The working group considered the outcomes failure of contrast media examination, complication rates (damaged CVCs or PICCs, contrast media extravasation) critical measures and outcome for the decision making process. The working group did not define criteria for outcomes a priori, but used the outcomes as defined in the studies.

Methods
The databases Medline (OVID), Embase and the Cochrane Library were searched from 1st of January 1996 to March 2018 using relevant search terms for systematic reviews (SRs), randomized controlled trials (RCTs) and observational studies (OBS). A systematic literature search was conducted at May 16th 2018.

The literature search produced 97 hits: 2 SR, 13 RCTs and 13 OBS and 68 mixed designs. Based on title and abstract a total of 18 studies were selected. After examination of full text 0 articles were selected. Since there

are no direct comparisons on the safety or efficacy of contrast injections via central venous catheters or peripheral inserted central catheters (PICCs) versus normal infusion, literature has been described in a descriptive manner. The SR of Buijs, 2017 was selected and covers the literature on efficacy and safety of contrast injection via central venous catheters for contrast enhanced computed tomography until September 10th 2016. This study was used as key article for the literature review. Studies published after September 10th 2016, on efficacy and safety of contrast injection via central venous catheters or peripheral inserted central catheters were added.

Verantwoording

Laatst beoordeeld   : 24-06-2020
Laatst geautoriseerd : 24-06-2020

Voor de volledige verantwoording, evidence tabellen en eventuele aanverwante producten raadpleegt u de Richtlijnendatabase.

Referenties

Alexander MD, Morrison HL. Power-injectable ports: safety during placement, therapeutic use, and contrast administration during computed tomography procedures. J Vasc Access 2012; 13: 432-437.

Beckingham T, Roberts A, St John A, O'Callaghan G. Bursting pressure of triple-lumen central venous catheters under static and dynamic loads. J Vasc Access 2017; 18: 430-435.

Buijs SB, Barentsz MW, Smits MLJ, Gratama JWC, Spronk PE. Systematic review of the safety and efficacy of contrast injection via venous catheters for contrast-enhanced computed tomography. Eur J Radiol Open 2017; 4: 118-122.

Bonciarelli G, Batacchi S, Biffi R, et al. Gruppo Aperto di Studio Accessi Venosi Centrali a Lungo Termine (Study Group on Long-Term Central Venous Access). GAVeCeLT* consensus statement on the correct use of totally implantable venous access devices for diagnostic radiology procedures. J Vasc Access. 2011; 12: 292-305.

Burbridge BE, Adams S, Burbridge C. Computed tomography frequency and power injection utilization for a cohort cancer patients with arm ports. J Radiol Med Imaging 2018; 1: 1002.

Busch JD, Herrmann J, Heller F, Derlin T, Koops A, Adam G, Habermann CR. Follow-up of radiologically totally implanted central venous access ports of the upper arm: long-term complications in 127,750 catheter-days. AJR Am J Roentgenol 2012; 199: 447-452.

Busch JD, Vens M, Herrmann J, Adam G, Ittrich H. Material failure of silicone catheter lines: a retrospective review of partial and complete ruptures in 553 patients. AJR Am J Roentgenol 2017; 208: 464-469.

Chang DH, Kabbasch C, Bovenschulte H, Libicher M, Maintz D, Bangard C. Experiences with power-injectable port systems: complications, patient satisfaction and clinical benefit (in German). RöFo Fortschr Röntgenstr 2013; 185: 454-460.

Coyle D, Bloomgardeb D, Beres R, Patel S, Sane S, Hurst E. Power Injection of contrast media via peripherally inserted central catheters for CT. J Vasc Interv Radiol 2004; 15: 809-814.

Craigie M, Meehan L, Harper J. Tip migration post-contrast pressure injection through pressure-injectable peripherally inserted central catheters causing vascular injury: a report of 3 cases. Cardiovasc Intervent Radiol 2018; 41: 509-512.

Food and Drug Administration. FDA Warns of Dangers of Misusing Vascular Access Devices. Bethesda MD, FDA, 2004. Available at:
https://gavecelt.it/nuovo/sites/default/files/uploads/fda_warns_of_dangers_of_misusing_vascular_access_devices.pdf. Accessed: 11 July 2019.

Goltz JP, Noack C, Petrisch B, Kirchner J, Hahn D, Kickuth R. Totally implantable venous power ports of the forearm and the chest: initial clinical experience with port devices approved for high-pressure injections. Br J Radiol 2012: 85: e966-e972.

Haggag H, Roh C, Chan I, Burbridge B, Leswick D. Quality of computed tomography images acquired with power injection of an arm port. Can Assoc Radiol J 2016; 67: 112-114.

Herts BR, O'Malley CM, Wirth SL, Lieber ML, Pholman B. Power injection of contrast media using central venous catheters: feasibility, safety and efficacy. AJR Am J Roentgenol 2001; 176: 447- 453.

Hollander S, Mojibian H, Emery M, Tal MG. Power injection of iodinated intravenous contrast material through acute and chronic hemodialysis catheters. J Vasc Access 2012; 13: 61-64.

Klee SJ. The ideal use of the power injectable peripherally inserted central catheter in the pediatric population. JAVA 2011; 16: 86-93.

Kok M, Mihl C, Mingels AA, Kietselaer BL, Mühlenbruch G, Seehofnerova A, et al. Influence of contrast media viscosity and temperature on injection pressure in computed tomographic angiography: a phantom study. Invest Radiol 2014; 49: 217-223

Lambeth L, Goyal A, Tadros A, Asadoorian M, Roberts AC, Karimi A. Peripherally inserted central catheter tip malposition caused by power contrast medium injection. J Vasc Interv Radiol 2012; 23: 981-983.

Lozano LA, Marn C, Goodman LR. Power injectable peripherally inserted venous catheter lines frequently flip after power injection of contrast. J Comput Assist Tomogr 2012; 36: 427-430.

Macha DB, Nelson RC, Howle LE, Hollingsworth JW, Schindera ST. Central venous catheter integrity during mechanical power injection of iodinated contrast medium. Radiology 2009; 253: 870-878.

Macht S, Beseoglu K, Eicker S, Rybacki K, Braun S, Mathys C, et al. Safety and feasibility in highly concentrated contrast material power injections for CT-perfusion studies of the brain using central venous catheters. Eur J Radiol 2012; 81: 1883-1885.

Morden P, Sokhandon F, Miller L, Savin M, Kirsch M, Farah M, et al. The Role of saline flush injection rate in displacement of CT-injectable peripherally inserted central catheter tip during power injection of contrast material. AJR Am J Roentgenol 2014; 202: W13-W18.

Salis AI, Eclavea A, Johnson MS, Patel NH, Wong DG, Tennery G. Maximal flow rates possible during power injection through currently available PICCs: an in vitro study. J Vasc Interv Radiol 2004; 15: 275-281.

Sanelli PC, Deshmukh M, Ougorets I, Caiati R, Heier LA. Safety and feasibility of using a central venous catheter for rapid contrast injection rates. AJR Am J Roentgenol 2004; 183: 1829-1834.

Seckold T, Walker S, Dwyer T. A comparison of silicone and polyurethane PICC lines and postinsertion complication rates: a systematic review. J Vasc Access 2015; 16:167-177.

Schummer C, Sakr Y, Steenbeck J, Gugel M, Reinhart K., Schummer W. Risk of extravasation after power injection of contrast media via the proximal port of multilumen central venous catheters: case report and review of the literature. RöFo Fortschr Rontgenstr 2010; 182: 14-19.

Teichgräber UKM, Nagel SN, Kausche S, Enzweiler C. Clinical benefit of power injectable port systems: A prospective observational study. Eur J Radiol 2012; 81: 528-533.

Verity R, Leswick D, Burbridge B, Bryce R, Lim H. Quality of computed tomography pulmonary embolism and aortic phase images acquired with power injection via an arm port. JAVA 2017; 22; 88-92.

Weinbeck S, Fischbach R, Kloska SP, Seidensticker P, Osada N, Heindel W, et al. Prospective study of access site complications of automated contrast injection with peripheral venous access in MDCT. AJR Am J Roentgenol 2010: 195: 825- 829.

Zamos DT, Emch TM, Patton HA, D'Amico FJ, Bansal SK. Injection rate threshold of triple-lumen central venous catheters: an in vitro study. Acad Radiol 2007; 14: 574-578.

Optimal treatment of contrast medium extravasation

Uitgangsvraag

What is the optimal treatment in contrast media extravasation?

Aanbeveling

Consider the following treatment options for contrast extravasation:

- Try to aspirate the extravasated contrast medium through an inserted needle.
- Mark affected area.
- Use compresses, for relieving pain at the injection site.
- Use painkillers.
- Elevate the affected extremity above the level of the heart.

Record contrast extravasation and treatment in the patient record (volume, concentration, area, clinical findings).

Give the patient clear instructions when to seek additional medical care:

- Any worsening of symptoms.
- Skin ulceration.
- Development of any neurologic or circulatory symptoms, including paraesthesia's.
- Give the patient a patient information leaflet.

For severe extravasation injury:

- Consult a plastic surgeon.
- Notify the referring physician.

Overwegingen

The working group has based this protocol on expert opinions and international guidelines.
At the end of the recommendations suggestions for further reading are given.

<u>Extravasations and injuries</u>
One or more of the following signs or symptoms can develop: progressive swelling or pain, altered tissue perfusion as evidenced by decreased capillary refill at any time after the extravasation has occurred, change in sensation in the affected limb, and skin ulceration or blistering. It is important to note that initial symptoms of a compartment syndrome may be relatively mild (such as limited to the development of focal paraesthesia).

Most extravasations result in minimal swelling or erythema, with no long-term sequelae.

Few extravasations result in significant tissue damage, i.e. severe skin necrosis and ulceration. Compartment syndrome may be seen associated with extravasation of large volumes and after extravasation of relatively small volumes in less capacious areas.
Extravasation can occur during hand or power injection.

The risk of extravasation is much less with GBCA injections.

Risk factors
Location of extravasation:
Less capacious areas (such as over the ventral or dorsal surfaces of the wrist) – higher risk
More capacious areas (such as upper arm) – lower risk

Volume of extravasation:
Large volume of contrast medium – higher risk

Inability to communicate:
Infants, young children, and unconscious and debilitated patients

Management

- Recognition of the extravasation, stop infusion of contrast media immediately.
- Try to aspirate the extravasated contrast medium through the inserted needle.
- Mark off affected area.
- Consultation of a radiologist.
- Surgical consultation (plastic surgeon) should be obtained whenever there is concern for a severe injury. Alternative: consultation of a physician in the emergency department.
- Clear instructions should be given to the patient to be aware of alarming symptoms.
- Appropriate patient information leaflets should be available. One should consider having these available in multiple languages.
- Appointments for follow up, if necessary.
- The referring physician should be notified.
- Record contrast extravasation and treatment in patient record (name, volume, concentration, area, clinical findings).
- Record names of all professionals involved in the patient management in patient record.
- Report contrast extravasation as a complication in the local reporting system.

Treatment
Non-severe extravasation injury:

- Use of cold of warm compresses, helpful for relieving pain at the injection site.
- Use of cold compresses, mainly helpful for relieving pain at the injection site.
- Use of warm compresses, helpful in improving absorption of the extravasation as well as in improving blood flow, particularly distal to the site.

- Use of pain medication (analgesics).
- Elevation of the affected extremity above the level of the heart to decrease capillary hydrostatic pressure and thereby promote resorption of extravasated fluid is recommended.
- Clear instructions should be given to the patient to seek additional medical care, should there be any worsening of symptoms, skin ulceration, or the development of any neurologic or circulatory symptoms, including paraesthesias.

Severe extravasation injury:

- Surgical consultation (plastic surgeon).
- Clear instructions should be given to the patient about the follow-up.

Inleiding

Extravasation of intravascular (intravenous or intra-arterial) injected contrast (hand or power injection) is a well-recognized complication of contrast enhanced imaging studies (CT and MRI and US), angiography and interventions. Currently the clinical consequences and most optimal management is a matter of debate.

Samenvatting literatuur

Not applicable. There were no studies investigating the research question.

Zoeken en selecteren

To answer our clinical question a systematic literature analysis was performed.

P (Patient): patients with extravasation after intravascular contrast Administration;
I (Intervention): cContrast aspiration, cooling of area of contrast extravasation, fasciotomy, necrotectomie, dilution, flushing with sterile water, application of ice, anti-inflammatory agents, corticosteroid, removal catheter, elevation of the affected limb / extremity, cold compresses, Plastic Surgery Review, monitoring the patient, surgical consultation;
C (Comparison): conservative treatment or comparison of interventions above;
O (Outcomes): rhabdomyolysis, tissue necrosis, long term injury / disability, compartment syndrome, pain, swelling and ulceration.

Relevant outcome measures
The working group considered compartment syndrome, tissue necrosis, and permanent or long-term injury or disability critical outcome measures for the decision making process, and location and volume of extravasation, pain, swelling, ulceration important outcomes for the decision making process.

Methods
The databases Medline (OVID), Embase and the Cochrane Library were searched from 1st of January 1996 to 7th of February 2018 using relevant search terms for systematic reviews (SRs), randomized controlled trials (RCTs) and observational studies (OBS).

The literature search procured 480 hits: 1 SR, 41 RCTs and 438 OBS. Based on title and abstract a total of 22 studies were selected. After examination of full text a total of all studies were excluded and 0 studies definitely included in the literature summary.

Verantwoording

Laatst beoordeeld   : 24-06-2020
Laatst geautoriseerd : 24-06-2020

Voor de volledige verantwoording, evidence tabellen en eventuele aanverwante producten raadpleegt u de Richtlijnendatabase.

Referenties

American College of Radiology. ACR Manual on contrast media, v10.3. Available at: www.acr.org/Clinical-Resources/Contrast-Manual. Accessed: 11 July 2019.

European Society of Urogenital Radiology Contrast Media Safety Committee. ESUR Guidelines on contrast safety, v10. Available at: www.esur-cm.org. Accessed: 11 July 2019.

Behzadi AM, Farooq V, Newhouse JH, Prince MR. MRI and CT contrast media extravasation: a systematic review. Medicine (Baltimore) 2018; 97: e0055.

Ding S, Meystre NR, Campeanu C, Gullo G. Contrast media extravasations in patients undergoing computerized tomography scanning: a systematic review and meta-analysis of risk factors and interventions. JBI Database System Rev Implement Rep 2018; 16: 87-116.

Hrycyk J, Heverhagen JT, Böhm I. What you should know about prophylaxis and treatment of radiographic and magnetic resonance contrast medium extravasation. Acta Radiol 2019; 60: 496-500.

Hwang EJ, Shin CI, Choi YH, Park CM. Frequence, outcome and risk factors for contrast media extravasation in 142,651 contrast-enhanced CT scans. Eur Radiol 2018; 28: 5368-5375

Ko CH, Tay SY, Chang HC, Chan WP. Large-volume iodinated contrast medium extravasation: low frequency and good outcome after conservative management in a single-centre cohort of more than 67,000 patients. Eur Radiol 2018;28: 5376-5383.

Mandlik V, Prantl L, Schreyer AG. Contrast media extravasation in CT and MRI: a literature review and strategies for therapy. RöFo Fortschr Röntgenstr 2019; 191: 25–32.

Organisation of health care for contrast media

Hospital-based protocols
Develop hospital-based protocols on the safe use of contrast media (CM) describing (preventive) measures, workflow and responsibilities. Protocols should be available about The prevention of adverse reactions.

Treatment of adverse reactions.
Safety of gadolinium use.
Contrast media extravasation.
Safe use of catheters using power injectors.

A panel of various local experts should establish these protocols. The panel members will depend on the specific protocol (including a nephrologist, a (plastic) surgeon, an internal medicine specialist, a pharmacologist, a cardiologist, an allergology specialist and a radiologist). The referring physician is held responsible for analysing and giving notice of the patient's kidney function and hypersensitivity reactions to contrast media, instructing about the patient's medication, and the patient's after-care. And for taking blood samples for laboratory testing (tryptase levels) in case of moderate to severe hypersensitivity reactions to contrast media and for referring the patient to an allergy specialist in case of moderate to severe hypersensitivity reactions to contrast media. The physician responsible for the procedure should take the decision about contrast administration. Make agreements with the allergy specialist about the procedure for referral and testing for contrast media allergy.
Actions can be delegated to others according to local rules and protocols.

Hypersensitivity reactions to contrast media and prevention
Have a description of preventive measures in patients with a previous allergic reaction, for outpatient and clinical patients. Appropriate patient information leaflets should be available, about the procedure and about the preventive measures. Including the instruction about not driving a car/motorcycle for 24 hours after administration of clemastine.

<u>Workflow and responsibilities</u>

Responsible person	Action and responsibility
Referring physician	Order procedure: contrast-enhanced CT, contrast-enhanced MRI or angiography / intervention Inform patient about procedure Assessment hypersensitivity reactions to contrast media Mention previous hypersensitivity reactions in the order Instruct patient about preventive measures Record severe hypersensitivity reactions to contrast media in allergy registry of the patient record Record all severe drug (including contrast media) adverse reactions at the National Pharmacovigilance Institute LAREB
Physician responsible for the procedure - Cardiologist/Radiologist/ Nuclear Medicine/ Radiotherapist	Check the order for the imaging examination/procedure Check previous hypersensitivity reactions to contrast media Determine examination protocol and the choice of intravascular contrast medium Determine prophylactic medication If there is disagreement about the examination order, consult the referring physician Order contrast medium and prophylaxis medication in patient record Record and authorize CM safety alerts in patient record Record all severe drug (including contrast media) adverse reactions at the National Pharmacovigilance Institute LAREB
Physician responsible for the procedure	Before and during examination/procedure: Check hypersensitivity reactions and prophylactic medication Check medication and contra-indications Administration of prophylactic medication Administration of contrast medium Recording prophylactic medication and contrast administration in patient record (name, concentration, volume) Recording presence of any hypersensitivity symptoms

Treatment of acute hypersensitivity reactions to contrast media

Have a description of measures in patients with an acute hypersensitivity reaction. Appropriate patient information leaflets should be available, including the instruction about not driving a car/motorcycle for 24 hours after administration of clemastine.

Workflow and responsibilities

Responsible person	Action and responsibility
Management of department of the Physician responsible for the procedure - Cardiologist/Radiologist/Nuclear Medicine/ Radiotherapist	Drugs (minimum requirement), equipment and protocol available in every room where contrast media are administered Crash cart in every department where CM are administered Telephone number rapid response team available Organisation of regular training of personnel dealing with contrast media in the management of hypersensitivity reactions to contrast media and other emergency situations.
Physician responsible for the procedure - Cardiologist/Radiologist/Nuclear Medicine/ Radiotherapist	Check and stabilize patient Stop infusing contrast media Act according to type of reaction If applicable, call rapid response team Keep patient for at least 30 minutes after contrast agent injection in a medical environment After administration of clemastine, instruct the patient that is not possible/safe to drive a car/motorcycle for 24 hours Determine serum tryptase 1-2h after start of CM administration
Physician responsible for the procedure	Record contrast administration in patient record (name, concentration, volume) – see details below Record moderate and severe hypersensitivity reactions to contrast media in patient record (in allergy registry)
Referring physician	Take blood samples for laboratory testing (tryptase levels) in case of moderate to severe hypersensitivity reactions to contrast media Refer patient to allergy specialist in case of moderate to severe hypersensitivity reactions to contrast media AND elevated tryptase levels Record name contrast medium in consult order
Allergy specialist	Test contrast medium given to patient, which caused a hypersensitivity reaction, and alternative contrast media

Gadolinium Safety

Have a description of the safety of macrocyclic and linear gadolinium-based contrast agents (GBCA), nephrogenic systemic fibrosis (NSF), signs of gadolinium deposition, preventive measures and when to evaluate kidney function. Use always macrocyclic GBCA. For liver MRI the use of intravenous linear GBCA is allowed, because they are taken up in the liver and meet an important diagnostic need. For MR arthrography the use of intra-articular linear GBCA is also allowed.

Workflow and responsibilities

Responsible person	Action and responsibility
Referring physician	Order procedure: contrast-enhanced MRI Check laboratory results for eGFR value or determine eGFR If eGFR < 30 ml/min, be careful with gadolinium-based contrast agents
Physician responsible for the procedure - Radiologist	Check order procedure Check eGFR if available If eGFR < 30 ml/min consider indication Re-examine the need for the use of contrast medium with respect to an unenhanced study or other potential imaging modalities If there is no agreement on indication consult referring physician
Physician responsible for the procedure - Radiologist	Before and during procedure: Check eGFR Check contra-indications Administration of contrast agent Recording contrast agent administration in patient record (name, volume, concentration)

Contrast Media Extravasation

Have a description of measures in patients with extravasation of contrast media. Appropriate patient information leaflets should be available.

Workflow and responsibilities

Responsible person	Action and responsibility
Physician responsible for the procedure - Cardiologist/Radiologist/Nuclear Medicine/ Radiotherapist	Clinical assessment of CM extravasation Treatment of non-severe extravasation injury If severe injury, consider a surgical consultation (if needed a plastic surgeon) Clear instructions to the patient to be aware of alarming symptoms Record CM extravasation and treatment in patient record Record contrast extravasation as a complication in the local reporting system Notify the referring physician

Contrast injection via central catheters and ports using power injectors

Have a description of the use of various catheters and ports applicable in the hospital, where use of power injectors for contrast media is permitted.

Workflow and responsibilities

Responsible person	Action and responsibility
Management of department of the Physician responsible for the procedure - Cardiologist/Radiologist/Nuclear Medicine/ Radiotherapist	A (digital) protocol should be available in every room where contrast media are administered using power injectors

Exceptions:

Emergency patients/ procedures

In case of a major life-threatening medical condition, requiring rapid decision making including emergency imaging or intervention, determination of the eGFR and assessment of hypersensitivity reactions to contrast media can be postponed. If it is possible to wait a short time without harm to the patient, eGFR should be determined immediately. And assessment of hypersensitivity reactions should be done. When indicated, preventive measures should be taken before the administration of intravascular contrast medium.

Recording of hypersensitivity reactions to contrast media

Proper recording of any hypersensitivity reaction to CM is important, but the way of recording is not well standardized and often insufficient (Balfour, 2015; Deng, 2019).

It is mandatory that the physician responsible for the administration of the CM accurately records the following:

- The contrast agent name, dose (volume, concentration), and time of administration in the imaging report and in the electronic patient file.
- The patient symptoms (blood pressure, pulse, respiration rate, oxygen saturation, skin abnormalities), the treatment given, and the response of the patient to the treatment in the imaging report and in the electronic patient file.
- Any clinical follow-up and advice on need for future premedication in the imaging report and in the electronic patient file.
- Any results of consultation with a drug allergy specialist on future CM administration in the electronic patient file.
- All details of the reaction (blood pressure, pulse, respiration rate, oxygen saturation, skin abnormalities, tryptase levels 1 to 2 hours after start of reaction), in the hospital adverse events register ("complicatie registratie").
- The presence of a documented allergy in the electronic patient file allergy registry ("allergie registratie"). This reporting should be based on the name of contrast medium.

If the adverse reaction to a contrast medium is severe or unusual, report all details of the reaction to the National Pharmacovigilance Authority (LAREB).

Patient information leaflets

Appropriate patient information leaflets on the various radiological examinations with contrast medium should be available. The occurrence of late reactions must be mentioned in these leaflets.

And indicate what patient should do, ask for advice at the hospital or consult their general practitioner.
In addition, appropriate patient information leaflets about preventive measures in patients with a previous allergic reaction, about treatment of acute hypersensitivity reactions to contrast media, and contrast extravasation should be available.
One should consider having these leaflets available in multiple languages.

Training of Personnel

It is important that personnel that work in departments where CM are administered to patients are regularly trained in the management of hypersensitivity reactions and other emergency situations. It has been shown that high-fidelity hands-on simulation training programs are more effective than other forms of training, such as didactic lectures or computer-base training (Wang, 2011; Wang, 2014; Parsian, 2018; Ali, 2019). Checklists and visual aids can help personnel in accurate management of hypersensitivity reactions to CM (Gardner, 2018; Parsian, 2018).

Verantwoording

Laatst beoordeeld   : 24-06-2020
Laatst geautoriseerd : 24-06-2020

Voor de volledige verantwoording, evidence tabellen en eventuele aanverwante producten raadpleegt u de Richtlijnendatabase.

Referenties

Ali S, Alexander A, Lambrix M, Ramakrishna R, Yang CW. High-fidelity simulation training for the diagnosis and management of adverse contrast media reactions. AJR Am J Roentgenol 2019; 212: 2-8.

Balfour S, McCloskey J, Patel P, Xue X, Hershey B. Event documentation and transfer of care after severe contrast reactions. J Am Coll Radiol 2015; 12: 1069-1072.

Deng F, Li MD, Wong A, Kowalski LT, Lai KH, Digumarthy SR, Zhou L. Quality of documentation of contrast agent allergies in electronic health records. J Am Coll Radiol 2019; 16: 1027-1035.

Gardner JB, Rashid S, Staib L, Asch D, Cavallo J, Arango J, Kirsch J, Pahade J. Benefit of a visual aid in the management of moderate-severity contrast media reactions. AJR Am J Roentgenol 2018; 211: 717-723.

Parsian S, O'Malley RB, Hippe DS, Bush WH, Bhargava P, Chen LE, Wang CL. A checklist manifesto: effectiveness of checklist use in hands-on simulation examining competency in contrast reaction management in a randomized controlled study. AJR Am J Roentgenol 2018; 211: W1-W12.

Wang CL, Davenport MS, Chinnugounder S, Schopp JG, Kani K, Zaidi S, et al. Errors of epinephrine administration during severe allergic-like contrast reactions: lessons learned from a bi-institutional study using high-fidelity simulation testing. Abdom Imaging 2014; 39: 1127-1133.

Wang CL, Schopp JG, Petscavage JM, Paladin AM, Richardson ML, Bush WH. Prospective randomized comparison of standard didactic lecture versus high-fidelity simulation for radiology resident contrast reaction management training. AJR Am J Roentgenol 2011; 196: 1288-1295.